

WHY IBM'S NEW PS IS GOOD NEWS TO THE INDUSTRY/46
VHSIC GETS ITS ACT TOGETHER AND CHARGES INTO PHASE 2 /84

A McGRAW-HILL

PUBLICATION

SIX DOLLARS

APRIL 16, 1987


Electronics

**HOW DOD
IS CREATING
A MAJOR
NEW
BUSINESS**



INSTRUMENTS ON CARDS:

- ONLY A LACK OF STANDARDS IS HOLDING BACK THE FLOOD/57
- WAVETEK PLUGS ITS NEW LINE AS A DE FACTO STANDARD/60



Series 32000 makes VAX power more personal.

**NOW YOU CAN JOIN
HEWLETT-PACKARD, FUTURENET,
EATON, COMPUTERVISION, AND
OVER 50 OTHER COMPANIES IN
BRINGING 32-BIT POWER TO THE
LARGEST INSTALLED BASE
IN THE WORLD**

There are over 10.7 million* IBM® personal computers and compatibles in use today. That's the largest "installed base" in the world — an enormous pre-existing market that represents an enormous marketing opportunity. And National Semiconductor is leading the way for OEMs, systems integrators, VARs and VADs to take full advantage of it.

Because it's now possible to put the power of a VAX™ 11/780 into the PC environment. At a mere fraction of the cost.

PC add-in boards, based on National's Series 32000® family, allow you to immediately upgrade almost any personal computer to true 32-bit performance.

Simply by plugging a Series 32000-based board into one of the computer's standard expansion slots,** you can deliver the power and speed of a \$30,000 workstation for about \$3,000.

That means you can put high-performance CAE/CAD capabilities onto every engineer's desktop. You can distribute more computing power to more people at a lower cost in a multi-user, multitasking office environment.


* Source: Infocorp 1987

** For IBM PC/XTs, PC/ATs, and compatibles. Standard PCs need to be upgraded with a hard disk (10 Mbyte, minimum) and a larger power supply.

Series 32000 is a registered trademark of National Semiconductor Corporation.

IBM is a registered trademark of International Business Machines Corporation. VAX is a trademark of Digital

Equipment Corporation. UNIX is a trademark of AT&T. © 1987 National Semiconductor Corporation.



You can capitalize on the hot new market in desktop publishing. The opportunities are endless.

DELIVER TRUE 32-BIT POWER

Already more than 50 key systems integrators, VARs and VADs have realized the potential of this market by using PC add-in boards.

And more PC add-in board manufacturers are using the Series 32000 than all other 32-bit microprocessors combined.

That's because no other 32-bit microprocessor offers a more complete, integrated family of solutions, including coprocessors, peripherals, software, and development tools.

And, because the entire family was designed with the same highly symmetrical, orthogonal 32-bit architecture, the Series 32000 is fully software-compatible across all its CPU offerings. So your customers' software investment is completely protected even as they migrate to higher performance.

BRIDGE THE UNIX-DOS GAP

A Series 32000-based add-in board gives your customers the best of both worlds in operating systems. Since the Series 32000 was the first 32-bit microprocessor to support full demand-paged virtual UNIX™, your customers can run high-performance engineering and business applications in the most cost-efficient multiuser, multi-

tasking environment in the industry. Yet they can still run important personal-productivity tools like spreadsheets, word processing, and project managers under DOS.

PLUG INTO THE MARKET NOW

Obviously, the potential of the PC add-in market is enormous. And it's already being tapped with Series 32000-based boards being manufactured by a number of OEMs. If you're a systems integrator, VAR or VAD, contact one of these companies about their products.

Or if you're a board-level OEM yourself, follow their lead by contacting National Semiconductor about how you can design the Series 32000 into your own product.

PC ADD-IN COMPANIES USING SERIES 32000

Selected OEMs

Aeon Technologies, Vail, CO (303) 986-3599
Cybertool Systems USA, San Jose, CA (408) 263-1700
Definicon Systems, CA (818) 889-1646
DFE Electronic Data Systems, CA (415) 829-3925
Hightec EDV Systems, Saarbrücken, Germany
Matrox Electronic Systems, Quebec, (514) 685-2630
Opus Systems, Cupertino, CA (408) 446-2110
Sritek, Cleveland, OH (216) 526-9433
Zaiaz, Huntsville, AL (205) 881-2200

Selected VARs

Analog Design Tools	Lattice Logic USA
Auto-Trol Technology	Matrox Elec. Sys.
Cambridge Graphics	National Semiconductor
Computervision	Oasys
Cybertool Systems USA	Olivetti
Hightec EDV Systems	Siemens AG

Either way, the PC add-in market represents one of the most significant business opportunities in years. With over 10,000,000 prospective customers. And the Series 32000 can help you reach every one of them.

Personally.

National Semiconductor
MS 23/200
P. O. Box 58090
Santa Clara, CA 95052-8090



**National
Semiconductor**

Circle 1 on reader service card

WHAT TOP DESIGNERS SAY ABOUT T1



Leading designers say the Mitel MT8976 is the most advanced single chip T1 solution on the market. This 28-pin CMOS T1 link interface has more features than multi-chip solutions - ESF, two-frame elastic buffer, system level maintenance features and pin compatibility with European CEPT interface MT8979. It all adds up to a simple design solution in less board space at lower power levels. No one else even comes close. Call today for a complete information package on the entire Mitel family of T1 and ISDN components.

United States San Diego CA (619) 276-3421 • San Jose CA (408) 249-2111 • Oakbrook IL (312) 574-3930 • Boca Raton FL (305) 994-8500
Europe Denmark + 45 1-612566 • West Germany + 49 711-7701522 • United Kingdom South Wales + 44 291-423355
Canada 360 Legget Drive Kanata Ontario Canada K2K 1X5 (613) 592-5630

Circle 2 on reader service card



International edition

EDITOR-IN-CHIEF

Robert W. Henkel

EXECUTIVE EDITORS

Samuel Weber (technical), Arthur Erikson (news)

MANAGING EDITORS GROUP

Bernard C. Cole, Lawrence Curran, Tom Manuel,
Benjamin A. Mason, Jonah McLeod,
Howard Wolff, Jeremy Young

ART DIRECTOR

Fred Sklenar

DEPARTMENT EDITORS

CAD/CAE: Jonah McLeod (San Mateo)

Communications: Tom Manuel

Components: Samuel Weber

Computers & Peripherals: Tom Manuel

Jonah McLeod (San Mateo)

Lawrence Curran (Boston)

Industrial & Consumer: Wesley R. Iversen
(Chicago)

Military/Aerospace: Ron Schneiderman

Packaging & Production: Jerry Lyman

Semiconductors: Bernard C. Cole (San Mateo)

Software & Microprocessors:

Alexander Wolfe

Test Instruments: George Sideris (San Mateo)

NEWS DEPARTMENT

Features Editor: Jeremy Young

Front of the Book: Howard Wolff

New Products: Jack Shandle

EDITORIAL PRODUCTION & COPY DESK

Benjamin A. Mason (Director)

Production

Charles D. Ciatto (Mgr.), Kathy O'Neill

Copy Editors

Larry King (Chief), George Ellis,

Nancy J. Erickson

ART

Sachiko Soskin (Associate Director)

NEWS BUREAUS

Boston: Lawrence Curran (Mgr.), Paul Angiolillo

Chicago: Wesley R. Iversen (Mgr.)

Dallas: J. Robert Lineback (Mgr.)

Los Angeles: Larry Waller (Mgr.), Ellie Aguilar

New York: Tobias Naegele (Mgr.)

San Mateo: Clifford Barney (Mgr.)

Frankfurt: John Gosch (Mgr.)

London: Steve Rogerson

Paris

Tokyo: Charles L. Cohen (Mgr.),

Ayako Hayashihara

EDITORIAL ADMINISTRATION

Laura Aspery (Administrative Assistant),

Lisa Costenbader, Ina Gruber

PUBLISHER

Laurence Altman

Director of Operations: Thomas E. Vachon


Director of Circulation: Daniel McLaughlin

Production Director: Thomas Egan

Manager of Sales Administration:
Evelyn Schmidt

Promotion Associate: Diane Breder

Experience: Cervantes called it "the universal mother of sciences." No matter what the field, there is no substitute for it. So when we at *Electronics* reorganized our news-gathering operation on the East Coast to expand and sharpen coverage of the region's technology, we decided to build on experience. The next step was a natural one: we turned to Larry Curran, a seasoned journalist who has been writing about electronics in all its phases



CURRAN: A voice of experience returns to *Electronics*.

and covering the computer and communications industries for more than 25 years.

From his Boston base, Larry will cover a territory stretching from New England to the southeastern technology outposts in Georgia, North Carolina, and Florida. That territory includes some of the places where much of the most advanced technology that will take the electronics industry into the next century is being developed. For example, there is Route 128 around Boston, Research Triangle Park in North Carolina, the Atlanta area, and the east coast of Florida from Melbourne in the north to Boca Raton and Miami in the south.

Larry has the seasoning that makes him particularly well suited for the job. He has spent a dozen of his 25 years in the business in various capacities on *Electronics*, working on both coasts. Included are stints as bureau chief in Los Angeles and Boston and news editor in New York.

More recently, he served as editor-in-chief of a trio of major computer magazines: *Byte*, *Mini-Micro Systems*, and

Systems & Software. And back in the heady days of massive expenditures on space and missile programs, when so much of the foundation for the solid-state era was being built by the Pentagon, he was a Washington-based editor on *Missiles & Rockets* magazine before coming to *Electronics* for his first tour of duty.

A native of Pittsburgh, Larry received his bachelor's degree in English from Washington & Jefferson College near his hometown.

He returns to *Electronics* after being away for about eight years. During that time he was involved not only with editing, but also with public relations. To take the maximum advantage of his expertise and years in the business, we have created a new job for him as eastern regional editor, with a particular emphasis on computer and communications technology. In addition to having responsibility for technology coverage, Larry will become a member of the magazine's Managing Editors Group.

We are glad to have him back. As for Larry, "It feels great to be back. My previous 12-year association with *Electronics* is a very special part of my career. I learned a great deal about technical journalism in the early years, and I think my contributions from Los Angeles and Boston were important.

"It's especially good to be part of an editorial team that still practices good journalism. In almost two years in public relations, I found precious few publications that prided themselves for journalistic enterprise and thorough reporting the way *Electronics* does."

Laurence Altman

April 16, 1987 Volume 60, Number 8
138,582 copies of this issue printed

Electronics (ISSN 0883-4989). Published biweekly by McGraw-Hill Inc. Publication office: 1221 Avenue of the Americas, N.Y., N.Y. 10020; second class postage paid at New York, New York and additional mailing offices. Postage paid at Montreal, P.Q. Registration Number 9024.

Executive, editorial, circulation, and advertising addresses: *Electronics*, McGraw-Hill Building, 1221 Avenue of the Americas, New York, N.Y. 10020. Telephone (212) 512-2000. Teletype 12-7960 TWX 710-581-4879. Cable address: MCGRAW HILL NEW YORK.

Officers of McGraw-Hill Information Systems Company: President: Richard B. Miller; Executive Vice Presidents: Frederick P. Jannot, Construction Information Group; Russell C. White, Computers and Communications Information Group; J. Thomas Ryan, Marketing and International. Senior Vice Presidents-Publishers: Laurence Altman, *Electronics*; Harry L. Brown, *BYTE*; David J. McGrath, *Engineering News-Record*. Group Vice President: Peter B. McCuen, *Communications Information*. Vice Presidents: Robert D. Daleo, Controller; Fred O. Jensen, Planning and Development; Michael J. Koeller, Human Resources; Talat M. Sadig, Systems Planning and Technology.

Officers of McGraw-Hill Inc.: Harold W. McGraw Jr., Chairman; Joseph L. Dionne, President and Chief Executive Officer; Robert N. Landes, Executive Vice President and Secretary; Walter D. Serwatka, Executive Vice President and Chief Financial Officer; Shel F. Asen, Senior Vice President, Manufacturing; Robert J. Bahash, Senior Vice President, Finance and Manufacturing; Ralph R. Schulz, Senior Vice President, Editorial; George R. Elsinger, Vice President, Circulation; Ralph J. Webb, Vice President and Treasurer.

Title registered in U.S. Patent Office; Copyright 1987 by McGraw-Hill Inc. All rights reserved. The contents of this publication may not be reproduced in whole or in part without the consent of copyright owner.


Where necessary, permission is granted by the copyright owner for libraries and others registered with the Copyright Clearance Center (CCC), 21 Congress Street, Salem, Mass. 01970, to photocopy any article herein for the base fee of \$0.50 per copy of the article plus \$0.25 per page. Payment should be sent directly to the CCC. Copying done for other than personal or internal reference use without the express permission of McGraw-Hill is prohibited. Requests for special permission or bulk orders should be addressed to the publisher. ISSN 0883-4989/87 \$0.50+.25.

Editorial department phones: Administration (212) 512-2645, News and New Products (212) 512-2685, Technology (212) 512-2666. Bureaus: Boston (617) 262-1160, Chicago (312) 751-3811, Dallas (214) 458-2400, Los Angeles (213) 480-5234, New York (212) 512-3322, San Francisco/San Mateo (415) 349-4100, Washington (202) 463-1650, Frankfurt 72-5566, London 493-1451, Paris 42-89-03-80, Tokyo 581-9816. **Business departments:** (212) 512-6435 (Business departments follow the Advertisers' Index).

Electronics

NEWS	INSIDE TECHNOLOGY
Newsletters Electronics, 25 • GE/RCA fires another shot in the battle of the pinouts • Sun clips the price of its low-end work station International, 27 • NEC asks court to block sales of Seiko Epson PC • TI Japan beefs up bipolar capacity and signs on ASIC partners • Hitachi takes aim at networks with high-bit-rate lasers	COVER: How the DOD is creating a major new business, 57 All three branches of the military are pushing major instrument-on-a-card programs, and only a lack of standards is holding back the flood Card-based ATE system could set a standard, 60 Wavetek's 680 instrument-on-a-card system replaces a rack of instruments with eight plug-in modules for ATE applications This bipolar process gives dynamic range and density, 69 Fairchild combines highly doped buried layers with thin epitaxial layers to get practical linear circuits plus densities needed for digital LSI Prolog compiler is key to IBM-Japan AI research, 72 IBM Japan is developing an optimized Prolog compiler that runs on an enhanced IBM RT PC with a new operating system Japan's NTT has world's fastest Lisp processor, 73 The ELIS desktop computer can execute 1 million basic Lisp instructions per second, six times better than existing Lisp machines Japan's ICOT triples speed of its inference machine, 74 The PSI-II uses revised software and 8,000-gate CMOS arrays to execute 100,000 logical inferences per second Technology Update, 75 Sierra's EEPROM cell moves into designs... Philips scores with its low-cost scopes SPECIAL REPORT: A major facelift for strategic radar nets, 78 Recent advances in solid-state phased arrays, power devices, pulse compression, and signal processing are reshaping U. S. defenses SPECIAL REPORT: VHIC finally builds a head of steam, 84 Phase 1 got off to a slow start, but the controversial Pentagon R&D program has scored some notable successes and is now rapidly moving the advanced chips into military hardware VHIC moves headlong into the submicron stage, 91 Building on a successful Phase 1, Phase 2 aims at 0.5- μ m geometries and chip densities of more than 500,000 devices
Optical memories, 33 Magneto-optic memories begin to look like a good bet: Nikon method erases and writes in one pass Memories, 34 Design tricks speed up INMOS SRAM Radar, 34 A billion-dollar program for the Advanced Tactical Fighter excites the industry Artificial intelligence, 35 Processor links number crunching and symbolics Integrated circuits, 36 • Faster gallium arsenide chip - nears production • Bell Labs is setting up a GaAs MOD FET pilot line Consumer, 39 FMX is the sound of a new FM stereo market Production, 42 Automating a PC-board hole-masking process Solar cells, 42 At last, a cheap, efficient solar cell	PROBING THE NEWS Why IBM's new PS line is good news for the industry, 46 It doesn't close the personal computer market; it sets a strong new graphics standard; and it opens up new business Under Thomson's wing, Mostek is beginning to fly, 48 Having gotten out of the commercial DRAM business, Mostek is now growing twice as fast as U. S. market; it aims to help Thomson hit the Top 10 list soon

HOW DOD IS CREATING A MAJOR NEW BUSINESS



PAGE 57

NEW PRODUCTS

Newsletter, 27

- NEC's 32-bit microprocessor outspeeds rivals at 6.6 mips
- IC integrates peripheral buffers and SCSI interface to save board space
- Wang adds low-end Tempest minis

Semiconductors, 98

- Applied Micro Circuits scales down its bipolar logic arrays to 2 μm to achieve 25% gain in speed
- Customized diode stacks from Philips handle voltages up to 20 kV and feature 30-ns reverse-recovery time
- Waferscale Integration's 16-by-16-bit multiplier-accumulator boasts a 30-ns cycle time

Computers & Peripherals, 100

- Edge Computer's dual-processor 1200 runs at a peak rate of 11 mips, thanks to a 32-Kbyte instruction cache and equal bus loading
- Changing documentation records takes less time and effort with Context's new Change Control software

Communications, 102

- Systech's communications system mixes fiber-optic and coaxial cable to transmit up to 4,000 ft

Military/Aerospace Newsletter, 95

- Sematech planning is running ahead of schedule
- DOD picks candidate projects for Conventional Defense Initiative
- Low-frequency radar, fiber optics, and antisub warfare are Navy priorities for near-term R&D

DEPARTMENTS

Publisher's letter, 3

A seasoned electronics journalist, Larry Curran, rejoins *Electronics*

FYI, 8

Another sign of an upturn: "I have just attended three product allocation meetings; we see increased demand across the customer spectrum," says Motorola's Chuck Thompson

Letters, 12

People, 16

Deteriorating trade relations make the job harder for Visual Information Technologies' Brightman

Electronics Week, 110

- China market gets good review
- GE expects VHSIC certification for its 1.25- μm fab line
- Monolithic Memories settles with Altera on its suit over programmable logic
- Now showing: The three Amigas


INTERNATIONAL

International Week, 54A

- West Germany: The electrical components market was flat in 1986 but is expected to recover
- Hong Kong: Toshiba is opening an LSI design center in Hong Kong
- Japan: IBM Japan slips to third place among computer makers
- West Germany: Allied Corp. and Vacuumschmelze have signed an amorphous metals pact
- West Germany: Siemens expects its sales in the U. S. to rise
- UK: Two satellites to bring UK television to Europe

New Products, 54B

- Integrated Photomatrix squeezes a photodiode and op amp into an 8-mm package to handle electro-magnetically noisy environments
- Reflectometer from Cossor Electronics works with single-mode optical fibers



Advanced Micro Devices • Bruxelles (32-2) 771 99 93 • Hannover area (49-5143) 50 55
Hong Kong (852-3) 695377 • London area (44-4862) 22121 • Manchester area (44-925) 828008
Milano (39-2) 3533241 • München (49-89) 4114 0 • Osaka (06-243) 3250 • Paris (33-1) 45600055
Stockholm (46-8) 733 03 50 • Stuttgart (49-711) 62 33 77 • Tokyo (81-3) 345 8241
Latin America, Fort Lauderdale, Florida/U.S.A. Tel: (305) 484-8600 Tlx: (510) 955-4261 amd flt

© Advanced Micro Devices, Inc. 1987


Don't let reality stop you.

Grab a pad and get to work on tomorrow.

That's how we designed the Am95C60 Quad Pixel Dataflow Manager, a CMOS graphics coprocessor that proves "high performance graphics" is no longer a contradiction in terms.

With a polyline draw speed of 110,000 vectors per second, a BITBLT transfer of 55ns per pixel, and a polygon fill of 20ns per pixel, QPDM can change a screen faster than the speed of thought. (It can redraw a 1K X 1K screen in 0.2 seconds.)

Besides being powerful, this animal is highly trained. The instruction set for full graphics and text primitives is already on the chip. There aren't any extra programming hurdles to slow it down.



Each QPDM addresses four planes. It's cascadable, too. With no degradation in performance. And it can deliver all the color you need.

Get ahead of the market by designing it in now. Find out more about QPDM and QPDM seminars. Just call or write the sales agent near you. Then get to work on designing the future.

Advanced Micro Devices

For more information, contact the sales agent nearest you or write the word "QPDM" on your letterhead and mail to Advanced Micro Devices, Mail Operations, P.O. Box 4, Westbury-on-Trym, Bristol BS9 3DS, United Kingdom.

Circle 105 on reader service card

Real-time Digital Filter and FIR Filter Development System for PC Workstations

with the
DFS001 - PC
and
FIRCALC-PC Software

DFS001-PC:

- PC-bus board with:
- Programmable digital FIR filter
- 14/16 bit A/D and D/A
- 50 kHz sample rate
- 256K word data RAM
- Analog, 16-bit digital and bus data ports

FIRCALC-PC:

- Filter design and simulation software
- On-screen filter response plots
- Menu driven board interface
- Create and download filter coefficients

An Integrated Package

**AVAILABLE
NOW!**

CALMOS[®]

Calmos Systems Inc.


USA: Call 1-800-267-7231 Tlx: 053-4501

Europe: UK (0272) 277332 Tlx: 449731

Canada: (613) 836-1014 Tlx: 053-4501

FYI

*Motorola's Chuck Thompson:
'I have just attended three product
allocation meetings; we see increased
demand across the customer spectrum'*



You could almost feel it in the air; it wasn't just spring in New York, it was the upbeat mood at Electro/87. After two years of what Charles E. Thompson, director of world marketing at Motorola Semiconductor, described as "market paralysis," it felt good to talk about an upswing. Said Thompson: "I have just attended three product-allocation meetings." The products, he added, were "certain new discretes and advanced microprocessors."

He was quick to note that this spring's optimistic outlook was different than the one that seemed to show up a year ago. This time around the upturn is real because "real demand is up," Thompson said. "A year ago, it was triggered by distributors who were looking for their business to increase," he added. This time the increase is "OEM driven." He figures that a third of it came from real demand, a third from anticipating the new IBM personal computers, and a third from people replenishing their inventories.


Motorola Semiconductor, which last year racked up the best record among the U.S. majors, is seeing "increased demand across the customer spectrum," Thompson noted, adding he's "particularly pleased" with major computer makers. As yet, Motorola hasn't revised upward its 1987 forecasts, but Thompson did say it was "bringing on stream some front ends that we had shut down during the downturn."

If the nation's economy holds up, Jack Beedle, who retains the title as the "most bearish of the semiconductor market forecasters," figures it's entirely possible that U.S. sales could increase by more than 10% this year. Not great, but much better than what he had previously forecast. But Beedle, a keen-eyed scorekeeper in the semiconductor business, counted up first-quarter U.S. sales in his *IN-STAT Electronics Report*, and found them "kinda blah." He says sales look to be about \$2.15 billion, about the same as a not-so-good 1986 fourth quarter. The good news, however, is that these sales are 17% ahead of the first quarter last year and, like Motorola's Thompson, Beedle is becoming increasingly bullish. He says incoming orders seem to support second-quarter sales going up 10% over the previous year's. Beedle still worries, though, that the bulk of these increased bookings are primarily for inventory replenishment and could evaporate, much as they did a year ago. Nevertheless, an increasing number of experts are seeing 1987 Thompson's way. **ROBERT W. HENKEL**

VSP™ MEANS FASTER SIGNAL PROCESSING.

DSP just doesn't get any faster than Zoran's Vector Signal Processor (VSP). The world's most powerful DSP processor.

Capable of performing a 1024-point complex FFT in just 2.6 ms. Using only a kernel of three simple instructions. Plus you can parallel VSPs to perform an even faster FFT in just 925 μ s.



Zoran's unique architecture lets you parallel multiple devices on a single bus to achieve even faster signal processing.

The secret's in our proprietary architecture, which is optimized for faster, more efficient execution of embedded algorithms.

In fact, the VSP computes a 63-tap FIR filter in real time with an input sample rate of 250kHz.

Faster programming with our high-level instruction set. We slashed programming time with an embedded high-level instruction

set that eliminates the need to write lines and lines of code.

So you can concentrate on your end application, instead of getting bogged down in the details of software implementation.

Take spectrum analysis, for example. You can do a complete 256-point power spectrum in real time with an input sample rate of 340kHz. Using only 29 instructions.

Faster system design with our tools and support. Speed's not enough if you can't use it in a hurry. So we provide you with all the tools and support you need to shorten your development cycle.


Like comprehensive VAX™ and PC-based hardware and software tools. So you can completely develop and simulate any DSP application, from concept to hardware.

All the way from simple spectrum analysis programs to sophisticated 2D image transforms. And even to image compression, where you can do more than 1000 16 x 16 cosine transforms per second.

All of which explains why Zoran's VSP and Digital Filter Processor (DFP) product families provide the fastest, easiest solutions for computation-intensive applications.

Best of all, we're shipping VSP and DFP products now, instead of simply announcing them. Which means you don't have to wait to get the jump on your competition.

Think fast and get a free Zoran databook. Call 1-800-556-1234, ext. 99 (outside CA) or 1-800-441-2345, ext. 99 (in CA). Or write Zoran Corporation, Dept. MC-4, 3450 Central Expressway, Santa Clara, CA 95051. We'll get it out to you fast.



YEARS FROM NOW, WILL YOUR MILITARY SUPPLIER BE JUST A BAD MEMORY?

It's no secret—there's a lot of uncertainty in the marketplace. You never know if the company you're dealing with today will still be around to service you tomorrow. And that's a chance you can't take—especially in the military market.

With INMOS, you're not taking any chances. We have a seven-year history of supporting all major military defense programs with static and dynamic RAMs. Our fabrication facilities are fully compliant with MIL-STD-883C; with military burn-in, performance testing and quality assurance conducted in Colorado Springs.

We have your future in mind with our new CMOS military SRAMs (with performance to 35ns over the full military temperature range) and military low power battery backup CMOS SRAM products. And we're going to keep on producing and servicing innovative military products year after year.

For military products you can depend on, count on INMOS—the beginning of a very good memory.

16K SRAMs		
Device	Process	Access Times
IMS1400M (x1)	NMOS	45, 55, 70ns
IMS1420M (x4)	NMOS	45, 55, 70ns
IMS1403M (x1)*	CMOS	35, 45, 55ns
IMS1423M (x4)	CMOS	35, 45, 55ns

64K CMOS SRAMs	
Device	Access Times
IMS1600M (x1)*	45, 55, 70ns
IMS1620M (x4)*	45, 55, 70ns
IMS1624M (OE, x4)*	45, 55, 70ns
IMS1630M (x8)*	45, 55, 70ns

*Also available as Low Power Battery Backup CMOS SRAMs with I_{dr} of 10µA (typical I_{cc} at 2V at 25° centigrade). inmos,  and IMS are trademarks of the INMOS Group of Companies.

MIL-STD-883C RAMs



INMOS, Colorado Springs, Colorado, Tel. (303) 630-4000;
Bristol, England, Tel. (0454) 616616;
Paris, France, Tel. (1) 46.87.22.01;
Munich, Germany, Tel. (089) 319 10 28;
Tokyo, Japan, Tel. 03-505-2840.

Circle 11 on reader service card


Does your analog simulator analyze:

- production yield?
- sensitivity?
- worst case?

Good circuit simulators, will analyze your "best case" design... but what about the real world?

Use MicroSim's **PSpice**. We offer a fully integrated, **Monte Carlo Analysis** package which will analyze both discrete (printed circuit) and IC designs using statistical techniques.

Predict yield by simulating the effect of component tolerances, and the combined effect of variations. Identify performance sensitivity to individual components, and the "worst case" combinations. The Monte Carlo Analysis is fully integrated for error-free setup and use, faster simulation, and collated results.



Our **Probe** graphics option shows the performance variations of your design, quickly and accurately. Also, PSpice gives you more than just voltages (for example, *group delay* for filter design is included).

Monte Carlo Analysis is just one of the options available for PSpice, the world's most widely used analog circuit simulator.

MicroSim's PSpice software runs on IBM-PC™ compatible and DEC VAX™ computers.



MicroSim Corporation
23175 La Cadena Drive
Laguna Hills, CA 92653
(714) 770-3022 • (800) 826-8603

Call today for further information and a free evaluation copy of our software.

IBM-PC is a trademark of International Business Machines Corp.
VAX is a trademark of Digital Equipment Corporation.

LETTERS

It's not materials...

To the editor: I am writing in reference to the February 19, 1987, article on the Josephson-junction-based Picosecond Signal Processor recently announced by Hypres Inc. This instrument represents an important achievement in the area of superconducting electronics. However, the article [p. 49], along with the accompanying one on superconductor research and development [p. 54], incorrectly emphasized difficulties IBM Corp. is supposed to have had with materials.

As a member of the IBM Josephson program, I would like to try to correct this error, which has contributed to general misunderstanding of the problems encountered in trying to fabricate large-scale Josephson circuits. The opinions expressed here are my own and do not represent an official position of IBM.

The Hypres article contains the statement that Hypres can "produce reliable, repeatable Josephson junction circuits—something that IBM, which used lead and lead alloys, was never able to do, according to Sadeg M. Faris, Hypres's president and a former IBM staff member." The accompanying superconducting R&D article refers to "the kinds of difficulties IBM was having with materials."

The IBM Josephson effort after 1981 was based on niobium-edge-junction technology, which uses niobium base electrodes and lead-alloy counterelectrodes for the junctions—and not on lead and lead-alloy devices. The use of niobium for the base electrode eliminates the problem of poor thermal cyclability, which limited the usefulness of lead-alloy-based junctions. Niobium-edge-junction technology was demonstrated to yield reproducible, reliable circuits, as first described at a Josephson workshop in August 1983.

Josephson technology has advanced significantly since IBM dropped its program in 1983. However, it was difficulties inherent in the use of Josephson devices as digital circuit elements, not materials problems, that caused IBM to abandon the technology for large-circuit-count applications. We continue to apply niobium-edge-junction technology internally for scientific and instrumentation applications, and we share the general enthusiasm for such small-scale applications that was expressed in your article.

Alan Kleinsasser
IBM T. J. Watson Research Center
Yorktown Heights, N. Y.

...Yes it is

Sadeg M. Faris, the president and chief executive officer of Hypres Inc., responds:

Producing reliable, repeatable Josephson junction circuits is something that IBM, which used lead and lead alloys,

was never able to do. Researchers may not appreciate what it means to have a manufacturing line producing chips on a daily basis with run-to-run repeatability, a stage that IBM never approached. For instance, when I was at IBM, it took us four to five weeks to complete one fabrication run. At Hypres, a fabrication run takes four days and we come to within a few percent of a nominal target current density.

Also, IBM stuck to its guns to the end in using lead as a counterelectrode. The edge-junction Squids [superconducting quantum interference devices] failed, and the failure was attributed to the lead counterelectrode.

There was no question that IBM had a materials problem. For example, if it wasn't for the niobium oxide and its high capacitance, IBM would not be going to the edge junction to make the area very small. The edge junctions can excite very bad resonances that ultimately affect the operating margins.

Hypres is managing to make all-niobium junctions repeatedly and reproducibly without having the capacitance problem because we use a different barrier.

Who's on first?

To the editor: We must take issue with the comments made about market share in Japan for disk-drive testers [Electronics, Feb. 19, 1987, p. 77]. There, it is reported that "By its own estimate, Toyo [Corp. of Japan] has 50% of the Japanese market for disk-drive test equipment." My company, Applied Circuit Technology Inc., is the world's largest supplier of disk-drive test equipment—as market researcher Peripheral Research confirmed in your article. Two years ago, ACT entered the Japanese market via an exclusive distribution, support, and service agreement with Mitsui & Co., Japan's second largest trading firm. At the same time, we established the basis for our joint-venture corporation, and I am pleased to report we are on target in establishing our subsidiary.

While Toyo has been in the market for some time, it is clear that ACT, given its product range and customer base, has extended its superiority to Japan.

José C. Elaydo
President
Applied Circuit Technology Inc.
Anaheim, Calif.


Call Mizar for MDX

Correction: Mizar Digital Systems Inc. of St. Paul, Minn., is now the manufacturer of the MDX line of STD-bus board computers [Electronics, March 19, 1987, p. 90]. It bought the line from Thomson Components-Mostek.

W424	W424	W424	Polling Capability/Real Time Clock						
4040	105D	105B	Enclosed in Metal Housing						
4X40	1X5D	1X5B	NEMA 12 or 4X Stainless Steel Bezel						
			115/230 Volt Power Supply Included						
			12 Volt Power Supply Required						
			Four Line x 24 Character Readout						
			Single Line Readout (24 Characters)						
			64 Canned Messages in EPROM						
			256 Canned Messages in CMOS RAM						
			1/2" Characters Utilizing Gas Plasma Technology						
			RS232/RS422 and 20mA Outputs						
			Full and Half Duplex Communication						
			Accepts RS422 Serial ASCII Input						
			Accepts RS232 & 20mA Serial ASCII Input						
			PC Software Available for Message Programming						
			Accepts Parallel ASCII Input (TTL Logic Levels)						
			Recall Message with +5 to +30VDC Logic						
W424	W424	W424							
4040	105D	105B							
4X40	1X5D	1X5B							

CHERRY 

3601 Sunset Avenue, Waukegan, IL 60087 • (312) 360-3500
Switches • Automotive Devices • Electronic Components • Displays • Printed Circuit Boards • ICs • Keyboards



Here's the speed you

64 bit

CY7C189
16x4 15ns 90mA
CY7C190
16x4 15ns 90mA
CY27LSO3M
16x4 65ns 38mA

CY7C122
256x4 15ns 90mA
CY7C123*
256x4 7ns 120mA
CY93422
256x4 45ns 120mA
CY93L422
256x4 60ns 80mA


CY7C147
4Kx1 25ns 90/15mA
CY7C148
1Kx4 25ns 90/15mA
CY7C149
1Kx4 25ns 90mA
CY7C150
1Kx4 15ns 90mA

CY7C130*
dual port
1Kx8 35ns 120/30mA
CY7C140*
dual port
1Kx8 35ns 120/30mA

CY7C128
2Kx8 25ns 120/20mA 300 mil
CY6116
2Kx8 35ns 130/20mA
CY7C132*
dual port
2Kx8 35ns 120/30mA
CY7C142*
dual port
2Kx8 35ns 120/30mA
CY7C167
16Kx1 25ns 45/60mA
CY7C168
4Kx4 25ns 70/90mA
CY7C169
4Kx4 25ns 70/90mA
CY7C170
4Kx4 25ns 90mA
CY7C171
4Kx4 25ns 70/90mA
CY7C172
4Kx4 25ns 70/90mA

*Available 2nd quarter 1987

need.



64K

CY7C185
8Kx8 35ns 100/20mA 300 mil
CY7C186
8Kx8 35ns 100/20mA
CY7C161
16Kx4 25ns 70/20mA
CY7C162
16Kx4 25ns 70/20mA
CY7C164
16Kx4 25ns 70/20mA
CY7C166
16Kx4 25ns 70/20mA
CY7C187
64Kx1 25ns 70/20mA



CYPRESS
SEMICONDUCTOR

CMOS SRAM

If your job is building faster systems, here are a few compelling reasons to think Cypress Semiconductor when you think fast SRAM.

As the specs on the left indicate, we have the speed you need. In cool, low power CMOS.

And it's all available in the packaging you need. From CERDIP to plastic to surface mount to flat packs. Military versions? Yes *sir*.

A word on speed. And on choice.

We offer each of our SRAMs in a variety of configurations. So you only pay for the speed, size, or organization you need.

And if you need the highest speeds available, our customers tell us we are leading the way in delivering production quantities of the fastest, 25ns parts.

That benefit is a direct result of our success in producing the most advanced VLSI technology available.

As a result, when you design in our highest performance SRAM specs, you are designing in *deliverable* parts.

When you're in production, the ability to choose the speed you need and the ability to rely on production quantities become extremely important. Narrow-line SRAM suppliers don't always offer you these key benefits.

How to simplify your SRAM selection:

Beyond performance specs, look for a supplier in control of the fab process, for dependable delivery of the most demanding, high performance parts.

Look for a full line SRAM supplier, so you spend less time qualifying, and more time engineering.

That is our fast SRAM story.

We have an equally beneficial story to tell you when it comes to our other three product families:

High performance PLD.
High performance PROM.
High performance LOGIC.

It's all in our new 1987 databook and our databook is yours for a phone call.

DATABOOK HOTLINE

1-800-952-6300, Ask for Dept C80

1-800-423-4440 (In CA), Ask for Dept C80


(32) 2-672-2220 (Europe)

(416) 475-3922 (In Canada)

New SRAM Highlights:

- **64K SRAM:** A variety of configurations and speeds, *including* the ultra hard to find 25ns operating speeds.
- **1K SRAM:** Scheduled for Q2, 1987, this 7 nanosecond SRAM will be the world's fastest TTL-compatible SRAM.





New CMOS 1K serial EEPROMs use 3 mA active, 100 μ A standby.

Samples of Catalyst Semiconductor's two new EEPROMs are available for immediate delivery from stock. Quantity deliveries are available 30 days ARO.

The CAT93C46 unit is pin-for-pin compatible with National Semiconductor's NMOS part #NMC 9346 and the CAT59C11 with General Instrument's part #ER5911. Pricing is very competitive.

Both Feature:

- ☐ Reliable CMOS floating gate technology with a power drain of 3 mA active and 100 μ A standby.
- ☐ Single 5-volt supply.
- ☐ Eight pin DIP and Small Outline Packages.
- ☐ 64 $\times$ 16 or 128 $\times$ 8 user selectable serial memory.
- ☐ Word and chip erasability.
- ☐ Self timed programming cycle.

They each operate over a temperature range of 0°C to 70°C, offer 10,000 erase/write cycles, ten year data retention, and power-on/off data protection.

Both provide a 10 ms programming cycle.

Write or Call for our Serious, No Fooling Data Pack.

Please address Catalyst Semiconductor, 4051 Burton Drive, Santa Clara, CA 95054. Phone (408) 980-9144. FAX (408) 980-8209. TWX 510-601-7631.

In Europe, contact Catalyst (U.K.): 14 Larkwood Rise, St. Albans, Herts, England AL4 9JU. Phone 0727-38183. FAX 0727-53355.



CATALYST
SEMICONDUCTOR, INC.

PEOPLE

TRADE RELATIONS MAKE BRIGHTMAN'S JOB HARDER

PLANO, TEXAS

After the Reagan Administration slapped tariff sanctions on a list of Japanese electronic products, Thomas A. Brightman was among those anxiously waiting to see what would happen next in the uncertain trade relations between the U.S. and Japan. Brightman, the vice president of operations at Visual Information Technologies Inc., was sweating out trade relations because he has to map out a global strategy of product assembly and chip procurements for the image-processing startup.

The Plano company's aim is to eventually sell powerful image-processing computers for less than \$5,000. Visual Information Technologies is already on the right path with custom chips and a highly parallel architecture, known as the VITec Image Computer [*Electronics*, Feb. 19, 1987, p. 62], says Brightman.

Brightman believes the timing is right for the proper strategy in low-cost, powerful image computers. "Today, the mathematics are well understood, and the key enabling technologies are getting in place. Applications are forming up around the new technology," he notes.

Now what's needed, Brightman adds, is an international manufacturing and procurement strategy to drive \$100,000 image processing below \$5,000 and put it into personal computers. But how and where to build? "If I wanted to be some kind of wise guy I would say, 'Ask Ronald Reagan what he is going to do next,' because [sanctions are] creating a very turbulent situation," notes Brightman,

who once headed procurement and planning for Atari Inc.'s plant in Taiwan.

The 32-year-old Brightman, who holds a BSEE from Yale University, believes volume-selling image computer systems can be assembled in Japan, Germany, or along the Texas-Mexico border. But higher tariffs on Japanese chips could change that lineup. "Is the U.S. going to create a situation where chips are selling in Japan for one third of what they cost elsewhere?" Brightman asks. "If so, then I cannot very well go to Mexico. It is a difficult situation, and we will have to maintain a flexible posture."

FROM SPEECH TO IMAGES. Brightman, a native of Syracuse, N. Y., started his career in 1976, developing microcomputer-based controls for home appliances at P. R. Mallory & Co. in Burlington, Mass. A year later, he joined the sales force of Texas Instruments Inc. in the Boston area. He eventually became a product-engineering manager for synthetic-speech products.

In 1982, Brightman went to work for a startup operation formed by Commodore Business Machines Inc. in Dallas to develop speech peripherals for its line of home computers. Two years later, a change in Commodore management shut down the operation.

Brightman then joined a team of a dozen managers formed in 1984 by Jack Tramiel, who left his post as president of Commodore and acquired Atari. For a year Brightman was vice president of engineering, and in 1985 he got his first taste of international dealings in the

electronics trade as head of procurement and planning.

"Jack Tramiel is one of the great teachers in how to buy," Brightman says. "One of his mottoes is you cannot ever count on selling, but you know for sure that if you can buy something for a dollar today, you will be able to buy it for 70 cents a year from now."

At his new company, Brightman thinks he can bring "an international experience, certainly from the Asian basin. I hope I can contribute here with the ability to strike a few strong strategic alliances with some big players." And the first step will be to settle on a good location—or locations—for manufacturing.

—J. Robert Lineback



BRIGHTMAN. Divining a global manufacturing strategy in a period of flux.

Time is Money.

Time lost is profit lost.


- Slipped development schedules.
- Lengthy prototype cycles.
- Product/process obsolescence.
- Late market entry.
- Competitors as 2nd sources.

Orbit lets you recover lost time.

Guaranteed 10 or 15 day delivery to recover slipped schedules.

Advanced processes include CMOS, CCD, Analog CMOS, and Radiation Tolerant. And because Orbit is strictly a foundry, we are a guaranteed noncompetitive second source.


For more information on how Orbit's services can help you recover lost time, call Gary Kennedy, President. Before it gets any later. 1230 Bordeaux Drive, Sunnyvale, CA 94089. TWX 910-339-9307, FAX (408) 747-1263. Or call (800) 331-4617, in California (800) 647-0222, (408) 744-1800.



A subsidiary of Orbit Instrument Corporation.

What others promise, we guarantee.

NEW FROM SILICON SYSTEMS— A SERVO CHIP SET FOR HIGH PERFORMANCE HDD's!



Silicon Systems now introduces the SSI Servo Chip Set. It is a 3-chip servo set for precise head positioning in the new high-performance hard disk drives. This is just the latest development in the company's program for the full integration of disk drive electronics.

The new set consists of the SSI 567 Servo Demodulator, which provides servo demodulation for dedicated-surface servo systems; the SSI 568 Servo Controller, which provides servo control; and the SSI 569 Servo Motor

Driver, which is a voice coil servo motor predriver that is compatible with complementary power FETS. The chip set includes all the functional building blocks required in the servo channel, and is easily controlled via the microprocessor interface.

This chip set will break down major barriers to entry into the development of high performance hard disk drives. With its high level of integration, it provides superior performance and features for lower power, reduced board

space, and lower cost.

For more information on the new SSI Servo Chip Set and the other exciting product families in the complete ESDI and SCSI Chip Sets for HDD and FDD disk drive electronics, contact Silicon Systems today.

Silicon Systems, 14351 Myford Road, Tustin, CA 92680. Phone: (714) 731-7110, Ext. 575.

silicon systems™
INNOVATORS IN INTEGRATION

ELECTRONICS NEWSLETTER

AT&T AIMS TO MATCH SPEED OF TI'S NEXT DSP CHIP

Bidding to win the next round in digital signal processing, AT&T Co. is promising a new CMOS 32-bit design, which equals the more than 33 million floating-point operations/s slated for market leader Texas Instruments Inc.'s latest DSP. Like the Dallas company's future TMS320C30 [*Electronics*, March 19, 1987, p. 21], AT&T's DSP32-C is slated for early 1988 delivery. The competing designs are targeted to perform 60-ns single-cycle executions, and both have a floating-point math unit on board. AT&T is starting off with an existing n-MOS 32-bit floating-point DSP, which executes 12.5 megaflops at a top cycle time of 160 ns. The much faster CMOS version will get a bundle of new features, including 24-bit addresses instead of 14-bit, the ability to access 16 Mbits of external memory compared with 56 Kbytes, and interfaces for 8- and 16-bit microprocessors. It will be packed inside a 133-pin grid array instead of the 100-pin packages in use now and will likely take aim at advanced image-processing environments. □

GE/RCA FIRES ANOTHER SHOT IN THE BATTLE OF THE PINOUTS

It's been nine months since Texas Instruments Inc. of Dallas fired the first shot in what turned out to be a bitter summer-long skirmish between Fairchild Semiconductor and TI over the package type and pinouts used for certain advanced CMOS logic devices [*Electronics*, Aug. 7, 1987, p. 29]. But the war isn't over yet. The GE/RCA Solid State Division in Somerville, N. J., another of TI's opponents in the squabble, has completed changes to its Advanced CMOS Logic, or ACL designs, that it says have cut the ground-voltage bounce almost in half. GE/RCA has also developed a test method to measure the simultaneous switching transient that had caused problems. The problem led TI to abandon the industry-standard 20-pin package and switch to a 24-pin carrier, while moving the ground pins from the corner to the center pins. At the time, TI claimed the move would allow it to cut the transient from the 1.9-to-2.0-V range to 0.4 V. GE/RCA disagreed, and now, through redesign, has managed to cut the transient to just 1.08 V—low enough, according to Dick Funk, manager of IC applications, to eliminate any worry users might have. TI says it has made samples available of more than two dozen center-pin prototypes since the beginning of the year and that five devices are ready in volume. The Dallas company says the transient voltage for its parts is under 1.0 V. □

SUN CLIPS THE PRICE OF ITS LOW-END WORK STATION

Sun Microsystems Inc. isn't going to sit by while new high-end personal computers cut into its work-station business. Instead, Sun is slashing 37% off the price of its entry-level work station, dropping it from \$7,900 to \$4,995. Sun says the price cut was possible because production costs for the one-year-old Sun 3/50M fell. But executive vice president Bernie Lacroute acknowledges that one of the company's motives is to provide an alternative to machines such as Apple Computer Inc.'s Macintosh 2, and to ward off competition by the rash of upcoming work stations based on Intel Corp.'s 80386 microprocessor. Apple called the price cut "significant" but says it won't prevent the Mac 2 from carving out a chunk of the market. The Mac 2 is attractive because, with Unix operating-system software, it can act as a work station on a Sun network. Other high-end personal computers—such as IBM Corp.'s RT PC and Personal System/2 model 80 (see p. 46)—offer business software that Sun doesn't provide. But Sun points out that personal computers don't offer the multitasking and distributed computing capability afforded by work stations. Sun's move may also be the prelude to a series of higher-performance machines expected later this year. □

ELECTRONICS NEWSLETTER

NOW THE SIA WARNS AGAINST MITI-IMPOSED PRODUCTION CUTBACKS

Concerned about possible chip shortages, the Semiconductor Industry Association is taking a firm stand against limitations imposed by the Japanese government on memory chip production there. SIA president Andrew Procassini warned recently that Japan must not intervene "to restrict the flow of semiconductors to world markets." He added: "Quantitative restrictions by Japan on semiconductor exports would threaten to create artificial semiconductor shortages outside Japan," and would be "counterproductive" in resolving the trade dispute between the U. S. and Japan. "We did not ask for artificial restrictions, we asked for no more dumping," says one SIA official at the group's Sunnyvale, Calif., headquarters. □

MOTOROLA IS LATEST TO ADOPT NATIONAL'S TAPE PAK CHIP CARRIER

National Semiconductor Corp.'s Tape Pak, a small, leaded plastic chip carrier based on a single-layer tape-automated-bonding process [*Electronics*, Aug. 21, 1986, p. 74], is gaining support. The latest chip maker to adopt the package is Motorola Inc., the second-largest integrated-circuit producer in the U. S. The Phoenix, Ariz., company will use the tiny square packages with leads on 20-mil centers to house high lead-count VLSI circuits. Motorola is the second company to adapt National's packaging technology; about four months ago, the Delco Products Division of General Motors Corp., in Kokomo, Ind., also agreed to use Tape Pak. The list of supporters is expected to grow, especially now that it has been registered by the Joint Electronic Device Engineering Council (JEDEC) committee for mechanical standardization and second sourcing. □

SAPC SLAPS LOTUS WITH 1-2-3 'LOOK-AND-FEEL' COPYRIGHT SUIT

Lotus Development Corp. doesn't see much merit in the \$100 million copyright-infringement lawsuit brought by SAPC Inc. The action is "an ill-considered first strike by parties who have been preparing to release their own clone of Lotus 1-2-3," according to Henry Glutman, Lotus' litigation attorney. The suit resurrects a controversy over whether Lotus and its founder, Mitchell Kapor, who has since left, substantially copied the "look and feel" of Software Arts' VisiCalc spreadsheet in developing Lotus 1-2-3. Lotus bought VisiCalc last June from Software Arts Products Corp., since renamed SAPC. SAPC is suing to rectify infringements that allegedly occurred before Lotus purchased the VisiCalc. "We don't bring lawsuits that don't have substantial chances for success," says Mark Michelson, SAPC's lawyer. □

AMD ADDS PROTOCOL CONVERTER TO ITS ISDN CHIP SET

Advanced Micro Devices Inc. won't see first silicon for at least eight months, but buoyed by support from AT&T Co., the Sunnyvale, Calif., chip maker has announced what it claims is the industry's first single-chip protocol controller for the integrated services digital network. The new part, offered with the five existing members of AMD's ISDN chip family, will provide a "total solution" to both ends of ISDN's "S" interface, which connects terminal equipment with a digital private branch exchange. The AM79C401, which will be fabricated in 1.2- μ m double-metal CMOS technology, will replace a board full of components and cut hardware costs in half. Software development costs would also be cut, AMD says, because the chip has built-in real-time management functions, well-defined interfaces, and an overlying software module. AT&T is supporting development of the controller by providing documentation for its Digital Multiplexed Interface, part of its ISDN solution, and will share in testing and certifying the new part. □

Tailor your own system set-up!

Philips **System 21** – a highly flexible modular system for automatic test and measurement providing versatile I/O and switching functions controlled via the GPIB.

So you can get easily configure – and reconfigure – your own small to medium-size GPIB instrumentation set-up.

Simply and economically.

Occupying only a single GPIB bus address, **System 21** comprises a master GPIB interface/power supply module, and a range of slave modules for: switching (up to 18 GHz); digital I/O; A/D conversion, and a user-adaptable module for customized functions.

And our commitment to hard- and software development ensures that



Test the difference

System 21 will continue to grow up without ever growing old!

Product Credibility in technology, technique, quality and service, too, is assured because **System 21** is backed by the resources of one of the world's largest electronics companies.



Test the difference and you'll also agree that Philips wins on price and performance!

Write to: Philips I & E, T & M department, Building HKF70, 5600 MD Eindhoven, The Netherlands or call your local supplier: **Austria** (222) 629 141; **Belgium** (2) 5256692/94; **Denmark** (1) 572222; **Finland** (0) 5257225; **France** (1) 48301111; **Germany** (561) 5010; **Great Britain** (0223) 358866; **Ireland** (1) 693355; **Italy** (39) 3635 240/8/9; **Netherlands** (40) 782808; **Norway** (2) 680200; **Portugal** (1) 683121; **Spain** (1) 4042200; **Sweden** (8) 7821800; **Switzerland** (1) 4882211



Test & Measurement

PHILIPS

Circle 110 on reader service card

Need flexible I/O for your IBM PC?

The DTX Series solves that puzzle.

Introducing Data Translation's new iSBX compatible data acquisition module series. Now IBM PC users can have analog I/O flexibility tailored to fit their needs.


We call our boards the DTX Series. Offering you low cost, modular building blocks for data acquisition and control applications.

Each DTX module provides a single I/O function designed to be used with a bus compatible mother board.

The chart below shows you some of the available capabilities. All the DTX modules can be interfaced with the IBM PC, XT, or AT, and are ideal for industrial, factory or laboratory applications.

If you've been puzzled trying to find modular boards, call Data Translation today. We've put all the pieces together in a system to fit your exact needs.

Call (617) 481-3700



DT2806 mother board with A/D module (DTX311) and D/A module (DTX328) shown installed and digital I/O module (DTX350) separate.

Flexible I/O modules for the IBM PC

Model	Price (U.S.\$)	No. Channels	A/D		D/A		DIO Lines	Timers
			Resolution (Bits)	Speed (KHz)	Resolution (Bits)	Speed (KHz)		
DT2806*	295	to 80	—	—	to 24	—	to 72	3
DTX311 A/D	425	16SE/8DI	12	20	—	—	—	—
DTX311EX A/D Expander	385	48SE/24DI	12	20	—	—	—	—
DTX328 D/A	425	—	—	—	8	12	5	—
DTX350 DIO	199	—	—	—	—	—	24	—

*The DT2806 has 3 iSBX compatible connectors for any mix of DTX modules

Fred Molinari, President

To learn more, see us in Gold Book 1987, or call to receive our first-ever 1987 3-Book Set, including the 1987 Catalog, Product Summary Price List, and Applications Handbook.



DATA TRANSLATION®

World Headquarters: Data Translation, Inc. 100 Locke Dr. Marlboro, MA 01752 (617) 481-3700 Tlx 951 646

European Headquarters: Data Translation Ltd., 13 The Business Centre, Molly Millars Lane, Wokingham, Berks, RG11 2QZ, England Tlx 849862 (#D)

International Sales Offices: Australia (61) 2-662-4295; Belgium (32) 2-7352135; Canada (416) 625-1907; Chile (2) 2-253689; China (408) 727-8222; (86) 8-721-4017; Denmark (45) (02) 187188; England (44) 734-79383; Finland (358) 90-372144; France (33)(1) 69-28-01-73; Greece (30)(3) 152-7039; (30)(1) 361-4300; Hong Kong (852) 3-318585; India (91) 2-231040; Israel (972) 3-324298; Italy (39) 2-81821; Japan (81) (3) 502-5550; (81) (3) 375-1551; Korea (82) 778-0721; Malaysia (60) 3-36299; Morocco (21) 9-30-6949; Netherlands (31) 70996360; New Zealand (61) 2-662-4295; Norway (47) (02) 559050; Peru (51) (14) 31-8060; Philippines (63) 818-0103; Portugal (351) 1545313; Singapore (65) 271-3163; South Africa (27) 12469221; Spain (34) 14558112; Sweden (46) 8-7617820; Switzerland (41) 17231410; (41) 22360830; Taiwan (86) 2-709-1394; West Germany (49) 89809020.

IBM PC, XT, AT are registered trademarks of IBM. iSBX is a trademark of Intel Corporation. Data Translation is a registered trademark of Data Translation, Inc.

PRODUCTS NEWSLETTER

NEC'S 32-BIT MICROPROCESSOR OUTSPEEDS RIVALS AT 6.6 MIPS

Japan's first microprocessor with 32-bit data and address buses runs at a maximum rate of 6.6 million instructions per second—4 mips is typical of 32-bit chips. Fabricated in 1.5- μ m CMOS, the NEC Corp. V 70 has a dynamic bus sizing that enables it to match input/output with 8-, 16-, and 32-bit buses. Its TRON operating system will make it shine in real-time control and robot applications. The 20-MHz V 70 also incorporates floating-point facilities on-chip and has a function redundancy monitor for fault-tolerant computing. Sample price of the device is \$687.52. Prices will be lower for production quantities. ☐

CHIP INTEGRATES PERIPHERAL BUFFER, SCSI INTERFACE TO SAVE BOARD SPACE

Designers of controllers for half-height disk drives, where board space is at a premium, can save precious real estate with NCR Corp.'s latest CMOS Small Computer Systems Interface circuit, the NCR 53C300, which integrates two chips into one. While providing the same SCSI control functions found on NCR's year-old NCR 53C80, the new chip also has dual-port peripheral interface buffers ranging from 256 bytes to 64 Kbytes. Developed originally for Rodime Europe Ltd., Glenrothes, Scotland, the 53C300 is now being brought to market by NCR Corp.'s Microelectronics Division, Colorado Springs, Colo. Available now, it comes in an 84-pin plastic leaded chip carrier for \$21.50 each in 1,000-unit quantities. ☐

WANG ADDS LOW-END TEMPEST MINIS

An expanding government and business market for secure computer systems has prompted Wang Laboratories to add two entry-level 32-bit minicomputers to its Tempest systems product line. Available from the Lowell, Mass., company in May, the \$13,500 VS 5T supports as many as eight users and 16 peripheral devices; the \$21,500 VS 6T supports 16 users and 24 peripherals. Other machines in the Tempest line include the \$38,000 VS 65T, which supports 40 users, and the \$89,000 VS 85T, which supports 64 users. The new VS 5T and VS 6T feature fully removable storage media in the central processing unit and intelligent peripherals that can be taken out and locked up when the system is shut down. Both minicomputers can be used either as stand-alone systems or as end-node systems in large distributed networks, and neither requires special housing, power, or air-conditioning. The proprietary VS architecture allows the machines to interactively process data, text, voice, and images—a feature that Wang claims is unique to this architecture. ☐

CDC PLUNGES INTO 1-GIGABYTE DISK-DRIVE FRAY

Competition in the market for 1-gigabyte 9-in. half-rack disk drives for mainframes is heating up with Control Data's Corp.'s entry. The FSD III (for Fixed Storage Drive) provides 1.03 gigabytes of unformatted storage capacity and a 2.4-Mbyte/s transfer rate. Its cost is about \$6.80 per megabyte, which the Minneapolis company says puts it in the same league as NEC's D2363, a 1.13-gigabyte 9-in. half-height drive, and Hitachi's 1.05-gigabyte DK-815-10. An improved oxide media and better thin-film head design mean the FSD III can handle nearly twice as much data as its predecessor, the 515-Mbyte FSD II. It records on seven disk platters with 26 heads at densities of 1,283 tracks/in. and 20,254 bits/in. The unit supports three interfaces: SMD, SMD-E (for storage module drive with ECL drivers and receivers), or IPI (for intelligent peripheral interface). Available in the third quarter, it will sell for \$6,990 in quantities of 250. ☐

PRODUCTS NEWSLETTER

VIDEO CONFERENCING SYSTEM PROMISES TO SLASH COSTS

Look for full-motion color video conferencing to become more affordable April 21 when Compression Labs Inc. unveils a system that uses switched 56-Kbit/s telephone lines, costing \$50 per hour, instead of T1 lines that rent for up to eight times more. The Rembrandt 56's motion-compensation technique squeezes 40-Mbit/s full-motion color video frames down to 56 Kbits/s for transmission primarily by predicting movements within the frame. But it limits the number of people in the picture to just two or three. A video conferencing pioneer, the San Jose, Calif., company also offers 1.5-Mbit/s T1 systems and 384-Kbit/s systems with the same proprietary differential-transform coding now used in the 56-Kbit/s system. The Rembrandt 56 codec costs \$68,000—the same as the company's T1 codec. A complete 56-Kbit system, including five personal-computer-based stations, cameras, and the codec, costs \$113,500. The product is available this month. □

PERFORMANCE SEMICONDUCTOR PUSHES CMOS SRAM ACCESS UNDER 10 NS

With its 8-ns access time, Performance Semiconductor Corp.'s 1-Kbit CMOS static random-access memory is fast enough to challenge super-fast bipolar ECL circuits and 25% faster than the fastest TTL input/output SRAM. Organized into 256 by 4 bits with six-transistor cells, the P4C422-8PC aims at replacing ECL bipolar devices in such applications as high-speed caches, writable control stores, and lookup tables. Besides its speed, the device offers better electrical margins and better protection against single-event upsets than conventional four-transistor cells, says the Sunnyvale, Calif., company. Available now, the part costs \$19.95 each in 100-piece quantities, and delivery takes two to eight weeks after receipt of order. □

TOOL KIT SPEEDS DEVELOPMENT OF MULTIBUS II COMPUTERS

Designers of Multibus II-based single-board computers can now get all their development tools in one package, thanks to the Micro Industries MIB II 186/110 I/O Development Kit. Engineers can use it to design and debug Multibus II computers on either an Intel Corp. Series II or Series IV Development System or on a standard RS-232-C terminal. The MIB II 186/110 contains both hardware and software, says the Westerville, Ohio, company. Hardware includes an Intel 80186 microprocessor, a separate configuration processor, up to 256 Kbytes of electrically programmable read-only memory, up to 512 Kbytes of DRAM, an Intel 82258 direct-memory-access controller, an Intel 8259 interrupt controller, a serial communications port, and prototype space occupying about one third of the board area. The software includes the mSDM-186 Monitor/Debugger, a debugging monitor compatible with Intel's iSDM-86 Monitor/Debugger. Available now, the kit is priced at \$2,000 for single units. □

SIMULATOR LIBERATES MICROWAVE DESIGNERS FROM THE LAB

Microwave circuit designers can throw away their breadboards and lab instruments and for the first time simulate their nonlinear circuits on personal computers with Eesof Inc.'s new design tool. The Westlake Village, Calif., company's Microwave Simulator Spice 1.1 can display signal power at specific frequencies, sweep power levels and frequencies over specified ranges, and compute relative signal strengths. It also allows multiple waveform inputs to compute intermodular distortion instead of having the engineer run each signal separately and compute the composite algebraically. The licensing fee starts at \$8,450, and the tool runs on the IBM Corp. PC/XT, PC AT, and compatibles. □

Double your logic analysis capability!

The new PM 3570 Logic Analyzer featuring the dual-screen mode allows you to perform time-correlated state and timing analysis with no less than 115 channels simultaneously. Built-in performance analysis permits system optimization. Other special features include:

- **83 state and 32 transitional timing channels** for simultaneous, time-correlated acquisition at speeds up to 400MHz! Or you can combine them for an unprecedented 115 channels of state acquisition.

- **Microprocessor support** for 8, 16 and 32 bit analysis plus a wide range of adaptors including: 40-, 48- and 64-pin dual-in-line (DIL) as well as 68- and 114-pin grid array and 68-pin leadless chip carrier (LCC) versions.


- **Softkey operational simplicity** for step-by-step entry, and non-volatile memory for storage of instrument set-ups and measurement data.

- **Product credibility** in technology, technique, quality and service because the PM3570 is backed by the vast corporate resources of one of the world's largest electronics companies.



Test the difference

A simpler configuration, the PM3565, handles up to 75 channels including 59 state and 16 transitional timing channels with speeds up to 300MHz.



Test the difference and you'll also agree that Philips wins on price and performance!

Write to: Philips I&E, T&M Department.
 Building HKF/55. 5600 MD Eindhoven.
 The Netherlands: 040-78 25 43
 Germany: (0561) 50 14 66
 Great Britain: 0223-35 88 66
 France: 01-830 11 11
 Belgium: 02-525 111
 Switzerland: 01-488 22 11



Test & Measurement

PHILIPS

Circle 29 on reader service card

What technicians demand:

Quality
Safety
Accuracy
Reliability



Real-Time or Stored – Manual or Automatic Norma has it

OSCILLOSCOPE S1010 – the sturdy scope

Extreme ease of operation makes for a swift and accurate solution of your measuring task. Clearly arranged controls, outstanding quality and reliability will make your purchase decision easy.

OSCILLOSCOPE S1011 – the progressive scope

The OSCILLOSCOPE S1011 will show you what progress is in oscilloscopy. The easy-to-grasp arrangement of controls makes the numerous measuring modes of this instrument become just so many problem-solvers within your power. The superiority of this instrument as defined by its universal applications, together with its low price, makes the OSCILLOSCOPE S1011 truly a scope for everybody.

OSCILLOSCOPE S1004 – the selfacting scope

Never before has a 50 MHz oscilloscope shown such a degree of comfort, quality and reliability. But there is even more to the OSCILLOSCOPE S1004.

A timebase with autorange, an automatic trigger section and progressive circuit concepts will simplify quite a number of measurements, e.g. in servicing TV receivers.

The OSCILLOSCOPE S1004 is a milestone in the 50 MHz class.

The price of this instrument ensures that the OSCILLOSCOPE S1004 is well within your reach.

OSCILLOSCOPE S1007 – the scope with the excellent memory

The digital-memory OSCILLOSCOPE S1007 is no more complicated to operate than a simple real-time scope. But on the other hand it most significantly extends your facilities for measuring and monitoring. Thus single-pulse representation with or without previous history, roll or refresh operation and reference storage are provided, as well as the opportunity for image output to XY recorder. The price of the OSCILLOSCOPE S1007, too defies all competition.

Leading in measuring techniques

The state-of-the-art technology of our instruments together with more than 60 years experience in measuring techniques guarantees maximum quality and reliability.

Worldwide sales and service network

Our sales organization cares for customers all over the world, ensuring smooth service. We export our meters to 70 countries of the world.

Norma's successful OSCILLOSCOPES:

	S1010	S1011	S1004	S1007
Frequency range	20 MHz	20 MHz	50 MHz	20 MHz
No. of channels	2	2	2	2
Additional features	autofocus inside raster tube 2 Y channels in XY mode	autofocus inside raster tube autorange delay hold-off	autofocus inside raster tube autorange 3digit LED display hold off	digital memory inside raster tube real-time operation roll and refresh operation reference memory analog output

NORMA

NORMA – first in precision!

NORMA Messtechnik, Optik, Elektronik, Gesellschaft m.b.H., A-2351 Wiener Neudorf, Austria, Eumigweg 7, POB. 81 Telephone: (2236) 61 530-0, Telex: 79316, Telefax: 32 21 427, Telefax: (2236) 61 530/584 Cables: NORMAMETER WIEN

Circle 111 on reader service card

HOW TO COMPETE IN WORLD ELECTRONICS ...

There's a quiet revolution taking place in the UK electronics industry...

The design and manufacture of electronics products has exploded in terms of volume, complexity and range of applications. At the same time, the investment needed to manufacture competitively, in this technically dynamic market, has stretched the resources of even major companies.

In the UK, the need to provide sub-contract production capability to manufacture electronic assemblies, in any volume, and to stringent quality standards, has been met by one company. A company with the capital resources, the experience and the vision to provide a complete manufacturing service.

That company is the AB Electronic Products Group.

AB, over the past 2 years, has invested more than \$30 million in the very latest electronic design, production, and test equipment. With four UK sites covering over 200,000 square feet of purpose built electronic assembly facility, and a wealth of design, procurement and manufacturing experience, AB has assembled a world-beating force in electronics manufacture.

AB provides this design and manufacturing partnership for an ever-increasing number of successful companies, including many internationally known names, such as IBM, Jaguar, BT, British Aerospace, and General Motors.

Providing a Design and Development team with an unequalled range and depth of experience, together with the latest CAD techniques.

Surface mount 'Pick and Place' Machine, at AB's Microelectronics Plant.



AB's latest 'Wax-cut' Flow Solder line, part of a total Group capability of eleven complete lines.

...WITHOUT INVESTMENT IN MANUFACTURING

A procurement team which buys over \$150 million of materials and components every year, with all the buying power, computer scheduling and quality control that this entails. And providing complete production lines which can handle from as little as 50 up to 150,000 fully assembled products per month.

To find out more about the manufacturing service AB can provide your company or if you need to discuss current projects requiring assembly capability, contact Doug Mapplebeck, Director New Business Development.



**THE SOURCE OF
PROFESSIONAL ELECTRONICS**

AB Electronic Products Group Plc
Abercynon, Mid Glamorgan, United Kingdom, CF45 4SF
Tel: 0443 740331

Circle 122 on reader service card

Packaged Performance.



STANDARD!
Computer/GPIB
Controller and
Terminal Emulator

STANDARD!
Printer and Video
Outputs

STANDARD!
RS-232 and GPIB
Interfaces

STANDARD!
Disk storage of
set-up and data

STANDARD!
Performance Analysis
Histograms

Optional Features, all models:

- Waveform recorder
- Counter/Timer
- Signature Analysis
- Time Histograms
- Dedicated *uP* probes (except 800E)
- Second Disk Drive

Nicolet Logic Analyzers

A QUICK LOOK:

	800A	800B	800C	800D	800E
Timing Channels	16	16	16	16	16
Maximum Speed:					
Internal clock (async.)	100 MHz	100 MHz	200 MHz	200 MHz	200 MHz
External clock (sync.)	40 MHz	40 MHz	75 MHz	75 MHz	75 MHz
Main & Reference Memories	1000 x 16	1000 x 16	1000 x 16	1000 x 16	1000 x 16
Glitch Capture	5 nsec	5 nsec	3 nsec	3 nsec	3 nsec
State Channels	32	48	48	48	N/A
Maximum Speed	20 MHz	20 MHz	20 MHz	25 MHz	
Main & Reference Memories	1000 x 32	1000 x 48	1000 x 48	1000 x 48	
16 level triggering	✓	✓	✓		
Advanced nonsequential triggering (IF.THEN.ELSE)				✓	
Microprocessor Disassembly	8 bit	8, 16 bit	8, 16 bit	8, 16 bit	
Trigger Linkage	Link to/from State, Timing, Waveform, or External input				
Price	\$8900.	\$10,900.	\$12,900.	\$13,900.	\$9,900.

Get the Whole Story: Call for a complete brochure or to discuss your application. 800-356-3090 or 608-273-5008.

NiC Nicolet

"Instruments of Discovery"

Nicolet Test Instruments Division P.O. Box 4288 • 5225-2 Verona Road Madison, Wisconsin 53711-0288

Circle 32 For More Information

Electronics

MAGNETO-OPTIC MEMORIES BEGIN TO LOOK LIKE A GOOD BET

SIMPLE NIKON TECHNIQUE PERMITS ERASE AND WRITE IN ONE PASS

TOKYO

The race for dominance in the upcoming generation of high-capacity optical memories is heating up, and a flurry of recent activity is moving magneto-optic disks out of the shadow of magnetic disks. Work in the U.S. and Japan aimed at wiping out the major disadvantage of magneto-optic memories—they require two passes to overwrite, one to erase the old data and the other to record—could at last let eager computer designers take advantage of the considerable edge in density that magneto-optic disks have over magnetic memories.


The most recent developments come from Nippon Kogaku K.K., known as Nikon, in Japan; Carnegie Mellon University in Pittsburgh; and IBM Corp. The Carnegie Mellon and IBM techniques require the use of two lasers or of one laser with a split beam. So perhaps the most promising new technique is that of Nikon, a newcomer to the disk-drive business, which has perfected a relatively simple and straightforward one-laser solution.

ONE PASS. Nikon engineers made one-pass writing possible by going to a medium with two thin-film magnetic layers (see diagram). The magnetization of the lower layer, terbium iron cobalt, is repeatedly initialized to a downward reference on each pass. This gets it ready to erase 1s, which are stored as magnetization in the upward direction in the upper layer.

The lower layer has the relatively low coercivity of 3.5 kilo-Oe, permitting it to be magnetized in a single direction by a fixed field of 7 kilo-Oe. The upper layer, terbium iron, is the usual film used for magneto-optic recording. It has the high coercivity of 13 kilo-Oe and thus its magnetization is unaffected by that of the lower film at room temperature.

Immediately before writing starts, a given point on the disk always passes over the initializing magnet that resets the magnetization direction in the reference layer. This point then passes under the laser head, at which position there is a relatively weak field of 200 Oe pointing upward.

The laser may have one of two power



PASSING THROUGH. Nikon's system does one-pass erase and write by using a medium with two magnetic layers. The lower layer does the erasing of the 1s stored in the upper layer.

levels, 9 mW to write and 5 mW to erase. At the 5-mW power level, only the upper layer reaches its Curie temperature (the point at which a material no longer exhibits ferromagnetic properties) of 140°C. As it cools down, it is magnetized in the zero state by the reference film. At the 9-mW power level, the lower layer passes through its Curie temperature of 200°C. The low field is sufficient to magnetize both films in the upward direction, the 1 state.

Disks are read at a power level of 1.5 mW. Kerr-effect rotation is 0.3°. Tests show a carrier-to-signal ratio of 54 dB at 1 MHz and 44 dB at 8 MHz. Information density is about one bit/square μm . Experiments were conducted with a track pitch of 1.6 μm and a linear recording density of one bit per 0.84 μm .

In the conventional configuration, an erase head precedes the write head. The track is erased only prior to writing; at all other times the erase laser must be kept off to prevent destruction of data. Moreover, the system must account for the difference in position between the two heads along the track. The Nikon configuration requires no intelligence or control—operation is automatic. The write head has two states, 0 and 1, which is identical with the operation of a magnetic head.

One of the Nikon system's strong points is its compatibility with computer operating systems written for magnetic disks. Development manager Hideki

Akasaka's group has developed a magneto-optic disk that looks to a computer's operating system like a magnetic disk with greatly increased capacity. Experimental disks and a drive have been developed at Nikon's Information Storage Products Division; Akasaka says that "it will take two or three years to complete development, check reliability, and start production of a commercial product."

In the meantime, Nikon can expect to see some competition emerge. Indeed, most of Japan's major electronics companies—including Fujitsu, Hitachi, Mitsubishi, NEC, Sanyo, Sharp, and Sony—are working on erasable magneto-optic disks. And Sony says it will begin shipping samples this fall and production units by this time next year.

ALTERATIONS. In the U.S., Carnegie Mellon University researchers have come up with a lab technique based on their discovery that the inherent demagnetizing field can be used to erase and write directly [*Electronics*, Feb. 5, 1987, p. 76]. Altering the magnetic media's formulation with a laser raised the compensation temperature and made possible a read-before-write scheme. Program managers are now talking with commercial licensees.

IBM received a patent March 10 for a technique that is similar to the Carnegie-Mellon system in that the magnetic state is flipped with a laser beam.

—Charles L. Cohen

DESIGN TRICKS SPEED UP INMOS'S SRAMS

COLORADO SPRINGS

Inmos Corp. has done a topsy-turvy act with its fast 256-Kbit static random-access memories that should make possible faster, smaller, and more producible CMOS SRAMs. The trick is the layout of sense amplifiers. Some of the SRAM's MOS circuits are turned around, hooking inputs to sources rather than gates.

The layout resembles techniques normally associated with bipolar circuits, which are current-sensing, rather than MOS, which is voltage-driven. Inmos intends to use the design to avoid speed-hampering capacitance that can crop up on long bit lines with the voltage-sensing technique. Portions of the CMOS memories operate more like emitter-coupled logic, quickly sensing bit lines by reading current rather than voltage differentials.

FASTER. Access times of 18 ns can be accomplished with the 256-Kbit chips because current-sensing circuits quickly detect slight differences in the flow of electrons. With voltage sensing, more time is needed to detect bit-line capacitance, because it takes longer to reach voltage differentials sufficient for sensing. And a simpler clocking mechanism used in current sensing also adds speed, because extra cycles are no longer needed to clear out voltage differentials from lines before the next memory access.

The move to MOS current-sensing circuits also cleans up the circuit design. It enables Inmos to forgo more than a thousand pre-sense amplifiers typically wedged into the pitch between bit lines on a 256-Kbit chip. Normally, these are used to boost differential reading from cells and are placed directly at the end of bit lines to cut capacitance.

Since bits are read internally when using current-differential levels, the length of lines and the amount of capacitance are less critical, notes Ken J. Mobley, one of the principal design engineers for the 256-Kbit fast SRAM. A soon-to-be-announced 64-Kbit-by-4-bit design contains only 32 pre-sense amplifiers instead of the 1,024 that would have been used in a voltage-sensing design. That means the die is smaller by 3,000 mil². More important, most of the reduction was made by trimming the width of the 172-by-404-mil chip, making it possible for Inmos to offer it soon in a standard 300-mil-wide plastic dual in-line package.

The 64-Kbit-by-4-bit memory—plus a 256-Kbit-by-1-bit chip and two 64-Kbit SRAMs—will reach market later this year with worst-case access times of 25 ns. Typical access times have been clocked at 18 ns with a 5-V power sup-

ply at room temperature. Essential to keeping the resistance low for the current-sensing technique is a new double-level metal 1.2- μ m CMOS technology, called Process '86 by Inmos for the year it was first put into pilot production.

"If we had stayed with a single-metal process, we would have had a lot of parasitic resistance, which would have detracted from the ability to perform current sensing," says Larry F. Childs, another principal designer.

MAKING IT. The elimination of the pre-sense amplifiers and the die reduction have also eased manufacturing. "The sense amp in any memory device is absolutely the most sensitive area of a die in terms of process variations," explains Mobley, referring to the difficulty in matching MOS transistors for linear duties. The chips are also going to feature a proprietary sensing circuit that self-generates a reference signal from a bit line rather than use duplicate mirror-reference circuits, which are susceptible to mismatching with each bit line.

To develop the MOS current-sensing

circuits, engineers had to reinvent the amp, so to speak, and forget standard voltage-sensing amplifiers used in memories for the past 15 years. "Once you start designing any kind of differential amplifier, you start to worry about all the basic things such as common mode rejection and differential gain," says Mobley in explaining the departure from common memory-layout practices.

"The normal voltage-sensing technique, which is well understood, fixes the source of two transistors at an identical voltage and then applies an input signal to the gate. Because gates of MOS circuits are by nature high-impedance devices, they are strictly capacitive and there is no current flow into the input," Mobley says. "We have turned that around and fixed the gates of two input devices at an identical potential, which is generated through a reference path. The inputs are made to the sources." A difference in gate-source voltage still exists, but current flows through the inputs, and there is a dc path to the amplifiers.

—J. Robert Lineback

RADAR

A BILLION-DOLLAR PROGRAM EXCITES THE INDUSTRY


LOS ANGELES

A new procurement is exciting the military electronics industry. Not only is it the only big avionics program around in a period of tight budgets, but it is the first major military project to specify the use of Very High Speed Integrated Circuits from the start, and it

is a departure from the customary contracting procedures.

The procurement is the programmable signal processor for the Air Force's Advanced Tactical Fighter. It's a dedicated computer that will serve the aircraft's multiple sensors, mainly radar. As decision time nears, the competitors are three heavyweight companies, one a relative newcomer to the radar business. And not only is the program worth upwards of \$1 billion through the next decade, it also is being watched for clues to the changes in procurement and design that VHSIC creates.

One apparent difference is that the project is drawing new players. For the ATF processor, IBM Corp.'s Federal Systems Division is competing with the two major producers of military radar, GMHE/Hughes Aircraft Co. and Westinghouse Corp. The radar competition is a natural battleground because most of the VHSIC Phase 1 chips, from six contractors, are aimed at better signal processing. Also, where processing tasks and front-end functions ordinarily are bundled in the same system, VHSIC capability permits them to be split to boost performance.



VHSIC BOX. Westinghouse's entry in the competition for the VHSIC-loaded ATF radar.

All three will submit their final proposals before the end of April to both potential prime-contractor teams: Lockheed and Boeing-General Dynamics, and Northrop and McDonnell Douglas. Each prime contractor will pick a processor subcontractor and begin development by late summer. This is uncommonly fast for military work, one of VHSIC's goals. Ultimately, the winner is to be chosen after a flyoff some five years from now. Under the old system, one prime contractor would already have been selected.

Although the Air Force and the two prime-contractor teams are not divulging details about the processor, enough is known to understand general structural and performance goals. A major advance appears to be an architecture of common modules that will best support design flexibility and device improvements as they occur. This "building block" approach, long sought by military planners but held back by lagging

Hughes, Westinghouse are upgrading existing processors

military semiconductor work, is made possible by the density of VHSIC Phase 1 chips that replace many component boards and have clock speeds up to 50 MHz. To support the multiple sensors, the system must perform up to 100 million complex operations per second (COPS), about 10 times faster than current operational processors.

The three contenders will take somewhat different approaches, but Hughes and Westinghouse closely follow processor improvements that both have in the works. IBM's design is based on 13 new 1- μ m Phase 1 chips being developed for ATF, says Robert Estrada, VHSIC program manager at the IBM Federal Systems Division in Manassas, Va.

Hughes already has started low-rate production on a unit for other craft that uses 1.5- μ m CMOS gate arrays with 10-Kbit gate-complexity levels in a parallel-processing scheme. Though these arrays are not yet qualified to VHSIC standards, Hughes expects them to pass muster before the end of 1988, says Milton E. Radant, vice president and director of technology of the Radar Systems Group in El Segundo, Calif. The processor, which Hughes calls its fourth generation, has a computational core shrunk to one third that of the previous generation; signal-processing speed is 40 million COPS, up from 7 million. Reliability is put at 750 hours mean time between failures, up from 460 hours.

For the ATF, Radant says, Hughes cuts the size of the processing element once again by two thirds and doubles

the speed. Its proposal has three basic module types. The Hughes group already has next-generation hardware well along in the lab, using available VHSIC devices and working toward the 100-million-COPS goal. It will be at the demonstration stage by late next year.

Westinghouse is building a VHSIC-

based programmable signal processor for the F-16 fighter. The processor is to reduce the number of boards from 31 to 14, increase performance from 16 million to 40 million COPS, and lower the power requirement from 2,948 W to 725 W. Westinghouse expects to have the go-ahead by late this year. —Larry Waller

ARTIFICIAL INTELLIGENCE

PROCESSOR LINKS NUMBER CRUNCHING AND SYMBOLICS

ANAHEIM, CALIF.

A new startup has produced a fast 40-bit inference machine that links conventional number crunching with the kind of symbolic processing typically used in artificial intelligence. Integrated Inference Machines Inc. has just delivered its first production unit to the National Aeronautics and Space Administration, and in so doing becomes a standard bearer for the combinational approach that some observers believe is the next wave of symbolic processing.

The company joins the field at a time when the makers of symbolic processors—including Lisp Machine Inc., which has filed for Chapter XI protection from its creditors (see p. 110), and Symbolics Inc.—are finding it tough to increase sales and profits. But Robert T. Wang, president and founder of Integrated Inference Machines, is undaunted. He believes the promise of symbolic processors will be realized as integrated coprocessors in systems, not in stand-alone computers.

The Anaheim company's strategy is to build a high-performance, low-cost symbolic processor that is tied to a numeric accelerator and a general-purpose computer and that readily runs multiple symbolic processing languages. The price for its SM45000 will be \$39,000 to \$44,500, and the company claims the machine runs 1.3 to 8 times faster than current symbolic computers, such as the \$50,000 to \$80,000 Symbolics 3600.


Clearly, airborne and space-borne applications will require high levels of intelligent symbolic processing plus fast numeric computation, which is one reason why the company's first unit went to NASA's Ames Research Center in Mountain View, Calif. NASA plans to use the machine as an experimental prototype for space-borne computers for the proposed U.S. space station and the national aerospace plane. In addition, NASA will use the SM45000 for software development in a joint project with the British Aerospace Agency.

The trend toward combining number crunching and symbolics is unmistakable in other applications as well. Where-

ever rapid analysis and decision making are required in fast-moving control situations, a very fast reasoning computer or inference engine must work with fast number crunching to augment human decision and reaction. Other companies are working in this direction, including Texas Instruments Inc.

TAGGING WORDS. The symbolic processor in the SM45000 was designed for fast response. The architecture that works best for symbolic processing is called a tagged architecture, since tags are attached to each word to characterize them. Most current Lisp machines are 32-bit machines with the tag included in the 32 bits. But the SM45000 has 40-bit words—32 bits with an 8-bit tag. The engineers at Integrated Inference Machines developed proprietary high-speed hardware for tag decoding, which helped them make such a fast machine.

This performance is just from the symbolic part of the machine. The SM45000 also has a mathematics accelerator option that does numeric processing at the rate of 4 million floating-point operations per second, and an enhancement is on the way to increase that to 8 megaflops. In addition, the design incorporates an Intel 80286 processor that han-



TOGETHER. Inference machine combines number crunching with symbolic processing.

dles all input/output, including file storage. The file system is compatible with the PC DOS file system used in IBM Corp. Personal Computers and compatibles. This means that PC files can be loaded into the machine and that, conversely, the SM45000 can generate files that can be loaded into a PC.

Also making the machine ideal for real-time embedded work is the avail-

ability of large amounts of memory at a low price. This means that real-time applications will not be slowed by swapping chunks of programs between disk drives and main memory—big chunks or even whole programs will fit into the large memory. The machine supports a linear address space for a virtual memory of 4 billion words, 20 gigabytes. The basic machine comes with 10 or 20

Mbytes of real memory with expansion slots for up to 240 Mbytes.

The SM45000 symbolic process runs an extended version of Common Lisp, and a Prolog language will be available next month. The I/O processor and numeric accelerator support standard languages. And the low price of the machine should keep the integration trend rolling along.

—Tom Manuel

INTEGRATED CIRCUITS

A FASTER GaAs CHIP NEARS PRODUCTION

BLOOMINGTON, MINN.


Digital integrated circuits based on gallium arsenide modulation-doped field-effect transistors are moving rapidly toward commercial density levels. Honeywell Inc. has developed a chip with 1,350 gates—the densest GaAs MOD FET logic circuit ever built. This technology is very significant in that it is seen by many as the heir apparent to today's production GaAs ICs based on metal-semiconductor FET processes. This is because they are faster and show less leakage. MOD FETs are a kind of HEMT (high-electron-mobility transistor).

The Pentagon's Defense Advanced Research Projects Agency is also jumping on the bandwagon. On March 30, the agency awarded a contract to a team headed by AT&T Bell Laboratories to develop a pilot line for digital chips that is based on ultrafast heterostructure-based GaAs technology (see "Bell labs to set up pilot line for Pentagon").

The Honeywell chip is an 8-by-8-bit pipelined parallel multiplier that was built in Honeywell's 1- μ m aluminum gallium arsenide/GaAs heterostructure technology with self-aligned gates [*ElectronicsWeek*, May 13, 1985, p. 19]. "This is the biggest MOD FET logic circuit we've ever seen reported or talked about," says Nicholas C. Cirillo Jr., who heads GaAs work at the Honeywell Physical Sciences Center in Bloomington.

SPEEDY. Honeywell was able to break the 1,000-gate barrier without making any sacrifices in speed. The circuit also exhibits the shortest room-temperature propagation delays of any working chip in any technology. Gate propagation delay at room temperature is 70 ps per gate, and power dissipation on the chip built came in at 1.4 mW per gate. All gates were built using direct-coupled FET gate logic.

The complexity record for a MOD FET logic circuit was held by Fujitsu



RECORD SETTER. Honeywell's 1,350-gate 8-by-8-bit parallel multiplier is densest GaAs MOD FET logic circuit to date.

Ltd., which in February 1986 reported an 8-by-8-bit parallel multiplier that integrated 970 gates and exhibited room-temperature propagation delays of 245 ps per gate, at about 6 mW/gate. Before that, Honeywell's 370-gate, 5-by-5-bit parallel multiplier was the speed

king, with delays of 73 ps/gate. So at 70 ps, the latest device is comparable in speed, but the device is nearly quadruple the complexity of its predecessor.

On the memory side, Fujitsu has already reported on a fully functional 1-Kbit static random-access memory chip that is based on HEMT structures that integrate 7,244 transistors, and others, including AT&T Bell Laboratories, Hughes, McDonnell Douglas, Rockwell, and NTT, are also working in the field.

Unlike MES FETs, in which channels are formed in a GaAs substrate by ion implantation, MOD FET channel structures

are grown by use of molecular-beam epitaxy or by use of metal-organic chemical vapor deposition. This means that in a MOD FET structure, electrons can be made to flow in a pure, undoped GaAs buffer layer, unimpeded by the dopant atoms that can lead to electron

BELL LABS SETTING UP GaAs MOD FET PILOT LINE

Honeywell Inc. isn't the only one interested in pushing gallium arsenide modulation-doped field-effect transistor ICs out of the lab and into production. The Pentagon's Defense Advanced Research Projects Agency is giving the technology a shove with a four-year, \$19.8 million contract awarded late last month to AT&T Bell Laboratories, Hughes Aircraft Co. and McDonnell-Douglas Corp. are subcontractors.

The DARPA deal calls for Bell Labs to develop a pilot line for heterostructure-based AlGaAs/GaAs ICs that can turn out 100 wafers per week within three years, says Robert C. Vehse, program manager for the contract at Bell Labs' Compound Semiconductor Integrated Circuit Laboratory in Reading, Pa. The contract calls for the design of six digital logic ICs, each with between 3,000 and 5,000 gates, which will be built in Bell Labs' submicron SDHT process (for selectively doped heterojunction

transistor). Bell Labs is also to develop a 4-Kbit static random-access memory using the SDHT process.

The six logic chips are aimed at digital-signal-processing applications, Vehse says. Two will be custom devices; the others will be based on standard-cell technology. Two of the standard-cell chips will be designed by Hughes, which will also be responsible for developing computer-aided design tools. McDonnell-Douglas will provide testing and analysis of the chips' radiation hardening.

The pilot line will use molecular-beam epitaxy and will begin operation by July, Vehse says. A second pilot line will also be established by Hughes in El Segundo, Calif. Besides the initial \$19.8 million, the contract also contains a DARPA option worth an additional \$10 million that would aim at even more advanced circuits based on AlGaAs/GaAs superlattice quantum-well structures, Vehse notes.

—Wesley R. Iversen

scattering in MES FET channels. Also, because of the higher Schottky barriers that result from putting the gates in an AlGaAs layer, MOD FETs exhibit much less leakage than MES FETs.

The result, says Cirillo, is the potential for circuits about twice as fast as today's MES FET ICs, and with four to five times higher noise margins. That translates into four to five times higher integration levels.

Honeywell pulled out of the merchant GaAs IC business last year, closing down its MES FET digital-circuit produc-

tion line in Richardson, Texas [*Electronics*, Dec. 18, 1986, p. 21]. But the company is continuing GaAs efforts with an eye toward meeting internal and possible future merchant-market needs.

"True production of MOD FET ICs across the industry, I think, is two to three years away, barring a major technology breakthrough in the use of metal-organic chemical vapor deposition to grow wafers," Cirillo says. In the meantime, Honeywell will continue to work on problems associated with molecular-beam-epitaxy approaches to growing

MOD FET structures, he says, such as material-defect density and throughput.

Honeywell plans eventually to use the same 1- μ m self-aligned process for production that it used for the demonstration 8-by-8 multiplier, Cirillo says. The company will continue to push device complexity with the process, and it has plans to build additional developmental chips, including an 8-by-8 multiplier/accumulator at about 2,300 gates, followed by a 16-by-16 multiplier/accumulator that will integrate more than 4,000 gates.

—Wesley R. Iversen

CONSUMER

FMX IS THE SOUND OF A NEW MARKET

BLOOMINGTON HILLS, MICH.

FM stereo broadcasting is headed for its first major improvement since it was adopted in 1961. Delivery of a final specification for the FMX Extended Range Stereo System is now expected by mid-May, an upgrade that would significantly reduce noise and extend the reception area up to four times. FMX now appears headed for commercial reality. And at least two semiconductor manufacturers plan to capitalize on it.

About 30 million FM stereo receivers are sold annually in the U.S., all eventual candidates for FMX chips. But the initial target of the two manufacturers—Sanyo Semiconductor Corp. of Santa Clara, Calif., and Sprague Electric Co.'s Semiconductor Group in Worcester, Mass.—is the auto market, which accounts for about half the U.S. radio sales.

Both are developing single-chip receiver-decoder circuits for the proposed FMX system. Sanyo plans first samples as soon as late May, with production quantities for less than \$2 each by October, says Aki Goto, executive vice president. Sprague is taking a more conservative approach. "We'll have samples by the end of this year or early next year, and if there's interest from customers, we could gear up for production by late 1988," says Robert F. Milewski, linear products manager at Sprague. The Sprague chip will integrate linear and digital BiMOS circuitry and will be a medium-scale circuit of about 15,000 mil², Milewski says.

The patented FMX technique was developed jointly by CBS and the National Association of Broadcasters [*Electronics*, June 17, 1985, p. 18]. It uses a unique compressor/expander system in which the compressor works with an adaptive expander in a receiver that can conform to any transmitted compression curve. Conventional expanders must be carefully tuned to a set compression ratio.

Though the drive to commercialize the technology was stalled by the closing of

the CBS Technology Center in Stamford, Conn., last September, it gained new impetus April 1 with formation of a partnership backed by Detroit-area investors to complete FMX development and handle licensing. The partnership, Broadcast Technology Partners, is based in Bloomington Hills, Mich.

CBS and NAB sponsored the first successful field tests of FMX more than two years ago. But the closing of the CBS center prevented the delivery of a final specification, says Emil Torick, co-inventor of the system and former vice president at the center. CBS has permit-



TORICK: Most U.S. stations will be broadcasting in FMX in two to three years.

ted Torick, president of the new partnership, to set up shop with his FMX team in another CBS facility in Greenwich, Conn. He expects to deliver the final FMX specs within weeks.

Sanyo and Sprague aren't the only ones waiting for that document. "We've got four manufacturers of FM broadcast equipment just waiting for us to give them the go-ahead," Torick says. If all goes as planned, commercial FMX broadcast equipment could be available

by this fall, and FMX stations could be on the air by late 1987, Torick notes. The first receivers based on the new FMX chips could be available early next year, he adds.

Broadcast Technology Partners plans to license receiver and broadcast equipment manufacturers for a nominal fee and then reap royalties on hardware sold. Partnership officials won't provide financial details, but Brown says the group hopes to break even on its investment in two to three years. The partnership will initially pursue the U.S. market, where no Federal Communications Commission rule change is required to implement FMX. It is compatible with existing FM stereo, Brown says.

BANDWAGON. The FMX chips from Sanyo and Sprague are designed to replace the existing stereo-decoder circuit in FM receivers and will receive FMX as well as conventional FM stereo broadcast signals. Though only about a half dozen FM stations have so far tested prototype equipment, Sprague and Sanyo are hoping for a rapid commercial FMX deployment by broadcasters and that FM-receiver manufacturers will jump quickly on the FMX bandwagon.

Torick predicts that most U.S. FM stations will be broadcasting in FMX in two to three years, given the improvement offered and the relatively low entry price. Torick likewise believes that FMX-receiver chip sales could hit 1 million units within one year of production availability. Within five years, he adds, "I expect we'll see the majority of receivers being FMX equipped."

Given those kind of prospects, Sanyo and Sprague could see some competition as the FMX market develops. "I think in the near future, others might be getting into this," says Sanyo's Goto. In high volume quantities, the new FMX receiver circuits are expected to sell for about \$1 each, compared with about 50 to 75 cents for today's conventional FM stereo decoder circuits.

—Wesley R. Iversen

Which is the



brighter power?




AUTOMATING A PC-BOARD HOLE-MASKING PROCESS

HAVERHILL, UK

The people at Philips Radio Communications Systems Ltd. were having problems spot-masking printed-circuit boards for mobile radio equipment at their Haverhill factory in the UK. Most of the components were assembled, inserted, and soldered automatically, but trouble started when the boards were masked for secondary components that would be added later: the work had to be done by hand to keep holes from filling with solder.

This meant the mask had to be positioned very accurately so that it did not overlap nearby pads. For small holes, the solder resist had to completely block the hole, with the area around large holes accurately covered by a ring of resist. The operator also had to work to a pattern of hole masking that was often very complex and varied from one board to another.



FAST MASKS. Philips and its allies have found a way to automate spot masking.

The procedure was time-consuming and prone to errors. So a research project was set up involving Philips; Kenco Ltd. of Chatham, which makes masking paste; and DEK Printing Machines Ltd. of Weymouth. They came up with a semiautomatic system, including a new, accurate water-resistant solder resist, that can handle several hundred boards

a week of up to 20 different types. Masking time for each board was reduced considerably—for example, a 200-hole board that took 5 to 6 minutes by hand can be done in 20 seconds by the automated method—and errors virtually disappeared. The system is available commercially from Philips.

Philips and its partners decided to develop their technique so that it would run on Philips' DEK 240 screen-printing machine. But Kenco's Aqua-strip resist, developed for hand masking, ran into problems when used with automatic machines. Viscosity and drying had to be carefully controlled. Being water-soluble, the resist was sensitive to changes in humidity. Kenco managed to retard the resist's evaporation rate and adjust the water content.

A polyester screen with 100 strands per inch was found to be best. It was placed across the frame at a 45° angle and given an emulsion coating of 100 to 300 μm , depending on the thickness of the mask required. The modified paste could then be printed without difficulty. DEK produced a number of different screens to suit the different boards used by Philips.

—Steve Rogerson

SOLAR CELLS

AT LAST, A CHEAP, EFFICIENT SOLAR CELL

ERLANGEN, WEST GERMANY

The twin thrusts of solar-cell development have been toward lower price and greater efficiency—and usually they have been mutually exclusive. But now researchers in West Germany have taken both routes and come up with a two-sided silicon cell that is both efficient and inexpensive to make.

The researchers, at the University of Erlangen-Nürnberg, believe their experimental devices have pushed solar cells a big step closer to economically viable photovoltaic energy conversion by achieving efficiencies up to 24%. Their goal is 30%; today's one-sided silicon cells are in the 14% range. Though 20% has been achieved before, getting there required costly materials such as gallium arsenide, expensive processing, or elaborate concentrators that focus light onto the cells' surface.

The key to the high efficiency that Konstanze Jäger and Rudolf Hezel have achieved at the university's Institute for Materials Research in Erlangen is true double-faced construction. Light hits not only the cell's front, but also is reflected onto the specially prepared back surface. Thus, depending on the background, the cell's efficiency is 15% on its

front and 13% to 14% on its rear surface. The two values do not exactly add up but amount to 20% to 24% depending on how the cell is positioned.

The difference between the Erlangen bifacial cell and others developed elsewhere is in the fabrication. The others use elaborate and expensive high-temperature techniques; the Erlangen process is a simple one that involves very thin silicon and low-temperature doping steps. Hezel, the head of the Semiconductor Technology and Photovoltaic Research Group, will discuss it at the 19th IEEE Photovoltaic Specialists Conference in New Orleans, May 4-8.

Like a one-sided cell developed earlier at Erlangen [*Electronics*, Aug. 7, 1986, p.38], the bifacial version depends on a


silicon-nitride inversion layer for its operation. But it uses a single- or polycrystalline silicon substrate so thin that the finished cell is only 50 to 80 μm thick, five to eight times thinner than the earlier cell.

The cell's rear side is passivated with a silicon nitride insulator film that limits the recombination of charge carriers. This permits the light incident on that side to be used for the photovoltaic conversion at only 10% less efficiency than that obtained at the front. The transparent film serves as an antireflection layer and also guards the cell against foreign matter, particularly moisture.

The contribution of the rear surface, Jäger explains, depends on the background's reflection capacity, measured as a ratio of the backscattered light to the light perpendicularly hitting the surface. For both snow and clouds, she says, the value is up to 0.9, for chalk it is 0.85, and for water the ratio can reach 0.7.

The cell's thinness has several advantages, Hezel says. It uses less silicon and is lighter—a big plus for solar panels in space. Also, the cell's operating temperature is reduced, and therefore its efficiency increased, because the sunlight's infrared components go through the cell without being absorbed.

—John Gosch



SUNNY SIDE UP. Bifacial solar cell is made with thin silicon and low-temperature doping and offers up to 24% efficiency.

Of course.

...in terms of lumens or lux, the sun is the brightest source. However, in terms of smart power technology and power silicon system design know-how, it's hard to find a brighter power than SGS.

The industry itself has long acknowledged SGS' position as a leader. SGS power transistors and integrated circuits like the well established TDA 2005 audio amplifier or the L298 dual H-bridge motor driver have become industry standards, as have packages like the Multiwatt® and many others.

The brighter source is the one that can turn power system design ideas into silicon. That's why automotive, telecommunication, computer, peripheral, audio and video manufacturers look to SGS for realistic solutions to tough power problems.

We think it's time you looked into SGS. After all, the brighter your semiconductor source, the brighter your design's future.

Contact your nearest SGS sales office now.



The brighter power™


CORPORATE HEADQUARTERS • SGS Microelettronica SpA, Via C. Olivetti 2 - 20041 Agrate Brianza - Italy. Tel: 039-65551 Telex: 330131-330141 SGSAGR
SGS is present in Australia, St. Leonards, Tel: 02-4385388 • Benelux, Eindhoven (NL), Tel: 040-433566 • Brazil, São Paulo, Tel: 011-883-5455 • Denmark, Herlev,
Tel: 02-948533 • France, Montrouge, Tel: 01-47460800 • Hong Kong, Hung Hom, Kowloon, Tel: 03-644251/6 • India, New Delhi, Tel: 6414537 • Italy and South
Europe, Assago (MI), Tel: 02-8244131 • Japan, Tokyo, Tel: 03-3788161 • Korea, Mapo (Seoul), Tel: 02-7167472/3 • People's Republic of China, Beijing, Tel: 507766
Singapore, Tel: 482-1411 • Spain, Madrid, Tel: 01-7337043 • Sweden, Märsta, Tel: 0760-40120 • Switzerland, Grand-Saconnex (Genève), Tel: 022-986462/3 • Taiwan-
Republic of China, Taipei Sec 4, Tel: 2-772 8203 • United Kingdom, Aylesbury, Tel: 0296-395977 • USA, Phoenix, Tel: (602) 867-6100 • West Germany, Grafing bei
München, Tel: 08092-690.

® Multiwatt is a trademark of SGS. © 1987 SGS. All rights reserved. ® SGS is a registered trademark of the SGS Group. ™ The brighter power is a trademark of SGS.

Circle 112 on reader service card

WOULD YOU BELIEVE IT'S
THIS SMALL?

(IT IS.)



**LARGE CAPACITANCE
0.047F**

FOR MEMORY BACK UP

Murata's economical Ace Cap™ is the smallest capacitor series with the highest capacitance per unit area (0.018F to 0.1F). The rugged, resin-sealed design is impervious to detergent washing. Available with straight and crimp-type leads, Ace Cap™ gives greater circuit design flexibility.

- Applications: IC Memory backup in personal computers and many other types of equipment.
- Specifications: Capacitance: 0.018-0.1F
Rated voltage: 5.5V
- Dimensions: 11mm dia × 6.5mm H (0.047F type)
12.5mm dia × 7mm H (0.1F type)

Electronic Double Layer Capacitors

Compact AC 200 Series

ACE CAP™

For further information, contact:

muRata
MURATA MFG. CO., LTD.

HEADQUARTERS	26-10, Tenjin 2-chome, Nagasaki-kyo, Kyoto 617 Japan	Phone: 075-951-9111	Telex: 64270 MURATA J
MURATA ERIE NORTH AMERICA, INC.	2200 Lake Park Drive Smyrna, Georgia 30080-7604, U.S.A.	Phone: 404-436-1300	Telex: 542329
MURATA ELEKTRONIK GMBH (West Germany)	Holbeinstrasse 21-23 8500 Nurnberg 70, West Germany.	Phone: 0911-66870	Telex: 623763
MURATA ELECTRONIQUE, S.A. (France)		Phone: 03-024-6767	Telex: 699954
MURATA ELETTRONICA S.P.A. (Italy)		Phone: 02-607-3786	Telex: 330385
MURATA ELECTRONICS (UK) LTD. (England)		Phone: 0252-523232	Telex: 858971
MURATA ELECTRONICS SINGAPORE (PTE.) LTD. (Singapore)		Phone: 2584233	Telex: 21127
TAIWAN MURATA ELECTRONICS CO., LTD. (Taiwan)		Phone: 042-91-4151	Telex: 27571 MURATA
MURATA ERIE N.A., INC. (Taiwan Branch)		Phone: 02-562-4218	Telex: 27571 MURATA
MURATA COMPANY LTD. (Hong Kong)		Phone: 0-4992020	Telex: 56208
MURATA MFG. CO., LTD. Seoul Branch (Korea)		Phone: 730-7605/730-7321	Telex: 25858

**IT'S TIME
TO GET OUT
OF THE DARK.**



Open your eyes and see just how many subjects are covered in the new edition of the Consumer Information Catalog. It's free just for the asking and so are nearly half of the 200 federal publications described inside. Booklets on subjects like financial and career planning; eating right, exercising, and staying healthy; housing and child care; federal benefit programs. Just about everything you would need to know. Write today. We'll send you the latest edition of the Consumer Information Catalog, which is updated and published quarterly. It'll be a great help, you'll see. Just write:



**Consumer Information Center
Department TD
Pueblo, Colorado 81009**

A public service of this publication
and the Consumer Information Center of the
U. S. General Services Administration.

Spectrum Analyzer FSA

100 Hz to 1.8 (2) GHz

The Spectrum Analyzer FSA features not only low inherent noise, 10 dB better than comparable instruments, but it also sets new standards regarding phase noise, dynamic range, intermodulation, level and frequency accuracy.


A state-of-the-art microprocessor concept ensures measurement versatility combined with ease of operation.

IEC 625 Bus

IEEE 488



- Amplitude-measurement range -145 dBm (-150 dBm typ.) to +30 dBm
- Phase noise < -114 dBc/Hz at 1 kHz from carrier
- Resolution bandwidths 6 Hz to 3 MHz quasicontinuously variable
- 9-inch colour monitor
- Optional tracking generator for 100 Hz to 1.8 GHz with built-in attenuator



Please ask for the data sheet
Spectrum Analyzer FSA

Rohde & Schwarz
Postfach 80 14 69
D-8000 Muenchen 80
Federal Republic of Germany
Telex 523 703 (rus d)
Tel. internat. + (49 89) 41 29-0



ROHDE & SCHWARZ

Circle 114 on reader service card

PROBING THE NEWS

WHY IBM'S NEW PS LINE IS GOOD NEWS TO THE INDUSTRY

IT DOESN'T CLOSE PC MARKET, OPENS UP NEW BUSINESS, AND WILL BE LATE

by Tobias Naegele and Jeremy Young

NEW YORK

For months, April 2 was circled in red on most computer industry calendars. That was widely expected to be Introduction Day for IBM Corp.'s new line of personal computers. Rumors ran wild before the announcement that the Armonk giant was going to move from an open to a closed system. The new machines were going to be clone-killers, difficult if not impossible for other manufacturers to copy. And there was plenty of speculation that IBM would bring out a proprietary operating system that would both stymie competition and ultimately cut Microsoft Inc.—supplier of PC-DOS, the PC operating system—out of the picture.

But IBM's new Personal System/2 ends up being mostly good news for the electronics industry. Most important, the new line will effectively keep the huge PC market wide open for competition. It should also generate several new submarkets. The computer industry was also happy because it sees the computer giant primarily targeting Fortune 1,000 companies and concentrating less on the personal and small business markets. On top of that, IBM is not being very aggressive either on prices or delivery schedules. It will be July before the high-end 386-based system is shipped, and the operating system that puts its power to use won't arrive until early

next year. Pricing starts at \$1,600, a far cry from the less than \$1,000 now being charged for many PC clones.

While parts of the new machines will call for some fast engineering before copies can be built, the obstacles do not appear to be insurmountable. Both operating systems for the new machines, PC DOS 3.3 and the new multitasking OS/2, are from Microsoft, which can sell them to all comers. Even under OS/2, the new machines will run programs written for PC-DOS, so users of the old PCs can bring their old software to the new machines, a big advantage from their point of view.

GRAPHIC IMPACT. The feature that promises to have the broadest impact is a combination of built-in graphics hardware and a graphics-based user interface based on Microsoft's Windows software. Together, IBM and Microsoft have set a new graphics standard for personal computers that takes on Apple Computer's Macintosh in terms of functionality and wipes away the confusion that plagued earlier generations of IBM PC graphics. Software houses can now focus their efforts on the new standard, and the result is likely to be a large body of programs as easy to use as Macintosh software.

At the same time, the graphics hardware, called VGA, for video graphics array, is going to make chip manufactur-

ers and board-level subsystem builders scramble. Clone-builders will need VGA-compatible chips; owners of PC ATs and AT clones will want VGA-compatible cards so they can run software written for OS/2 at the same level of resolution, 640 by 480 pixels. Markets for both chips and boards will develop rapidly.

All four models of the Personal System/2 (see chart) have built-in 640-by-480-pixel graphics, although the low-end Model 30 has a watered-down version with only two-color capability. Nor does it share the new expansion bus IBM has developed: the 32/16-bit Micro Channel, used in Models 40, 50, and 80. All four machines, however, move to 3½-in floppy-disk drives similar to those in IBM's Convertible portable computer.

The new line spans a broad range of performance. The various models make use of three different Intel microprocessors and offer hard-disk drives from 20 to 115 Mbytes in size. The Model 30 is built around an 8-MHz 8086 and has a 20-Mbyte hard disk; Models 40 and 50 are based on 10-MHz 80286s and a choice of hard-disk drives; and the Model 80 sports either a 16- or a 20-MHz 80386 processor to cap the power spectrum. All are available now except the Model 80, due for shipment in July.

However, the full potential of the 286- and 386-based machines will not be unleashed until early next year, when IBM

delivers the multitasking OS/2 operating system. OS/2 allows the 286 and 386 to run in the more powerful protected mode, in which they can address a full 16 Mbytes of memory. OS/2 also brings into full play the new graphics interface, which will be bundled into it as the Windows Presentation Manager.

So users will not see the full benefits of either the powerful microprocessors or the graphics environment until OS/2 and applications software written for it hit the market. That gives the mak-

IBM DEFINES A NEW WORLD FOR THE PC INDUSTRY

	Micro-processor (clock rate)	Potential system throughput	Standard memory	Floppy disk size	Available hard disk drives (Mbytes)	Operating system(s)	Base price (without monitor)
			Expandable to (Mbytes)	Capacity (Mbytes)			
Model 30	8086 (8 MHz)	up to 2½ times PC XT	0.640 —	3½" 0.720	20	PC DOS 3.3	\$1,695
Model 50	80286 (10 MHz)	up to 2 times PC AT	1 7	3½" 1.44	20	PC DOS 3.3, OS/2	\$3,595
Model 60	80286 (10 MHz)	up to 2 times PC AT	1 15	3½" 1.44	44, 70, 115	PC DOS 3.3, OS/2	\$5,295
Model 80	80386 (16 or 20 MHz)	up to 3½ times PC AT	up to 2 16	3½" 1.44	44, 70, 115	PC DOS 3.3, OS/2	\$6,995
PC AT	80286 (8 MHz)	—	0.256 0.512	5¼" 1.2	20	PC DOS 3.0, 3.1, 3.2, 3.3, OS/2	\$4,595

SOURCE: IBM CORP.


ers of compatible systems plenty of time to come up with competitive hardware.

Makers of IBM-compatible PCs feel that IBM has left them a lot of room to move. Among other things, they point out that IBM's lineup ignores the low end of the market, abandoning that segment to the companies that serve it best—the clones.

"I don't see anything that could be considered a 'clone killer,'" says Tandy Corp.'s Ed Juge, director of market planning at the Fort Worth, Texas, company. Michael Dell, chairman and founder of PC's Limited, a division of Dell Computer Corp. in Austin, Texas, says his company will produce PCs using IBM's Micro Channel bus architecture and VGA graphics within just nine months—roughly the time it will take for IBM and Microsoft to ready OS/2.

"We were not surprised by anything we saw," says Mike Swavelly, vice president for marketing at Compaq Computer Inc., by far the most successful builder of compatible hardware. "But we were surprised that IBM was not more aggressive in terms of pricing or performance of the product they introduced. I might also add that they were not very aggressive in terms of a delivery schedule."

The makers of compatible systems won't be the only ones burning the midnight oil. Vendors who make add-on boards for PCs, particularly those that specialize in graphics subsystems, are going to be working overtime to adapt to IBM's new world.



HIGH END. Model 80, shown with a 16-in. display and an external 5¼-in. floppy-disk drive, tops IBM's Personal System/2 line.

The new IBM products have made this expansion-board market a whole new ball game, says Kimball Brown, a computer analyst at Dataquest Inc. in San Jose, Calif. "The whole idea is to get OS/2 to run on current cards of 80286 and 80386 boxes," he says. "As they sit, they will not run OS/2." There are two ways to do this, he says: hardware vendors will try to tweak their boards for the VGA standard, while software companies will try to write programs compatible with Windows 2.0 and the Windows Presentation Manager.

Eager as they are, board and system makers may not be able to get to work

right away. IBM is not making hardware manuals for the new systems available until mid-May, and the full specification for the Micro Channel bus will not be forthcoming until August. Board makers will have to wait for this information, says Howard Charney, engineering vice president of 3Com Corp., Mountain View, Calif., which makes Ethernet cards for IBM PCs. They will also have to wait for new chips, he points out.

Notably, companies that had been using standard graphics controllers on their boards are likely to find themselves searching for new parts that allow them to emulate the VGA. "I think the graphics improvements and enhancements over the EGA [Enhanced Graphics Adaptor] will prove to be a killer in the graphics controller market," says Ahmed Nawaz, graphics chip marketing manager

for Texas Instruments Inc., Houston. "The flexibility and programmability of the new IBM machines will mean death to the hardwired controllers as users move beyond the EGA."

Competition will be fierce in the rush to respond to IBM. Paradise Systems Inc., San Francisco, says it will have a single-chip video controller compatible with VGA within 90 days. The stakes are high: Dataquest's Brown says that if a company like Paradise can make a VGA look-alike, "they could be a \$100 million company in a year."

Additional reporting by J. Robert Lineback and Clifford Barney

MICROSOFT PULLS ANOTHER WINNER OUT OF THE HAT

Reports that IBM Corp. would be abandoning Microsoft Corp. have been greatly exaggerated. IBM's dependence upon the Redmond, Wash., company for basic software for its new Personal Systems is greater than ever. Microsoft assured its position as a leading microcomputer software company when it provided the operating system to IBM for the first IBM PC back in 1981. The subsequent success of the IBM PC established the operating system IBM PC-DOS and the MS-DOS version offered by Microsoft as the industry standard.

The latest announcements from Microsoft and IBM clearly establish a close and enduring relationship between the two companies. The system software offerings cement Microsoft's standard-bearer role in microcomputer operating software. Microsoft is now not just supplying the PC-DOS and OS/2 operating systems for the Personal System/2

products, but also the user interface and basic graphics software.

OS/2 is a "very full-blown" multitasking operating system supporting shared memory, threads, queues, and advanced scheduling, says Bill Gates, chairman of Microsoft. It takes up at least 400 Kbytes of memory, calling for a system memory of at least 2 Mbytes, preferably four. An application written for the MS-DOS environment can run as one of OS/2's tasks. "OS/2 is the biggest piece of work we've ever done," says Gates.

The Microsoft Windows Presentation Manager is included as part of OS/2, which both IBM and Microsoft will be offering. This will firmly establish the new Windows and its graphics services as the user interface and graphics standards for the next generation of single-user microcomputers. OS/2 and the Windows Presentation Manager were developed under a joint development agree-

ment between Microsoft and IBM that began in 1985.

IBM's adoption of OS/2 alone would have been big news for Microsoft. But its endorsement of the Microsoft's Windows system in its second-generation form as the Presentation Manager is an even bigger boost. The inclusion of the Presentation Manager as an integral part of OS/2 virtually assures its status as an industry standard. IBM and Microsoft will use the Presentation Manager for their applications; third-party applications-software vendors are unlikely to try to buck that trend.

"From a hardware point of view, they [IBM] have done exactly what we wanted to make these machines good for a graphics interface," says Gates. "Two and a half years from now, virtually all office machines will use the graphics interface and OS/2."

-Tom Manuel

UNDER THOMSON'S WING, MOSTEK IS BEGINNING TO FLY

NOW GROWING TWICE AS FAST AS U. S. MARKET, IT AIMS TO HIT TOP 10 LIST

by J. Robert Lineback

CARROLLTON, TEXAS

Mostek is still haunted by memories—not the unprofitable dynamic random-access memories that once helped it lose an incredible \$1 million a day, but the industry perception that little remains of the one-time memory leader, which France's Thomson-CSF purchased in the fall of 1985. The industry seems unable to forget the staggering losses and the exodus of engineers that eventually derailed Mostek when it was part of United Technologies Corp.

But now the Carrollton, Texas, company has been successfully reincarnated as Thomson Components-Mostek Corp., a subsidiary of the French electronics giant. The slimmed-down Mostek is now set to launch a flotilla of CMOS products, including tailorable 16-bit microcontrollers, specialized fast static RAMs, enhanced telephone-dialer chips, local-area-network circuits, and an entire family of large semicustom logic arrays using sea-of-gates technology.


Mostek's new 1.2- μ m CMOS logic arrays will contain as many as 127,680 gates, with upwards of 57,000 being routable. By June, Mostek plans to start shipping prototypes of a 20,000-routable-gate array containing a sea of 45,000 continuous gates. Thomson engineers in France are working with Mostek to create products that allow customers to use LSI-level macrocell functions when designing with these arrays.

Now fueled by technology developed for fast SRAMs, the Mostek subsidiary is also taking the lead on Thomson's forthcoming 1.2- μ m double-level CMOS process, which is earmarked for a new wave of chips, including digital signal processors and 64-Kbit SRAMs, as well as for build-to-suit foundry business. In addition, Mostek plans to start running a three-level-metal 0.8- μ m process at its Fab 6 research and development center this year.

With the \$71 million purchase of selected Mostek assets, Thomson has gained a key foothold in U.S. markets and an American fabrication presence, says Kathleen Killian, a London-based analyst for Dataquest Inc., San Jose, Calif., who tracks the French electronics giant. "It also got a world-class mask-making facility [capable of 0.5- μ m geom-

etries] and an automated diffusion center in Carrollton," she says.

Clearly, what was United Technologies' loss is Thomson's gain. Following a dramatic metamorphosis, Mostek turned an unexpected profit of \$1.1 million in 1986, partly on the sale of unneeded assets and partly on sales of a product portfolio in which commercial DRAMs are conspicuously absent. That compares with a loss of \$328 million in the first 10 months of 1985, when Mostek was still part of United Technologies. Now, Mostek executives expect the unit to become operationally profitable by the end of the year. "We



FIEBIGER: Mostek is on track with its plans to grow twice as fast as the U. S. market.

are right on track with our plans to grow at more than twice the rate of the U.S. market," says James R. Fiebigler, president and chief executive officer of Mostek. At that growth pace, Fiebigler figures the subsidiary will grab 2% of North American chip sales by 1990. Mostek will also sell semiconductors fabricated by sister Thomson operations, and it will keep a finger on the pulse of IC engineering trends in the U.S. Thomson is counting heavily on Mostek to help it make the Top 10 list of global semiconductor suppliers by the beginning of the next decade.

In the latest move to increase its size, Thomson has agreed to merge its nonmilitary chip-making operations with SGS Microelettronica of Italy, pending approval by the French and Italian governments

[*Electronics*, April 2, 1987, p. 55]. The merger would not have much effect on Mostek, since there is little overlap between it and SGS, says Michel Motro, international vice president at Thomson Components. But he does expect the SGS sales force to strengthen Mostek's international marketing resources.

Back in Texas, Mostek has begun untangling the maze of different MOS processes that evolved during the six-year stint with United Technologies. To Fiebigler's dismay, the task of standardizing Mostek's process technologies has proven to be a major task in itself. "When we got into the consolidation phase, we found out we had 68 different process flows for 80 products," Fiebigler groans. He was recruited from Motorola Inc.'s Semiconductor Sector by United Technologies shortly before Thomson stepped in.

During the United Technologies era, some products were even running on more than one wafer line, and thus being produced with dissimilar processes. Fabrication engineers would often attempt quick fixes to get designs to work and to boost yields. And while the proliferating morass of process flows was bogging down yields, prices were nose-diving in saturated commodity markets.

"We nearly had a unique process for every product," Fiebigler recalls. Today, Mostek has reduced the number to 20 process flows for about 90 products. It is now aiming to be down to just a dozen process flows by mid-summer. "The yields we are running today are at levels that previous management thought were impossible until the 1989 timeframe," he says, saying as many as 90% of the processed dice are now good when probed. Also, Mostek and Thomson operations are standardizing on a common 1.2- μ m CMOS process developed by the Carrollton operation.

Few of Mostek's new designs were in working order at the time of Thomson's purchase. Executives at Thomson in France and at Mostek moved in to reorganize the company's semiconductor strategy, carving up and consolidating product lines into centers of expertise at either Mostek or Thomson. Now Mostek is focusing on fast SRAMs, specialized static memories, chips packaged with embedded lithium battery cells, gate ar-

rays, networking chips, telephone dialers, and 16-bit microcontrollers. Thomson engineers in France have been given responsibility for microprocessors, erasable programmable read-only memories, telecom chips other than dialers, digital signal processors, smart power devices, and standard-cell parts.

In the microcontroller market, this month Mostek is unveiling a redesigned CMOS version of its three-year-old 16-bit MK68200 [*Electronics*, Apr. 2, 1987, p. 22]. The chip's speed has been doubled, and the die has been laid out in a modular fashion so customers will eventually be able to tailor the chip.

In telecom markets, Mostek will introduce a new line of enhanced dialer chips. For data networking, the company is working on additional ICs for the Starlan local-area network. The company expects

After losing \$1 million a day in 1985, Mostek made money last year

it will be able to provide samples of a variable-bit-rate LAN chip by midsummer.


In fast SRAMs, Mostek continues to emphasize six-transistor cell designs for low power. Spinoffs of standard SRAMs are targeted at first-in, first-out market segments, traditional areas for Mostek. The new 1-K-by-5-bit MK4505 FIFO, which is about three times faster than Mostek's older 4501 chip, is due soon. The SRAM operation also recently secured a critically needed second source for its specialty memories in a strategic pact with VLSI Technology Inc. of San Jose, Calif. Under the agreement, Thomson—along with Mostek—and VLSI Technology will second-source parts from each other, including FIFOs, dual-ported RAMs, cache-tag memories, and battery-backed SRAMs. The Mostek operation also continues to sell DRAMs in military markets, including a new 256-Kbit chip.

Excluding the unprofitable commercial DRAMs, Mostek had 1985 sales of about \$50 million, according to Fiebigler. The operation's sales grew by about 20% in the U.S. last year, but more encouraging to Fiebigler were the size of orders and the arrival of new customers. "We more than doubled the number of accounts that were entering \$1-million-plus orders in 1986 compared to 1985. And that was in a time frame when chip customers were trying to reduce the number of their suppliers," adds Fiebigler.

Although Mostek's recovery now seems to be on track, Fiebigler does not expect to get a nod of approval from major IC customers until 1988, when "we have shown that this was a successful turnaround." □

"If you're a retired U.S. manager, you have a lot to give to the world."

Thorton F Bradshaw,
Chairman, RCA



I'm a volunteer supporter of the International Executive Service Corps, a not-for-profit organization with a vital mission:

We send retired U.S. managers overseas to help businesses in developing countries, which often respond by increasing their imports of U.S. goods. In fact, developing countries consume about 40 percent of U.S. exports.

As an IESC volunteer, you would not get a salary. But you would get expenses for you and your spouse, plus a world of personal satisfaction.

IESC leads the field in this kind of work. We've done over 9,000 projects in 81 countries. We could have a project that's just right for you. To find out, send this coupon to: Thorton F. Bradshaw, Chairman, RCA, P.O. Box 10005, Stamford, CT 06904-2005.



**International
Executive
Service Corps**

It's not just doing good.
It's doing good business.




Dear Mr. Bradshaw: Tell me more about becoming an IESC volunteer. I am a recently retired manager or technician — or am about to retire — from a U.S. company. I'm free to accept an overseas assignment. I understand that volunteers receive expenses for themselves and their spouses, but no salary.

Name _____


Address _____

City _____ State _____ Zip _____



RELIABLE SUPPORT FOR ISDN

Surviving in the complex and competitive world of ISDN will depend on vital problem-solving capabilities like quick



MP1601A 5GHz
Pulse Pattern Generator

response, quick recovery and preventive checking. This requires comprehensive monitoring, rigorous testing and exacting quality control of transmission systems.

Anritsu's accuracy, quality and reliability are based on decades of experience in electronics, optical technology and laser research. Our focus is on the advanced optical devices and test equipment necessary for ISDN.

Anritsu excels in optical and digital communication test systems. We have shown our commitment to quick response to practical ISDN applications by introducing high-resolution OTDRs, 5GHz pulse pattern generators, high-performance error rate measuring equipment for digital transmissions, and many more.

Anritsu also designs industrial automation systems, applying lasers in many new ways. Feedback from every area enables us to develop ground-breaking new products.

For any network, one name provides the reliable support to keep it running smoother...

Anritsu makes you a survivor.

Anritsu

ANRITSU CORPORATION

10-27, Minamiazabu 5-chome, Minato-ku, Tokyo 106, Japan
Phone: Tokyo 03-446-1111, Telex: 0-242-2353 ANRITU J

Circle 51 on reader service card

Score A Winning Touchdown with UMC



With backing from UNITED MICROELECTRONICS CORPORATION, one of our customers scored a winning touchdown with a voice control IC last year. He netted a profit of 2.5 million dollars on just one product. This is one of the many examples of how UMC helps its customers score financial goals.

UMC scored its first touchdown by becoming profitable 6 months after it went into operation and has been making a profit and registering phenomenal sales growth annually since then. Last year, 4 quarters of penalties left most companies sitting on the bench and several others were ejected from the game. UMC, however, still romped to a sales growth rate of 24.4%, which was the fourth best in the world and outscored 92% of the IC industry.

If you want to be on a winning team, go with a proven winner.....UMC.



UMC

UNITED MICROELECTRONICS CORPORATION

CORPORATE HEADQUARTERS: NO. 3, INDUSTRIAL EAST THIRD ROAD SCIENCE BASED INDUSTRIAL PARK, HSINCHU CITY, TAIWAN, REPUBLIC OF CHINA
SALES OFFICE: 9TH FLOOR, NO. 201-26, TUNHUA NORTH ROAD TAIPEI, TAIWAN, REPUBLIC OF CHINA TEL: (02) 7152455 TLX: 28560 UMCTPE FAX: (02) 7166291
U.S.A. HEADQUARTERS: NMC CORPORATION 3054 SCOTT BLVD. SANTA CLARA, CA 95054 U.S.A. TEL: 408-7279239 TLX: 172730 NMC SNTA FAX: 408-9700548

INTERNATIONAL NEWSLETTER

NEC ASKS COURT TO BLOCK SALES OF SEIKO EPSON PC

The copyright dispute between Tokyo's NEC Corp. and Seiko Epson Corp. of Suwa [*Electronics*, April 2, 1987, p. 55] is now spilling into the courts. NEC says that Seiko Epson infringed on its rights with a personal computer that is fully compatible with NEC's PC-9801, Japan's best-selling personal computer, and the company has gone to court to ask for a provisional injunction to suspend sales of the disputed machine, Seiko Epson's PC-286. But NEC didn't stop there. The company also asked for a similar injunction stopping sales of Seiko Epson's 20-Mbyte external hard-disk drive, the HDD-20, a peripheral for NEC's PC-9801 that Seiko Epson began selling last December. NEC claims that software on the drive's interface board also violates its copyrights. Seiko Epson, meanwhile, says it plans to go ahead with delivery of the PC-286 late this month. □

TI JAPAN BEEFS UP BIPOLAR CAPACITY AND SIGNS ON ASIC PARTNERS

Texas Instruments Japan Ltd. of Tokyo is stirring things up in the Japanese chip market. TI is enlarging its manufacturing capacity for bipolar logic integrated circuits at its plant in Hiji, Oita, doubling output from around 22,000 advanced Schottky, advanced low-power Schottky, and TTL ICs per day to about 44,000. And the company is not ignoring its other business lines—TI Japan has signed Japan LSI Co., also of Tokyo, to act as a marketing arm and design center for TI's application-specific ICs and standard products. TI will provide Japan LSI with its standard-cell library but may also offer full-custom devices and gate arrays. The deal is TI Japan's second since November, when it signed Ascii Corp. of Tokyo to distribute graphic-system processors, digital signal processors, and other standard large-scale ICs [*Electronics*, Nov. 27, 1987, p. 48]. □

HITACHI TAKES AIM AT NETWORKS WITH HIGH-BIT-RATE LASERS

A multiple-quantum-well semiconductor laser with the 30-MHz resonant frequency needed for modulation rates up to about 11 Mbit/s has been developed at the Central Research Laboratories of Hitachi Ltd. This high-speed response will be needed for faster communications, including telephone company trunk lines, value-added networks, and local-area networks. Hitachi is using selective ion doping to speed the electron transitions that drive the laser for faster response. Initial work has involved gallium arsenide and aluminum gallium arsenide to fabricate lasers that operate in the 0.8- μm band. But light-scattering losses are lower at wavelengths of 1.3 and 1.5 μm , so Hitachi researchers plan to apply the new technology to indium gallium arsenide phosphide/indium phosphide lasers that will operate in the 1.3- μm band, and InGaAs/InP lasers for the 1.5- μm band. □

NEW VENTURE AIMS TO MAKE LCDs WITH 1,000-LINE RESOLUTION

Image Displays Ltd.—a new joint venture of London-based STC plc, Alcatel NV of the Netherlands, and venture capitalists—is aiming to turn the liquid-crystal-display market on its ear with a line of smart, high-resolution displays based on Smectic A technology. STC says the displays will be the first LCDs available to offer a full 180° viewing angle, and they will also have on-screen memory, meaning the screens will not need refreshing every 200 lines as do conventional LCDs. That will help Image Displays to produce screens with more than 1,000 lines resolution, much higher than is currently available. Samples of the new display will be available from STC Technology Ltd. in Harlow, England, this year, but production displays will not be available until next year, when a new production facility in Cambridge will be ready. □

INTERNATIONAL NEWSLETTER

NEC PAIRS A MES FET WITH AN INDIUM PHOSPHIDE PHOTODIODE

A new heterogeneous substrate, made by growing gallium arsenide epitaxially on selected areas of an indium phosphide wafer, is providing researchers at NEC Corp.'s Ultra High Speed Device Research Laboratory with a new way to build optoelectronic integrated circuits. The first device includes an InP PIN photodiode, a gallium arsenide metal semiconductor field-effect transistor, and load resistors for the diode and the transistor. The PIN diode provides a high-sensitivity photodetector in the 1.3- and 1.5- μ m optical communications bands. The development is a boon to NEC, because it allows the company to build on its experience with GaAs technology. The company says it might otherwise take years to develop complex ICs on InP substrates, because that technology is so new and there is no commercial experience on which to build. ☐

WILL WEST GERMANY OPEN UP THE MARKET FOR TERMINAL EQUIPMENT?

Bowing to pressure from the U. S., West Germany's communications authority, the Bundespost, is considering new regulations that would make it easier for foreign companies to sell terminal equipment used in public networks. The regulations, which could go into effect this fall, would relax acceptance procedures so that foreign suppliers without domestic standing would be on equal footing with native German suppliers. The rules also seek to shorten the arduous approval process from as much as a year or longer to as little as four months. The U. S. has pressed West Germany in recent years to open its terminal market to foreign producers, but the Germans have maintained that the U. S. already enjoys a trade surplus for communications equipment. The Bundespost says the U. S. registered big surpluses in the past three years—\$140 million in 1984, \$145 million in 1985, and \$130 million during the first eleven months of 1986. ☐

BASF TAPE CARTRIDGE PACKS 2 GIGABYTES—BUT YOU CAN'T BUY A DRIVE

Anticipating the kind of high-density backup tape drives users will be demanding in about two years or so, West Germany's BASF AG has developed a tape cartridge that holds as much as 2 gigabytes—about 10 times the capacity of most current cartridges. The 185-foot-long, 1/2-in.-wide chromium-dioxide tape will not find a use for some time, however, since drive equipment for the new cartridges will not be available until late 1988, according to BASF, of Ludwigshafen. BASF achieved the high density step by step. By doubling the number of tracks on the tape from 18 to 36, doubling the write density from 24,000 to 48,000 flux changes/in., halving the thickness of the tape itself—thus permitting more tape in the cartridge—and developing data-compression techniques, BASF achieved its goal of putting 2 gigabytes of data on one cartridge. ☐

WILL TOSHIBA AND SANYO JOIN THE LASER VIDEODISK CAMP?

Competition between laser-disk players and capacitive-pickup video home disk players in Japan is heating up, as Toshiba Corp. and Sanyo Electric Co. begin to straddle both camps. Since 1983, Toshiba, of Tokyo, has offered VHD machines; now the company is starting to market a combination player for laser video disks and audio compact disks made by Pioneer Electronic Corp., also of Tokyo. Toshiba was attracted to the laser-based video system by the advent of the compact disk with video, a new CD format called CD-V [*Electronics*, March 19, 1987, p. 53]. Sanyo, of Osaka, is also expected to sell a laser video/CD audio player. Toshiba says it expects to sell as many as 1,000 to 2,000 a month in Japan. ☐

INTERNATIONAL WEEK

COMPONENTS MARKET FLAT IN W. GERMANY

West Germany's electronic components market, after scoring 26.3% and 13.2% sales gains in 1984 and 1985 and registering a loss of 0.6% last year, is expected to recover only moderately in 1987 and 1988. The Central Association for the Electrotechnical and Electronics Industry now predicts sales gains of only 3.5% this year and 3.3% in 1988. That would bring total components sales to 11.6 billion DM, or \$6.44 billion, in 1987 and 12 billion DM, or \$6.66 billion, in 1988. Over the long run, the Frankfurt association is more optimistic: it expects average sales growth in the 1990s of about 10% a year as more data-processing and communications services become available.

TOSHIBA'S LSI CENTER OPENS IN HONG KONG

Toshiba Corp. of Tokyo is setting up an LSI design center in Hong Kong to create new demand for its semicustom LSI chips and to give greater support to equipment manufacturers in Southeast Asia. The center, the company's first in Southeast Asia and the seventh outside Japan, will be based at Toshiba Electronics Asia Ltd., a wholly owned sales subsidiary in Hong Kong. It will be going after an Asian semiconductor market estimated this year to be \$2.73 billion, or 400 billion yen, with Hong Kong accounting for 20%, industry sources say.

IBM JAPAN SLIPS TO THIRD PLACE

Sales of IBM Japan Ltd. in 1986 dropped for the first time since the Tokyo company was established in 1950. Consequently, IBM will fall from second to third place in sales among Japanese computer companies, behind Fujitsu and NEC. IBM's sales for 1986 were \$5.99 billion, or

878.5 billion yen, a decline of 3.9% from \$6.24 billion, or 914.2 billion yen, in 1985. An IBM spokesman attributed the slack sales mainly to the stronger yen. Domestic sales fell by 2.4% from \$4.49 billion, or 658.8 billion yen, to \$4.39 billion, or 643 billion yen, and international sales dropped by 8% from \$1.75 billion, or 256 billion yen, to \$1.6 billion, or 235.5 billion yen. Net income in 1986 was \$436 million, or 63.9 billion yen, a 12.4% decrease from \$497 million, or 72.9 billion yen in 1985.

AMORPHOUS METALS PACT SIGNED

Vacuumschmelze GmbH, a West German producer of metals for the electronics industry, and Allied Corp. of Morristown, N.J., have signed a deal to license to each other the technologies needed to make amorphous metals for magnetic applications. Hanau-based Vacuumschmelze will make available its technology for producing the soft-magnetic material Vitrovac. Allied Corp. will provide its know-how in making Metglas, a similar material. Both materials are used in high-frequency components and other electronic parts.

SIEMENS U.S. SALES EXPECTED TO RISE

Siemens AG expects its U.S. sales to increase from \$2.2 billion in fiscal year 1986 to \$2.6 billion in 1987. As much as 85% of that business will come from products and services it manufactures or generates in the U.S., which make the Munich company relatively safe from the low value of the dollar compared with major European currencies, including the deutsche mark. Most of the increase will be in the medical electronics and energy-and-automation sectors, each of which accounts for 40% of the company's total U.S. sales. The

remaining 20% comprises communications and data-processing equipment and components.

SATELLITES TO BRING UK TV TO EUROPE

British Telecom has signed two agreements to allow it to distribute UK television programs by satellite into Europe. The pact with Eutelsat is for up to eight transponders on the Eutelsat 2 medium-powered satellite to be launched in late 1989. The second pact, with Société Européenne des Satellites of Luxembourg, is for up to 11 transponders on its Astra satellite to be launched next year. British Telecom estimates that the extra power from these satellites will allow its programs to be picked up on dishes as small as 60 cm in diameter in an area bordered by Edinburgh, Stockholm, Milan, and Bordeaux.

NIXDORF GETS BIGGEST ORDER EVER

Nixdorf Computer AG, West Germany's No. 2 data-processing equipment maker after Siemens, has bagged the biggest order in its 19-year history. Valued at \$167 million, the order from the German Federal Labor Office is to computerize 90 of its employment offices. The equipment being used is the Nixdorf Targon/32 product family, which runs under Unix. The labor office chose Nixdorf in part because its multi-computer configuration offers fault-tolerant operation.

MATSUSHITA OPENS W. GERMAN PLANT

Japan's Matsushita group is expanding its manufacturing base in West Germany with a new plant in Neumünster. The group now has seven manufacturing sites in the country, most in the office equipment sector. The Neumünster plant, part of Matsu-

shita Business Machines GmbH, will produce nearly 36,000 copying machines this year. Production will be cranked up next year to 10,000 units a month. The Japanese group has a 4% share of West Germany's market for copying machines and is aiming for nearly a 6.5% share next year.

SIEMENS INTRODUCES UNIX-BASED SYSTEM

With the introduction of its Unix-based multiuser computer system, MX500, Siemens AG hopes to regain its No. 1 position among Europe's Unix systems suppliers, a position it lost last year to Altos Computer Systems of San Jose, Calif. On its home market, the Munich company has installed more than 12,000 computers using its operating system Sinix, for Siemens Unix. The MX500 serves up to 32 display-based work stations and ranges at the lower end of the performance scale for general purpose computers. It works with National Semiconductors' NS32032 32-bit processors. The price of the computer system starts at about \$10,000 and goes up to \$200,000, and deliveries will start in May.

UK CHIP FIRM SIGNS ASIC PACT WITH ES2

Microtech Semiconductors Ltd. has signed a deal with the pan-European ASIC start-up European Silicon Structures for development and assembly work in the UK for ES2. Microtech, which is based in Alton, UK, plans to do a five-day turnaround for the new ES2 custom designs. Microtech was chosen because its test facility has full military approval. The move is another step in ES2's plan to expand in the European ASIC market, following hard on the heels of its link-up deals with Mullard, Texas Instruments, and Gothic Crelion.

INTERNATIONAL PRODUCTS

OP AMP AND PHOTODIODE SQUEEZE INTO 8-mm PACKAGE

INTEGRATED PHOTOMATRIX PHOTODETECTOR AIMED AT NOISY ENVIRONMENTS

Integrated Photomatrix Ltd.'s 10500 family of photodetectors squeezes an operational amplifier and a silicon photodiode into an 8-mm-diameter package to reduce signal degradation in electromagnetically noisy environments.


A feedback circuit is used to maintain direct proportionality between the amplifier's output and the photocurrent produced by the n-MOS p-diffusion photodetector, says Keith Hopper, product manager. Noise levels in the four off-the-shelf parts vary from 0.3 mV for the 5-mV-output 10500A to 0.75 mV for the 10-mV-output 10500D.

Besides giving original-equipment manufacturers a means of circumventing the communications problems inherent in the low-voltage signals typical of photodetectors, the Dorchester, UK, company has enhanced its hybrid products by offering flexibility in the 10500 family's frequency response, output voltage, and packaging.

CUSTOMIZING. "If a customer wants a customized device with a 1-to-15-kHz frequency response, for example," says Hopper, "we are willing to provide it by changing the capacitor-resistor combination in the feedback circuit." In the standard parts, the 10500A offers a frequency response of 200-300 kHz; the 10500B, 0.6-0.9 kHz; the 10500C, 80-120 kHz; and, the 10500D, 65-100 kHz. Research is underway to extend frequency response into the 10-MHz range.

The voltage output and the signal-to-noise ratio can be increased by a factor of approximately 10 by replacing the photodetector's standard glass window with an optional lens, says Hopper. The company is also prepared to supply versions suitable for surface mounting, he says, but will "react to market interest." The off-the-shelf parts come in standard TO5 packages.

Although the devices' spectral response peaks at a wavelength of 850 nm, filters are available that shift the peak up or down the spectrum. The company's BG-18 filter, for example,



VERSATILE. The 10500 photodetector targets such applications as photocopying machines and industrial position-sensing systems.

produces a peak response similar to that of the human eye, says Hopper.

The 10500 series targets applications such as photocopying machines, where the sensor can be used in the peak black/white monitoring that is the heart of the optical-scanning subsystem. It can also be used in industrial position-sensing systems, says Hopper.

The standard 10500 photodiodes offer responsivity characteristics of 2.7, 10, 20, and 27 mV/ μ W/cm² for the A, B, C, and D, respectively. Their active area is 1.75 mm². The diodes are available now.

They cost £9 each in quantities of 10 or fewer.

In addition to the 10500, Integrated Photomatrix will introduce ten other 10000 Series devices at the British Electronics Week show. Most are available in standard or surface-mount packages and can be supplied in an array made to customer specifications.

Included among the more interesting products is the 10130, which is divided into four quadrants—each a separate photodetector—and can be used for high-accuracy position sensing.

Its characteristics include a dark, or quiescent, current of 0.1 nA per quadrant; capacitance of 45 pF per quadrant; response time of 15 ns; and an active area of 0.66 mm² per quadrant.

As with the majority of 10000-family devices, the 10130 has a reverse breakdown voltage of 60 V and a peak spectral response of 800 nm.

The IPL10120 is a monolithic two element annular silicon photodiode for use in positioning applications. It has a dark current of 0.2-nA per quadrant, a capacitance of 100-pF per element, a response

UK'S BIGGEST SHOW KEEPS GROWING

LONDON

British Electronics Week—a combination of seven trade shows under a single banner—is the largest electronics exhibition held in the UK and ranks second in Europe only to West Germany's Electronica. More than 1,000 exhibitors are expected at the show from April 28 to 30 on London's Olympia fairgrounds.

Its largest component is the All Electronics/ECIF Show, from which the idea of British Electronics Week was spawned. The Automatic Test Exhibition and Conference has joined the fold for the first time after a successful solo run. Two others are completely new:

the Power Sources and Supplies Exhibition and Conference and the Electronic Subcontractors Show.

The remaining shows were included in last year's British Electronics Week. They are the Circuit Technology Exhibition, the Fibre Optics Exhibition, and the Electronic Product Design Show.

Organizer Evan Steadman plans to add a fifth-generation computer show to the event next year, and he has a number of major expansions planned for 1989, when the new Earl's Court exhibition center will be complete. "From 1990, I'll have Electronica firmly in my sights," says Steadman. — Steve Rogerson



time of 25-ns, and an active area of 1.37 mm² per element.

The smallest and fastest family member is the IPL10020, whose response time of only 4 ns makes it suitable for laser and communications applications. Its active area is only 0.66-mm². Its dark current is 0.1 nA, and its capacitance is 9 pF.

Prices for the products range from £2.50 for the 10020 to £50 for the IPL10130. Discounts are available on volume orders. These prices do not include the customized array work, which depends on the application. The devices are available now.

Integrated Photomatrix Ltd., The Grove Trading Estate, Dorchester, Dorset DT1 1SY, UK.


Phone 44-305-63673

[Circle 500]

REFLECTOMETER FOR SINGLE-MODE FIBERS

Cossor Electronics Ltd.'s OFL213S optical-time-domain reflectometer is designed for use with single-mode fibers. Its printer interface gives a permanent record of the screen read-out, including the cursor position and attenuation losses between specific events.

The OFL213S operates at a 1300-nm wavelength at distances up to 40 km. It weighs 8 kg and is battery-operated.



It can do automatic splice or connector loss measurements and displays its information on a liquid-crystal display and a cathode-ray tube. Attenuation can be resolved to better than 0.1 dB. The OFL213S is available now and costs £10,000.

Cossor Electronics Ltd., The Pinnacles, Harlow, Essex CM19 5BB, UK.


Phone 44-279-26862

[Circle 701]

FUSEHOLDERS ALMOST IMMUNE TO VIBRATION

An independent cap-lock mechanism makes Wickmann Components Ltd.'s Series 19800 fuseholders virtually vibration-proof.

Fabricated from self-extinguishing thermoplastic, the fuseholders' terminals are molded to improve rigidity. The devices hold 5-by-20-mm and 0.25-by-0.25-in. fuses and are rated for 250 V and 10 A. They are suitable for miniature fuse links and have a maximum power dissipation of 2.5 W.



Each fuseholder is tested for one minute at 4 kV and 50 Hz. Features include parallel contact pins, removable fuse carrier, low contact resistance (there only three contact points), and VDE approval.

The holders are available immediately and cost 30p each in volume.

Wickmann Components Ltd., Unit 1, Centech, Fringe Meadow Road, North Moons Moat, Redditch, Worcestershire B98 9NR, UK.

Phone 44-527-61022


[Circle 702]

RACKS OFFER ACCESS FROM ALL SIDES

The model VR series of IEC297/2 electronic racks for electric mains distribution from Rittal Ltd. provide easy access from all sides and are designed to be compatible with 19-in.-wide enclosure systems.

Safe cable entry is provided and either left- or right-hand door hinging is available. The racks can be linked into suites and are available with a smoked-glass door, an open front, or electromagnetic and radio-frequency protection.

All have a standard base and integrat-



ed leveling feet. Prices range from £332 to £519, and the racks are available four weeks after order.

Rittal Ltd., North Anston Trading Estate, North Anston, Sheffield S31 7JJ, UK.

Phone 44-909-56781

[Circle 703]

1-KW POWER SUPPLY HAS FIVE OUTPUTS

The 1-kW multioutput P1000 series of switched-mode power supplies from Advance Power Supplies Ltd. are available with either 110-V or 220-V inputs and a range of outputs. The main output is 5 V at 150 A. There is a choice of four other outputs: 5 V at 15 A, 12 V at 15 A, 24 V at 8 A, and 48 V at 5 A.

A top-of-the-line model with all five outputs will cost about £860. The company has also upgraded its Powermag family of power supplies to include a version with 5 V output at 300 A. This is the first British-designed and -made switched-mode power supply to provide that output from a single fan-cooled industry-standard 8-by-5-by-11-in. box. It costs £985.

Advanced Power Supplies also offers the Powerflex series of open-frame power supplies. The PB350 350-W version with a 24-V dc input costs £332, and the PD500 500-W version with a 48-V dc input costs £502. Both can have up to five outputs.

Advanced Power Supplies Ltd., Raynham Road, Bishop's Stortford, Herts CM23 5PF, UK.

Phone 44-279-55155

[Circle 706]

FIBER-OPTIC MUXES RUN 48 CHANNELS 2 KM

Fiber-optic multiplexers from Wadsworth Electronics Ltd. offer virtually noise-free communications for up to 2 km in 48- and 16-channel versions.

The 720-3240 48-channel multiplexers provide a full 48-bit parallel highway in both directions over 2-km distances at transmission rates up to 19.2-Kb/s on each channel. They cost £1,495 each and target such applications as color graphics and work stations.

The 720-3240 16-channel multiplexer can be configured to produce a multi-user system. It costs £1,295. The optical-fiber transceiver operates at 76.8 Kb/s and accepts full-duplex CCITT V.24 and RS-232-C asynchronous data from computer ports and peripherals.

Wadsworth Electronics Ltd., Central Ave., East Molesey, Surrey KT8 0QB, UK.

Phone 44-1-941-4716

[Circle 708]

TINY CONNECTORS ARE ONLY 5 mm IN DIAMETER

The MCX series of microminiature connectors from Greenpar Connectors Ltd. offers the smallest sizes available in SMB military- and industry-standard connectors.

Typical overall length of a mated pair of SMB connectors is 41 mm, compared with 30 mm for the MCX series. The body of the connectors is only 5 mm

square, and the diameter is also 5 mm, compared with 7 mm for a typical industry-standard model.

The bodies are made of brass with either nickel or gold plating. The male contact is also gold-plated brass, and the female contact is gold-plated beryllium copper.

They are designed to meet industry specifications and are available in either printed-circuit-board, bulkhead, or cable versions. Frequency range is dc to 3 GHz, with a typical voltage standing-wave ratio of 1.35 at 3 GHz.

The unit price of a typical plug and cable is £2. In 10,000-unit purchases, the same device costs £1.

Greenpar Connectors Ltd., Cambridge Road, Harlow, Essex CM20 2ER, UK.

Phone 44-279-27192 [Circle 709]

SWITCHES AIMED AT LOW-CURRENT USES

The DG and DH series of microswitches from Cherry Electrical Products Ltd. are aimed at low-current applications. The DG measures 12.8 by 11.5 by 5.8 mm. The DH measures 8.2 by 2.7 by 10.5 mm. Prices for the parts have not been released.

The company's G80-0928H keyboard can be switched as required for use with IBM Corp. XT or AT personal computers. It has the standard European 102-key layout, with separate areas for the typewriter, numeric, function, and cursor keys. Its price has not been published.

Cherry Electrical Products Ltd., Coldharbour Lane, Harpenden, Herts AL5 4UN, UK.

Phone 44-5827 63100 [Circle 707].

COUNTING DIALS ARE ACCURATE TO 0.02%

The CT-50 counting dial from Kynmore Engineering Co. has a 7/8-in. diameter and a three-digit readout that is accurate to 0.02%. A dead-locking brake that operates by means of a concentric collar eliminates the need for a protruding brake lever. The price of the CT-50



counting dial is £7.50.

The CT-85 counting dial also has a 7/8-in. diameter, and it features analog dials going up to 15 turns. Its brake lever is shrouded from the mounting panel by the antirotation disk by which the dial is mounted. The CT-85 costs £3.50. Both dials fit 6-mm and 6.35-mm shafts.

Kynmore Engineering Co. Ltd., 19 Buckingham St., London WC2, UK.


Phone 44-1-839-2371 [Circle 705]

19-in. CARDFRAMES OPEN IN A SNAP

The Image series of 19-in. cases and cased cardframes from Imhof-Bedco Standard Products Ltd. feature fully reversible ventilated and plain covers that can be fixed or removed using just two screws.

All basic fittings are concealed, and the fluted-aluminum side extrusions are designed to be both attractive and usable as carrying handles.

Three types of rear panels are available—ventilated, plain, and with fan cut-



outs. The 19-in. cases have been designed to accommodate standard 19-in. subrack and panel-mounted equipment conforming to IEC297, DIN41494, and BS5954 standards. All models are supplied fully assembled with top and base panels, rear fixing screws, and nonslip self-adhesive feet.

There are two types of rear rails available for the cardframes: one to accept DIN41612 connectors, and the other for the mounting of motherboards or various connectors via mounting strips using nuts, nut retainers, or tapped strips. Prices for the Image series range from £45 to £130.

Imhof-Bedco Standard Products Ltd., Ashley Rd., Uxbridge, Middlesex UB8 2SQ, UK.

Phone 44-895-37123 [Circle 704]

DATA SENT 200 m OVER IR BEAM

Two products from Thorn EMI Measurement Ltd. reduce communications costs over rough terrain by allowing users to transmit information via light beams instead of cable.

Both the LH500 Ledhead Kit and the LH50 Laserhead Kit are available with either one- or two-way communications

capabilities and are aimed at divided-site local-area-network applications.

The LH500 Ledhead Kit uses infrared light to transmit video, pulse-code modulation, audio, and telemetry information over distances of up to 200 m. A typical system comprising two Ledheads, two power/interface boxes, and mounting brackets costs £2,500.

The LH50 Laserhead Kit uses lasers to transmit up to 1 km. It includes removable telescopic sites for accurate settings and costs about £5,000.

Both systems can operate on beams of light generated by either solid-state laser diodes or infrared light-emitting diodes. The received signal is optically filtered and focused onto a low-noise detector before demodulation.

Thorn EMI Measurement Ltd., Berrington Rd., Leamington Spa, Warwickshire CV31 1NB, UK.

Phone 44-926-35411 [Circle 710]

MEMORY MODULES MIX TECHNOLOGIES

The VPAC-1 series of Versapac memory modules from EMM-Densepac Ltd. allows users to mix memory technologies. Examples include SRAM with EEPROM, SRAM with EPROM, and EPROM with EEPROM. All the control logic is mounted under the leaded chip carrier—that is, within the substrate.

Each module has 66 pins, including two power and two ground pins. The pins are banked to accommodate a heat ladder. The package is 1.15 in. square.

Typical price for a 128-Kbit-by-32-bit EPROM with 150-ns access time is \$700. A 70-ns 32-Kbit-by-32-bit SRAM costs \$350, and a 150-ns 32-Kbit-by-32-bit EEPROM is \$900.

The products are second-sourced in the U.S. by the firm's sister company, Densepac Microsystems Inc., Los Angeles, Calif.

EMM-Densepac Ltd., Woodstock House, The Street, Bramber, Sussex BN1 3WE, UK.

Phone 44-903-813008 [Circle 711]

ENCLOSURES HANDLE ODD CONFIGURATIONS

The Copal S-5000 series of miniature dual in-line package switches from Kynmore Engineering Co. is available with resistors only, diodes only, or with resistors and diodes.

The product line includes hexadecimal, decimal, and binary-coded decimal types in all the usual configurations for random-access memory, read-only memory, and input/output boards. Prices range from £1.85 to £2.25.

Kynmore Engineering Co., 19 Buckingham St., London WC2, UK.

Phone 44-1-839-2371 [Circle 713]

LOOK TO THE LEADER FOR THE VISIONPOWER YOU NEED.



Over 250 leading industrial companies look to IRI for a wide range of AI Vision applications.

Simply stated, VisionPower™ is the ability of an AI Vision "engine" to perform required inspection and other vision tasks in a given timeframe. Expressed another way, VisionPower = Functionality x Performance.

IRI puts VisionPower to work in diverse industries.

IRI's complete line of vision engines, with VisionPower ratings ranging from 1 to 50*, are being used in over 250 major industrial companies. From aerospace, electronics, food processing, package reading and sorting, to automotive, materials handling and process control industries, IRI has a

The IRI P256 Vision System has a VisionPower rating of 1.

See us at:
ROBOTS '87 in Chicago,
April 28-30, booth #6023

system with the VisionPower requirements to meet your application needs.

IRI serves wide-ranging applications.

Name your application. Inspecting electronic components and sub assemblies. Performing robot guidance. Package reading. Flaw detection. Optical character recognition (OCR). Gauging and mechanical assembly inspection. IRI has a system specifically for you.

New IRI VisionPower focused on the future.

Now, IRI's SUPRA Series, a new family of high performance, high resolution systems, offers advanced hardware functionality for Pattern Recognition, Optical Character Recognition (OCR), Region of Interest Processing within multiple windows, and Local Area Network (LAN) connection.


The SUPRA Series can be configured up to a 200 VisionPower rating (200 times IRI's P256).

We provide vision software and hardware tools, too.

IRI has also extended its VisionPower leadership to new software and hardware tools as well. Our AI ToolBox provides software "building blocks" designed to facilitate application-specific software. Unique hardware features include: Up to 1024 x 1024 variable resolution, color graphics, array coprocessors, variable pixel length, pixel labeling, and vector correlation.

Now on-line at factories and plants throughout the world, IRI VisionPower is being utilized to enhance production efficiencies, improve product quality and reduce operating costs.

The IRI VisionPower Curve.™



For further information about VisionPower, volume pricing and OEM packaging, call:

Richard Carroll, V.P. Sales (619) 438-4424

International Robomation Intelligence

2281 Las Palmas Drive, Carlsbad, CA 92008



The Source for High Performance

... in interconnection/packaging products for microcomputer bus systems




Customer evaluations rate Hybricon's VME Backplanes high in performance.

Hybricon's engineers have optimized:

- Signal transmission integrity
- Propagation time
- Reflections
- Power distribution
- Crosstalk

... to produce a family of standard VME backplanes unsurpassed in their ability to support clean transparent transmission of signals between function boards.



Exceptionally clean signals characterize Hybricon's backplanes. (Illustrated from actual customer photos.)

Circle 56 on reader service card

An experienced engineer knows that **safe noise margins must be "designed in,"** reliability of operation depends on it.

Inadequate margins are eroded by:

- Production tolerances
- Traffic density
- Coincidence of signal currents
- Optional hardware additions

... which could lead to failure of a normally operating system. Hybricon products are **designed to maintain noise immunity** by taking into account the factors which affect them, such as:

- Backward and forward crosstalk
- Differential ground signals
- Rise time distortion and ringing due to reflected waves
- Signal propagation delay
- DC voltage drops


Excellence of Design

Hybricon Engineers understand your problems; they have direct experience in high speed system design. Hybricon backplanes rate high in performance because they incorporate **basic and solid engineering principles.**

We're your design-in source and deliver products configured to your exact specifications. Customizing to special needs is an integral part of the Hybricon process, which is:

- Cost effective: Starts from extensive CAD data base
- Interactive: Continuous communication with customer

Hybricon manufactures an extensive line of standard and customized products specifically for bus based systems, and they are available world wide. Send for the name and address of your local Hybricon representative or international distributor.



Don't Settle for Less...
go with

Hybricon

12 Willow Road / P.O. Box 149
Ayer, MA U.S.A. 01432-0149
(617) 772-5422 FAX (617) 772-0564

INSIDE TECHNOLOGY

HOW DOD IS CREATING A MAJOR NEW BUSINESS


All three services push major instrument-on-a-card programs, and only a lack of standards is holding back a flood of commercial business

by George Sideris

Drawn by the lure of extremely flexible and relatively inexpensive test-and-measurement systems, the Pentagon is pushing the development of test instruments built on single-card modules. The Air Force, the Army, and the Navy are all working on the microcomputer-controlled systems and are devoting much of their enormous purchasing power to the development of a new generation of automatic test equipment based on instruments on cards.

One likely result of the military's drive will be the creation of a major new commercial market for a new breed of card-based instruments. But that won't happen until the military eliminates a major stumbling block: so far, no military standard for instrumentation buses or card formats exists. All three military services are currently pursuing slightly different approaches, a course that instrument vendors find very frustrating. A single standard still looks doable, but many problems have to be solved first.

Many instrument vendors are already building instruments on cards that are compatible with IBM personal computers and other machines. But because of the lack of standardization in the military realm, instrument makers are by and large steering clear of the Pentagon's instrument-on-a-card programs. They do not see a broad market developing behind the service-specific systems. Thus the development of the



cards for the new military systems is being done almost entirely by prime contractors instead of instrument companies—GE is doing the job for the Navy, for example, and Grumman for the Army. The Air Force, on the other hand, is still working on a standard that might gain the support of the instrumentation industry. Meanwhile, a few companies have rallied around a VMEbus-based one-card module developed for the Air Force

by Wavetek Corp., San Diego (see p. 60), in an effort to make it a de facto standard.

But until a single standard is worked out and given the stamp of approval, traditional instrument makers are not likely to show much interest in the military's efforts. Particularly in the Army and Navy cases, "we can't do much for them because those are sole-source contracts with nonstandard instrument buses and card sizes," says Marlyn Huckleby, military/aerospace program manager at Tektronix Inc., Beaverton, Ore.

But Huckleby recognizes that the military has different goals it must pursue, goals not necessarily compatible with the interests of instrumentation manufacturers. For instance, to get rid of a "logistics tail" that now stretches over the waves to many commercial instrument manufacturers, the Navy wants its test equipment built like a weapons system and supported by a prime contractor. On a ship at sea, "the captain doesn't want to call an 800 number for service when

an instrument breaks down," Huckeby says.

Although the commercial instrument-on-a-card market is growing rapidly, it is still small compared with the total military ATE market. Prime Data, a San Jose, Calif., market researcher, estimates the computer-dependent instrument market, which includes instruments on cards, was \$191 million in 1986 and will grow to \$485 million by 1990, a rate of 26% a year. Of 1986 sales, \$18 million were low-end test instruments, mostly cards used with PCs; \$54 million were high-end test instruments, which are not by and large card-based; and the remainder were card-based data-acquisition instruments. Industry sources estimate the total military ATE market at \$3 billion.

Instruments on cards will challenge in the military market conventional instruments from such old-line manufacturers as John Fluke, Hewlett-Packard, and Tektronix—the big three in the military ATE market. Industry sources say that HP reaps about 40% to 50% of military instrument sales because it continually pushes the state of the art in rf testing.


MEETING RF REQUIREMENTS

But cards can already meet some of the requirements of rf testing, as demonstrated by a signal-generation unit using eight instruments on cards that Wavetek introduced in early April at the Electro show in New York [*Electronics*, Apr. 2, 1987, p. 107]. It puts out complex waveforms for such jobs as radar-receiver testing and boasts a precision of 100 ps at a signal delay of 1 μ s.

The unit is being used by Honeywell Inc. in an Air Force system known as GATE, short for Generic ATE, because it will be the first to test many kinds of avionics systems. Moreover, cards have helped improve system performance, says Trygve Svard, the GATE project's technical director at Honeywell's Test Systems and Logistics Operations in Minneapolis, Minn. Although Honeywell began developing GATE a year ago, Svard started asking instrument makers to work on instrument-on-a-card technology well before that.

"We started talking to vendors three or four years ago, and one that listened a lot was Wavetek," says Svard. "We generally use four or five of their instruments in a bay. They only cost around \$5,000, but the bay costs \$50,000 with all the power, cooling, shielding against electromagnetic radiation, and so forth. With eight cards in a module, you get a good cost ratio."

Honeywell is developing specialized instruments



1. SEAWORTHY. GE's system for the Navy is being built using instrument-on-a-card modules.

on cards that will fit into a Racal-Dana signal-switching chassis with a VMEbus backplane. Plugging cards into the chassis, which routes test signals, minimizes signal-path lengths and thereby eliminates most performance losses caused by the long cables in traditional rack-and-stack systems. Putting the cards close together improves signal fidelity and frequency response, says Svard.

To the Air Force, a GATE system using instrument-on-a-card technology is just another evolution of MATE, the Modular-ATE program that regulates procurement and provides system-integration guidelines and standards. The Air Force has not yet required contractors to use

card-based modules but is nudging them in that direction.

For the Navy, the Consolidated Automatic Support System, or CASS, in development at General Electric Co. is based on card-level instruments and will be "completely modular—from the built-in-test level to complex test functions, from dc to light," says John E. Barker, GE's program manager. GE will supply the modules. CASS will go into production in the early 1990s and will become the fleet's standard ATE system (see fig. 1).

Aircraft carriers are now loaded with 95 kinds of test equipment and must carry 30,000 spare parts and 21 civilian ATE workers. CASS will reduce that to five test systems, 3,800 spares, no contractor personnel, and will cut training programs from 185 to five. The Navy selected GE's Federal Electronic Systems Division in Philadelphia as the prime contractor in December, after GE won a design competition against Grumman Corp. of Bethpage, N. Y.

CASS will have a general-purpose core system, specialized test stands for applications such as electro-optical testing, and a portable unit for the flight deck. The system uses VMEbus at the instrument-control level and Ethernet at the station-control level.

The Army's instrument-on-a-card project aims to build what it calls Intermediate Forward Test Equipment. Grumman is set to start production early next year of IFTE, an evolution of System X, an ATE system Grumman built as part of a \$50 million investment to start up its Electronic Systems Division and win military ATE orders. The company expects orders to exceed \$1 billion.

With IFTE, an ATE system can go into a battle zone, something not possible with current Army ATE. The main system, called a shop tester, fits in

a shelter on a truck (see fig. 2). IFTE, like CASS, uses a modified VMEbus, but its cards are not compatible with those built for CASS. IFTE will replace an ATE system too big to move and dozens of small systems. A portable field unit will be used to make on-the-spot repairs. A system equivalent to the shop tester but built with commercial equipment will be used in depots.

Though Grumman will use cards for other instrumentation, it chose the HP 71000 modular spectrum-analyzer system for rf measurements. Each stage of the analyzer is separately packaged and plugs into a chassis.

And HP studied the possibility of building such instruments with cards and found that cards ran into a "microwave barrier" between 1 and 2 GHz, according to John Knobel, marketing manager for modular measurement systems in HP's Signal Analysis Division, Rohnert Park, Calif. Multiple cards would be needed, he says, and in that frequency range, shielding and matching requirements for cards become so hard to meet that building an instrument in the usual way becomes more cost-effective. The modular approach was adopted so modules could be mixed, matched and upgraded, which, he argues, provides the same benefits as cards.

There are no HP instruments in the Navy's CASS system, says Knobel. "GE intends to design every piece of test equipment themselves, including microwave. It's a big challenge."

IFTE and CASS have attracted few instrument companies. Racal-Dana Instruments Inc. was invited to participate in the IFTE program, "but we looked at the economics and declined," says Brian Hull, vice president of the Irvine, Calif., company. "It's not an open architecture that will be accepted by industry. Grumman has had to develop most of the virtual instruments."

Instrument makers are, however, ready to build instruments on cards for the military as soon as a single standard emerges. The search for a standard began in 1985 when the MATE program office asked its users group to recommend one. The task was assigned to a subcommittee headed by Louis Klahn, sales manager of Colorado Data Systems Inc. The group agreed that the VMEbus should be upgraded for instrumentation. "We had a fairly final version in November, and then the vested interests came out of the woodwork," Klahn says. "In my opinion and that of several others, this is a good standard. You can't optimize for everything."

The draft is in review but may not be adopted, says Col. George Wright, MATE program director at the Aeronautical Systems Division, Wright-Patterson AFB. "This would be the first standard that broaches major new territory for the MATE standards. While we are anxious to get it out, we are also anxious that we don't design

ourselves into a technical-obsolescence box."


"Our first-order concern is whether or not we need to establish a standard at all, then whether we should establish an interface at that level. It might not be necessary, it might be too detailed and limit freedom to innovate," Wright adds. "Our concern is whether or not that's the place to standardize and only secondarily whether or

The flexibility of card-based instrument systems makes it possible to replace a wide range of existing equipment and cut down on training programs

not that's the right bus. Most of the work on the standard has been at that second level." If those issues are resolved, Wright says, the standard could be adopted in June.

Wavetek's bus is compatible with the standard recommended by the MATE Users Group, according to Fred Bode, the company's business unit manager for system products and instrumentation computers. In addition to the two standard VMEbus buses, the Wavetek version includes a third bus for high-speed analog signals. "In fact, Lou Klahn talked at the last [users' group] meeting about some of the limitations that he found in using just the two VMEbuses. So I think that will probably be changed."

Instruments compatible with Wavetek's system are on the way from Racal-Dana and Datron Instruments Inc., Stuart, Fla. If more companies climb aboard, they may be able to establish the card size and bus structure as de facto standards for military and commercial applications. □



2. TRUCK-MOUNTED. This instrument-on-a-card system Grumman is building for the Army rides into battle on a truck.

CARD-BASED ATE SYSTEM COULD SET A STANDARD

Wavetek's instrument-on-a-card system replaces a rack of instruments for ATE applications with eight plug-in modules

by George Sideris



A young contender is pushing its way to the forefront of the emerging market for instruments on cards. The 680 system from Wavetek Corp. uses cards in a package that can replace a rack of conventional instruments—and Wavetek's approach is already making a strong bid to become a de facto standard in its market.


The 680 already is off to a flying start. The system is being introduced at Electro, [*Electronics*, April 2, 1987, p.107], but the first 680 was delivered to Honeywell Inc. in December, for use as a subsystem in a project for the Air Force.

More important, San Diego-based Wavetek has been joined by Racal-Dana Instruments Inc. of Irvine, Calif., and Datron Instruments Inc. of Stuart, Fla., in a campaign promoting the 680's design as a standard for high-performance, instrument-on-a-card systems, says Mathieu van den Bergh, system products manager at Wavetek. If the campaign is successful, it could make Wavetek a major player in the instrument-on-a-card segment of the ATE market—particularly the military segment, where growth has been hampered by a lack of standards (see p. 57).

The 680 is built around an open-architecture mainframe, the size of a conventional rack-mountable instrument, that supports independent or interactive operation of up to eight plug-in instruments on cards. At the heart of the mainframe is an upgraded VMEbus, upgraded with a high-speed instrumentation bus and analog buses that carry signals in the 100-MHz range. The new buses are built with impedance-matched striplines, a printed-circuit version of coaxial cabling. Van den Bergh says the bus outperforms the IB 1 design that has been proposed as an Air Force Modular Automatic Test Equipment, or MATE, standard, but that it is compatible with the proposed standard. Wavetek's architecture (see fig. 1) was aimed at military ATE systems and, in particular, MATE-compliant avionics systems.

The first 680 System Wavetek delivered, in fact, is intended for a military application. Honeywell is using it as the video stimulus subsystem of the Generic ATE system, a general-purpose avionics test system being developed for the Air Force. Van den Bergh says it may be used in as many as 120 test stations.

And Wavetek hopes that the



1. PICK A CARD. The 680 system's architecture includes a 68000 microprocessor and an upgraded version of VMEbus. The upgrades include instrumentation and analog signal buses.

push to make the 680 a standard will dramatically boost its use in other military ATE systems. Its two allies are doing their part by designing new cards that are compatible with the 680 system—and which widen its applications. Racal-Dana has developed a card version of its Model 1994 1.3-GHz microwave frequency counter/timer. Datron has a card equivalent of its Model 1602 6½-digit multimeter. To attract other instrument makers, Wavetek offers its software and documentation to them for a nominal fee.

The trio expects competition from larger companies but, says van den Bergh, they are a year or two ahead of the pack. And each is a leader in a different military ATE niche—Wavetek in signal sources, Racal-Dana in frequency counters and timers, and Datron in digital voltmeters.

The system they are all banking on, the 680, is based on a mainframe that comes in a 7-inch-high unit that fits into a standard instrumentation rack. Eight cards, each shielded by an aluminum housing, plug endwise into a backplane in the mainframe's floor (fig. 2). Each card's far end projects through a rear opening, so that coaxial cables and other test-signal lines can be connected to it. Internal temperature is maintained by three variable-speed cooling fans regulated with the aid of a temperature sensor in the switching power supply.


The cards share a host processor, called the VME board, based on Motorola Inc.'s 68000 microprocessor. Standard memory includes 512 Kbytes of dynamic random-access memory, 128 Kbytes of nonvolatile static RAM and 1 Mbyte of programmable read-only memory. Among the input/output ports is a 16-bit analog port for testing VLSI circuits, digital signal processors, and other components. A reference/calibration board provides a 10-MHz clock and a phase-locked-loop-controlled 100-MHz clock, both accurate to within ± 1 part per million, a trigger source that can be set to 5 digits and which has 0.1% frequency accuracy, and an external trigger input with programmable delay.

The reference/calibration board is controlled by a 6803 8-bit microprocessor. Programmed auto-calibrations are based on a zener voltage reference and a crystal clock that the user can align with external references. The 6803 uses the on-board references to align a digital voltmeter, counters (application-specific integrated circuits), system clocks, and other on-board circuitry. That done, it checks the card instruments and stores correction factors in the VME board's nonvolatile RAM. To maintain accuracy, the system generates an alarm if the operating temperature goes 5°C above or below the calibration temperature.

The front panel subsystem is designed for stand-alone operation and system troubleshooting. Its 6803 microprocessor can store and recall instrument-on-a-card setups and display the instruments' functions and test parameters. It communicates with the VME board via an optically isolated data link. Panel I/O routines were written in assembly language for speedy execution. Other system firm-

ware is programmed in the C language. Programs are compiled with the Greenhill C compiler from XEL Inc., Cambridge, Mass., and run on the PSOS real-time multitasking operating system from the Software Group Inc., Santa Clara, Calif.

Wavetek's system bus uses all three connectors and buses allowed by the VMEbus (IEEE-1014) structure. Only two connectors are employed by a combination VMEbus and instrumentation bus, known as IB 1, proposed last year as an Air Force standard by an instrument-on-a-card subcommittee of the National Security Industrial Association's MATE Users Group. Wavetek added a third section



2. CHASSIS. The instrument cards plug vertically into a VMEbus backplane and are controlled by the microprocessor.

that provides a variety of analog buses. One analog bus, for example, sums the output of up to eight cards. In the signal-generator version, this allows the system to generate very complex wave forms with much greater precision than a set of conventional signal generators.

Besides the third bus, the major difference between Wavetek's bus and IB 1 is the backplane construction. Wavetek went to an 8-layer backplane with stripline conductors and ground planes on the top layer, fourth layer, and bottom layer of the printed-circuit board. Analog lines are kept well away from the noisy power and digital lines. Each signal pin is isolated by grounded pins. The analog-line design rules are also stricter. For instance, there can be no more than a ½-inch stub between the trigger driver/receiver circuit and the connector. The striplines are conductors sandwiched between shielding, as usual, but advanced layout and termination techniques impedance-match the lines so they would not "ring" (generate noise by reflecting signals), says Kwok Lo, system products engineering manager.

Van den Bergh says Wavetek abandoned a more efficient, less costly proprietary bus to con-

more efficient, less costly proprietary bus to converge on the proposed IB 1 standard, and developed its backplane to boost performance over the VMEbus-based standard. "We found that IB 1's trigger buses work fine up to few hundred kilohertz," he says, "but if you go up in frequency, the triggers become ambiguous." Lo explains, "The pulse-transition time, not frequency, is the

Wavetek fashioned its upgraded VMEbus, with added instrumentation and analog buses, to hew as closely as possible to the proposed Air Force MATE standard

critical thing. If it's faster than a few nanoseconds, IB 1 causes a lot of ringing. To 20 ns, it's fine. Faster, you can cause multiple triggering. You send out one trigger pulse and you may get several in the bus line."

Like IB 1, Wavetek's design follows the VMEbus standard for the microprocessor bus. That is, a 96-pin connector P1 (3 rows of 32 pins) defines a basic 16-bit system bus with 16.7 megabytes of address space. Also, it expands to a 32-bit system bus with 4-gigabyte addressing by using one row of P2, a second 96-pin connector, for 8 upper address bits and 16 upper data bits. The other rows of P2 provide the instrumentation bus.

Wavetek's 32-bit digital-instrumentation bus has 4 lines for module identification codes, 20 lines for data at transistor-transistor-logic levels, and 8 lines for emitter-coupled-logic signals that can be con-

verted to TTL levels by the individual modules. The 20-bit bus allows modules to transfer data without tying up the VMEbus. The ECL lines provide for such functions as slicing up time intervals to increase timing precision. P2 also provides bus sections, constructed as analog lines, for synchronizing the system, triggering the various modules, and distributing the 10- and 100-MHz system clocks. System modules are synchronized within 1 ns; the card instruments can be triggered within 1 ns of each other.

Overall, the 680's design makes it well suited for military ATE applications, especially the avionics-oriented MATE systems. Military ATE systems usually contain low-frequency analog, radio-frequency and microwave test sections. Like the conventional instruments in MATE systems, the card instruments communicate via an IEEE-488 port. Programming options include English-like commands and, with an optional test module adaptor, the MATE Control Intermediate Interface Language. A MATE requirement that instrumentation automatically find 95% of all instrumentation problems with 98% confidence is met by the 680 with built-in test functions. □

For more information, circle 480 on the reader service card.

TECHNOLOGY TO WATCH is a regular feature of Electronics that provides readers with exclusive, in-depth reports on important technical innovations from companies around the world. It covers significant technology, processes, and developments incorporated in major new products.

FOR WAVETEK, CARD-BASED ATE IS A WAY TO COMPETE WITH LEADERS


For Kwok S. Lo, the exciting thing about instrument-on-a-card systems is that one and one add up to more than two. "Two signal generators linked together in the same place can do more things than two independent instruments could ever do in the past," says Lo, Wavetek Corp.'s system products engineering manager.

For Mathieu van den Bergh, system products manager, there's another attraction: the technology is an equalizer. It's a way for smaller companies to compete in the automatic-test-equipment market with industry leaders like Hewlett-Packard Co.

Lo, born in Hong Kong 49 years ago, joined Wavetek in 1969, the year he got his MSEE at California's San Jose State University (he got his BSEE at University of California, Berkeley, in 1966). "We talked about building a multisource instrument four years ago," Lo says. However, the project was shelved as too costly. Then van den Bergh, a 40-year-old native of the Netherlands (he got his

BSEE at Arnheim College in 1968) joined Wavetek early in 1984.

He soon won management's backing for the project. One reason: suitable application-specific integrated circuits were becoming available. Previously, only large firms could afford to develop custom components for high-performance instruments, he says. "ASICs made it possible for smaller companies



CARD PLAYERS. Wavetek's Mathieu van den Bergh (left) and Kwok S. Lo

like Wavetek to compete on an equal level in technology and performance." With gate arrays and other ASICs, Lo's team could squeeze high-performance instruments into a card system. The team had set as its goal tying at least eight signal generators together.

Wavetek had another advantage, van den Bergh adds. The Air Force's Modular Automatic Test Equipment program was creating a demand for highly modular systems, and Wavetek had begun to develop MATE-compatible instruments. Lo laid some of the groundwork by working on an industry committee defining CIIL, the program's Control Intermediate Interface Language that all MATE-compatible instruments must now "speak."

Wavetek went to an open-architecture system so that MATE prime contractors could use instruments on cards in the same mainframe. But the 680 System still met the original goal—the first version links eight signal generators.

SIEMENS

Short circuit eliminated

Card relay E

Siemens offers a highly extensive range of tried and tested electro-mechanical components, plus all the experience of a manufacturer who has consistently invested a great deal of know-how in developing and perfecting electromechanical components geared to market requirements.

The card relay E is a typical example. Fitted with one changeover, make or break contact, it provides reliable electrical isolation between light-current control circuits and heavy-current switching circuits – thus making a short circuit or "break-down" virtually impossible.

Other notable features include:

- High switching capacities (max. 4000 V/A)
- High dielectric strength (4 kV coil/contact)
- Immunity to external interference
- High overload capability

This makes the card relay E the ideal interface device in instrumentation, control and process engineering.

All the other features of the card relay E are detailed in a special publication. If you would like one, please use this journal's reader service or send us the coupon.

**Contacts you can rely on.
Electromechanical
components
from Siemens.**



Circle 115 on reader service card

Coupon: To Siemens AG, Infoservice 143/Z481, Postfach 2348, D-8510 Fürth 2
Yes, I would like to know more.
Please send me further free information.

Name _____
Street _____
Place/Postcode _____
Country _____
A 19100-N61-Z5
X-7600

People who deal with "baud" use every bit of McGraw-Hill

Nobody understands the value of good information better than the people who work in computers and communications.


And for those people, no information carries more weight than McGraw-Hill's. We provide the databases, analyses and news that computer and communications professionals rely on to illuminate the workings of their industries.

Everyone in the business keeps up with the latest developments by reading McGraw-Hill maga-

zines. BYTE, Electronics and Data Communications are all required reading in the field. So are books from Osborne/McGraw-Hill.

For people who buy computers (and run EDP operations) the most widely respected source of information is Datapro.

Datapro's print and on-line directories and reports cover every aspect of computer hardware and software, from mainframes to micros, as well as communications and office automation. There's ever-



and "byte" information.

a report on how to protect electronically stored information from piracy.

For people who manufacture or sell microcomputers and micro software, Future Computing is the number one information source for product tests, analyses and comparisons.

People who specialize in communications are wired into CCMI/McGraw-Hill, to receive not only the hard facts on communications tariffs, but also in-depth analyses and bottom-line recommendations,


via print, software and on-line products.

When it comes to turning megabytes into megabucks, nothing computes like McGraw-Hill information.

McGraw-Hill, Inc., 1221 Avenue of the Americas,
New York, N.Y. 10020.

McGraw-Hill.
Information that leads to action.





This champ meets your most critical cable-to-anything interconnect challenges.

Cable-to-cable, cable-to-panel, cable-to-board, CHAMP connectors meet every challenge with a strong balance of performance, technology and solid value.

Our newest ideas: connectors with advanced EMI shielding. And connectors with mass terminatable monolithic filter contacts to combat conducted interference. Shielded versions are lightweight and cost-effective, and they use existing tooling. With our covers or post-mold your own.


CHAMP contacts handle the widest range of wire sizes in the industry, 26-22 AWG solid, 28-22 AWG stranded. And that's across the broadest range of .085" centerline products available, including IEEE 488 interconnects and compliant pin headers for solderless pc board mounting.

For unbeatable performance at both ends of the cable, go with CHAMP connectors.



Snap-together shield incorporates stored-energy braid captivation.

Call (717) 780-4400 and ask for the CHAMP Information Desk.
AMP Incorporated,
Harrisburg, PA 17105.



Panel mount CHAMP headers include industry-standard 36-position printer interface. Others to solve any I/O need.



IEEE 488 interconnects, shielded or unshielded.

AMP Interconnecting ideas

AMP and CHAMP are trademarks of AMP Incorporated.

Circle 67 on reader service card

The lithium battery you can fit and forget.

Sonnenschein lithium batteries have a proven shelf-life of at least ten years. That's double what you can expect from conventional lithium batteries. And that's good news for all users of CMOS memories, real-time clocks and other long-term data storage devices. In fact, Sonnenschein lithium batteries are so good that they will outlive many of the products they're used in. Thanks to their passivation layer, our batteries have the exceptionally low self-discharge rate of less than one percent per year. What is more, the hermetically sealed battery copes happily with ambient temperatures from -55° to $+75^{\circ}\text{C}$ with no noticeable effect on electrical performance. Contact our specialists today for full details of the battery with a future. A long, long future.

Sonnenschein Li-SOCl₂ batteries:
OCV 3.67 volts

Temperature range: -55° to $+75^{\circ}\text{C}$

Self-discharge rate: Less than 1%/year

Hermetically sealed by encapsulation welding and glass-to-metal positive pin feed-through

Safe from short-circuit


Flat discharge curve

No internal pressure

Capacity range from 0.35 Ah to 30 Ah



IM Stockholm
Hall A-Stand 39:25



Sonnenschein Lithium GmbH
Industriestraße · D-6470 Büdingen
W.-Germany · Telefon (0 60 42) 8 15 22

THIS BIPOLAR PROCESS GIVES DENSITY AND DYNAMIC RANGE

A new process from Fairchild Semiconductor Corp. seems to resolve what has always appeared to be an irreconcilable problem for chip designers: how to get high-performance analog and high-density digital functions to reside on the same chip. The new process, called LFAST, is a 5- μ m linear bipolar process from Fairchild's Linear Division in Mountain View, Calif.

The process achieves a tenfold increase in density over existing linear bipolar approaches without sacrificing speed. The supply voltage, breakdown voltage, current density, and other key specifications are well above the minimums required for analog functions. And Fairchild engineers have been able to fabricate circuits with internal emitter-coupled-logic digital functions whose switching does not affect the noise figures of the analog circuitry.

LFAST blends existing techniques into a process combining highly doped buried layers with thin epitaxial layers, plus an unconventional isolation method with self-aligned processing. It also features composite masking and platinum silicide metal interconnection.


Before LFAST, any process capable of producing linear circuits with enough dynamic range to be useful in practical analog applications had to sacrifice the density required for large-scale integration, says Kulwant Egan, manager of bipolar process development. Moreover, few digital processes, either bipolar or CMOS, bring together the elements needed to fabricate high-performance operational amplifiers, comparators, multiplexers, and other linear functions—nor do these processes operate at sufficiently high supply voltages, he says. In addition, most digital processes cannot be used to fabricate the fast-switching pnp transistors, high-value matched transistors, or precision capacitors needed in many high-performance applications.

With LFAST, high-performance applications needing both high density and high performance—such as data-acquisition systems, computer peripherals circuits, and communications ICs—no longer require discrete linear components or multiple hybrid circuits to fill key system sockets, says Surinder Krishna, manager of advanced technology development.

Fairchild designers aimed at optimizing the linear portion of LFAST while maintaining the density and performance of the digital portion. "Of course, some sacrifices had to be made, and the

By combining highly doped, buried layers with thin epitaxial layers, Fairchild gets practical linear circuits without sacrificing LSI densities needed for digital functions

by Bernard C. Cole



1. QUICK CHIP. Built with the LFAST linear bipolar process, the μ A2490 data separator/encoder-decoder chip is capable of transmission rates up to 25 Mb/s.

LFAST TRANSISTORS WITHSTAND HIGH VOLTAGE

	npn	Lpnp
V_{CE0}	15 – 19 V	19 – 27 V
BV_{CBO}	33 – 39 V	33 – 39 V
H_{FE}	60 – 100	55 – 100
f_T	1.9 – 2.5 GHz	40 – 50 MHz
V_A	55 – 70 V	35 – 55 V

ECL portion of LFAST should not be compared with a process dedicated to digital ECL," says Egan. "But while LFAST ECL is not fully optimized, it offers respectable specifications." Typical gate delay is 1.8 ns at a 200- μ A current level, and this improves to 1 ns at a current of 1 mA. The ECL devices in Fairchild's CLASIC, or custom linear application-specific IC, cell library do not operate at the high levels of standard ECL. They are characterized for lower-current operation to permit operation with linear devices.

LFAST is already used internally at Fairchild to build a range of standard and semicustom mixed analog/digital products, Krishna says, including a data separator/encoder-decoder (see fig. 1), a

data-line interface family, a series of advanced Winchester-drive chips, and several high-performance comparators. In addition, the process will be used to make a range of custom and semicustom CLASIC circuits. "It is now possible to create custom LSI devices by selecting analog functions from a cell library," Krishna says.


LFAST is able to use tiny transistors without sacrificing performance or power-handling capacity, Krishna says. The transistor density of LFAST is more than 10 times that of conventional 10- μ m to 15- μ m bipolar processes: an LFAST transistor occupies about 1,100 μ m², compared with 16,000 μ m² for devices found in standard linear components. The process also incorporates Schottky diodes constructed with the usual platinum silicide materials. Its high-valued resistors, however, are anything but conventional, since they result from a unique implanting method. And the thin oxides that are used allow the construction of feedback capacitors for on-chip op amps.

LFAST fills a number of voids in conventional semiconductor processes that attempt to mate analog and digital circuitry, says Egan. For example, the supply voltage at which the linear devices operate poses a problem. To obtain reasonable dynamic range, the supply voltage must be greater than the 5 V used for the logic portion; at least 15 V is required. "To run at this level, conventional processes rely on stacking 5-V transistors—a risky procedure, since it is difficult to guarantee that phase relationships among the various voltages on the chip will not produce levels that exceed the breakdown voltage of individual transistors," says Egan.

LFAST, on the other hand, is a true 15-V process: all transistor breakdown voltages are 15 V or greater (see table). "What's more, LFAST does not rely on thicker, deeper junctions or wider spacings to ensure the breakdown voltage," says Krishna. "If it did, the process would no longer be suitable for building LSI digital logic on the same chip."

Current density of the LFAST transistors for peak f_T is 7,000 A/cm², compared with 500 A/cm² for conventional linear bipolar transistors, which means it is not necessary to increase the area of the transistors to boost their current-handling capability. With pnp transistors having a gain-bandwidth product of 40 to 45 MHz, LFAST devices are 15 to 40 times faster than any similar linear structures. And when used to fabricate digital transistors, LFAST can yield structures with typical gate delays of 1 ns at 1 mA. In LFAST, highly doped buried layers coexist with a thin, low-temperature-deposited epitaxial layer, giving the process its high packing density.

For op amps having a wide dynamic range, LFAST optimizes both the supply voltage—ampli-



2. INSIDE LFAST. This cross section of a chip fabricated in the LFAST process shows the structure of (a) a MOS capacitor, (b) a lateral pnp transistor, and (c) an implanted resistor.

fiers can swing to 15 V—and the equivalent noise voltage. To pull ac signals out of noise, LFAST op amps are specified for a noise voltage of just 1 nV/(Hz)^{1/2}. On the dc side, an amplifier must provide a very low input offset voltage, V_{OS} . Conventional op amps offer V_{OS} specifications of 1 to 10 mV, but Fairchild designers aimed for 1 mV or less with the LFAST process. “Actually, the offset-voltage parameters came out better than expected, ranging between 0.5 and 0.6 mV,” says Krishna. It is important to hold V_{OS} as low as possible, since an op amp with a gain of 1,000 amplifies a 10-mV V_{OS} to 10 V, driving itself into saturation.

SMALLER AND FASTER

A key factor in the gain of an amplifier is the Early voltage, the voltage needed to remove the charge from a transistor's base to reach zero current. When the collector-to-base voltage increases, the base width is reduced; this alters the output characteristic by changing the collector-to-base voltage. Early voltage and output impedance are closely related: the larger the voltage, the greater the output impedance. LFAST amplifiers exhibit a large Early voltage, because high-impedance amplifiers also happen to be high-gain amplifiers. A large Early voltage also improves an amplifier's common-mode-rejection ratio.

In general, an LFAST-implemented line driver or receiver is about 20% faster and consumes only one-fourth the power of a conventional single-chip IC. And with LFAST's smaller transistor size and 4- μ m design rules, an ASIC version is about 10 times as dense as its IC counterpart. An LFAST device can dissipate up to 1 W, but greater power dissipation is possible; the tradeoff is usually a larger package having greater heat-dissi-

pation capability. Egan says LFAST is the first process to apply high-performance digital fabrication techniques to linear devices (see fig. 2). For example, the low-temperature epitaxy growth is borrowed from digital-device construction. The problem, he says, is that the heavily doped buried layer must coexist with the thin epitaxial layer. Ordinarily, the buried layer moves into the epitaxial layer while the latter is grown. However, the low-temperature growth prevents movement of the buried layer during the epitaxial-growth step.

At the first mask level is a buried layer, over which is grown a thin epitaxial layer at low temperature. A composite masking technique is then used to define isolation islands, base islands, and the isolation sinker, all of which are self-aligned. The self-aligned regions of p^+ isolation, n^+ sinker, and p base give LFAST its high packing density. The three regions are implanted, along with the n^+ emitter.

Prior to implanting the emitter, however, a field oxide must be grown over it. Then the emitter is opened to allow implanting to take place through the emitter. The structure is then annealed in nitrogen, yielding a so-called washed emitter that serves as a self-aligned contact.

The result is that, in addition to their extremely small size, LFAST transistors operate at a current density of more than 10,000 A/cm² when the beta value—the ratio of the change in collector current to the corresponding change in base current—is at its maximum value. This is important for small-geometry transistors, says Egan, since it guarantees that the device will maintain its gain even at large collector currents. □

For more information, circle 481 on the reader service card.

WHY FAIRCHILD RUNS LFAST BIPOLAR ON ITS CMOS LINE

The primary aim that Surinder Krishna and Kulwant Egan had when they started the LFAST project two years ago was to develop a linear bipolar process that could match the density of linear CMOS but would not sacrifice any of bipolar's performance advantages. Krishna, 46, is manager of advanced technology at the Mountain View, Calif., company, and Egan, 36, is manager of bipolar process development in the advanced technology group.

What they came up with is a process that uses many of the same steps as CMOS. Indeed, parts being fabricated with LFAST are run on the same line as Fairchild's double-polysilicon CMOS process, and achieve the same yields, Krishna says. Moreover, many of the mixed analog/linear parts fabricated on the line to date have about the same die size.

The key to LFAST is a modular ap-

proach to processing, in which a basic set of process steps are developed to achieve a specific set of performance goals and then frozen, says Krishna. “Unlike traditional approaches to processing, where steps and parameters are modified to meet the needs of the circuit designer, LFAST was developed with exactly the opposite philosophy in



LFAST TEAM. Krishna (l.) and Egan squeezed linear bipolar performance into CMOS density.

mind,” he says. “To achieve various levels of performance and density, we subtract and add steps or modules to the [core] process, but we leave the basic parameters untouched,” adds Egan.

Krishna graduated from the University of Edinburgh, UK, in 1963 with MSEE and BSEE degrees. After stints at Marconi Research Laboratories in Essex, UK, General Electric's Research Laboratory in Schenectady, N. Y., and Westinghouse Research Center in Pittsburgh, Pa., he joined National Semiconductor Corp. in Santa Clara, Calif., in 1979. There he met Egan, who had been at National since 1975 after graduating from San Jose State University with an MSEE.

The close working relationship has continued at Fairchild, where Krishna started in 1981 as device engineering manager. Egan followed in 1982 as manager of bipolar process development.

PROLOG COMPILER IS KEY TO IBM-JAPAN AI RESEARCH

IBM Japan Ltd.'s Tokyo Research Laboratory is developing an optimized Prolog compiler that could play an important role in artificial-intelligence work stations. The compiler runs on an IBM RT PC enhanced with experimental versions of two other key AI work-station components: a multiwindow user interface and a new operating system.

Tetsunosuke Fujisaki, the lab's software technology manager, chose Prolog over the most commonly used language for AI, Lisp, because "I have a feeling that the research phase of Lisp has ended. For Prolog, there is much to be done, including language specifications and machine architecture."

Because the project's current Prolog compiler is still experimental, it lacks many functions, among them run-time check, garbage collection, and a large number of built-in predicates. But in a benchmark test with basic predicates only, it achieved a maximum speed of 87,000 logical inferences per second for a simple append operation, which exceeds the value on existing dedicated Prolog machines.

The Prolog compiler for this machine is based on the instruction set of an abstract machine proposed in 1983 by David H. Warren, the developer of DEC-10 Prolog. The IBM-Japan research-

ers chose the Warren abstract machine because they were familiar with it, not because it offered any performance advantages over other schemes. In fact, Warren's proposal was for a machine dedicated to symbolic processing, and it is not necessarily suited for general-purpose machines.

The Prolog source code is ultimately compiled into RT PC object code, but it is optimized numerous times in intermediate steps to improve execution performance. To prepare for optimization, the researchers added two declaration types to the mode declarations previously used in the source code. The no-trail declaration simplifies the processing of predicates that do not require backtracking. Data type declarations declare for the various parameters of the predicates what type of data they will input or what type of output data they will handle.


The Prolog source code is first converted into the Warren intermediate language based on the Warren abstract machine. Data type and other declarations are used for simultaneous optimization of Prolog language dependencies. Next the Warren intermediate language program data flow is analyzed, and optimization independent of the target machine is performed.

The Warren intermediate language code is then converted into PL8 machine-dependent code, at which time machine-dependent optimization is performed. For example, code is created that takes into account factors such as the necessary number of cycles for tag tests or memory accesses. Finally, compilation is done from PL8 to machine code.


In addition, the researchers at the Tokyo lab intend to port software from the IBM System/370 software to the RT PC, including the Prolog debug environment Proedit 2, the object-oriented knowledge representation language Spool, and the Ink environment on top of which Spool runs.

The RT PC is an engineering work station with a 32-bit reduced-instruction-set computer microprocessor [*Electronics*, May 5, 1986, p. 34]. The laboratory chose the new IBM machine primarily for cost reasons; it was less expensive to use an existing general-purpose machine than to develop a special-purpose machine.

The RT PC RISC architecture includes a 40-bit-address, single-level, nonhierarchical memory system in which each process has a 32-bit address that the memory management unit converts to a 40-bit address. The 4 most significant bits of the 32-bit process address are used to select one of sixteen 12-bit registers. These 12 bits are added to the 28 remaining least significant bits to obtain a 40-bit virtual-memory address. Since the maximum main memory of the RT PC is 16



1. HIERARCHY. The plan for user and programming interfaces of the AI work station has only been completed up to Interface 2.



2. WINDOW PROCESS. The operating-system kernel has a common portion in every process as part of the window manager.

Mbytes, the MMU converts the virtual address to a 24-bit real-memory address.

The advantage of a single-level memory is easier programming. Files and main memory can be placed in the same space, and file input/output

does not have to be considered a different kind of operation. Common address space among processes can be used effectively in the development of AI application programs.


The plan for the user and programming interfaces of the AI work station (see fig. 1) has been only partially implemented. It is currently completed only as far as the logic language on Interface 2. Above this, the knowledge base, the system language, and natural language interfaces will be implemented and tested.

The operating system used is the AIX OS developed at IBM's Watson Research Center in Yorktown Heights, N. Y. The kernel of this operating system has a common portion in every process (see fig. 2), included as part of the window manager. Fujisaki says that this configuration was selected because response is faster and overhead smaller. Processes running under control of Unix and other operating systems typically share one copy of the kernel.

An accurate evaluation of the compiler cannot be obtained because it does not have a complete array of functions. But the lab has taken the first steps toward building an AI work station with reasonable functionality on top of a general-purpose work station.

For more information, circle 482 on the reader service card.

TECHNOLOGY TO WATCH



'DUALING' PROCESSORS. ELIS's dual-processing system comprises a 64-bit CPU bus and a 16-bit front-end processor.

JAPAN'S NTT HAS WORLD'S FASTEST LISP PROCESSOR

A high-powered Lisp computer built by Nippon Telegraph & Telephone Corp.'s Electrical Communication Laboratories is now leading the pack as the world's fastest commercial Lisp machine. Called ELIS, the desktop computer can execute 1 million basic Lisp instructions per second, which is up to six times better than existing Lisp machines and minisupercomputers. It achieves this with extensive microcode for critical Lisp functions and a dual-processor architecture.

ELIS incorporates up to 128 Mbytes of main memory and a 540-Mbyte disk drive. Its multiple-paradigm programming language, Tao, was built upon Lisp and supports the Common Lisp standard. It also provides a logic language like Prolog and an object-oriented language like Smalltalk with which to write programs.

A microprogram-controlled machine, ELIS has a very large working control store: 64 Kbits of 64-bit words of writable control storage and a register stack of 32 Kbits of 32-bit words. These are both implemented in high-speed static random-access memory. Tao functions, written in microcode to speed up the interpreter, achieve

performance comparable to commercial Lisp compilers. Other functions are incorporated in a Common Lisp-compatible package. These functions are only about 10% of the total number of functions in Common Lisp, and the overhead is negligible. Although Common Lisp is a compiler-oriented language, preprocessing and other measures enable the Common Lisp interpreter to equal the performance of the Tao interpreter.

The ELIS system uses a dual processor-configuration with a central-processing unit and a front-

end MC68010 microprocessor to control input-output processes (see figure). Peripherals are connected to the front-end processor, and the bus and front-end processor bus are connected through a direct memory-access channel. The system program and library routines for ELIS are mainly written in Tao, with some speed-critical portions in microcode. The front-end processing system software is mainly written in C.

For more information, circle 483 on the reader service card.

TECHNOLOGY TO WATCH

JAPAN'S ICOT TRIPLES SPEED OF ITS INFERENCE MACHINE

Tokyo's Institute for New Generation Computer Technology is speeding ahead with its second sequential inference computer. The PSI-II, being developed by ICOT, Mitsubishi Electric Corp., and Oki Electric Industry Co., uses revised software and 8,000-gate CMOS gate-array technology to attain an execution speed in the KLO machine language of 100,000 logical inferences per second (100 klips), on the average, three times the speed of the original PSI.

ICOT, which is charged with developing Japan's fifth-generation computer technology, will use PSI-II as its software development machine, both for single- and parallel-processor systems. The new machine can serve as the building block in a system of 16 to 64 inference machines. The processor

was completed at the end of March; the system is to be finished by the end of the year.

The PSI machines use their own operating system, called Simpos, and the extended version of the Prolog programming language ESP (see table). In the list-append function that is used with high frequency in Prolog, PSI-II reaches 300 klips.

Two changes from the original design tripled the inference speed. The Warren instruction set, first proposed as a Prolog instruction set in 1983 by David Warren, the developer of DEC-10 Prolog, was adopted as the new base for the machine language; and the architecture was reworked.

ICOT also took several steps to improve the execution speed of the code generated by the Prolog compiler. The speed of the built-in predicates was boosted by changing the way their parameters are stored in registers. The researchers streamlined the instruction that extracts the nth element from a list by reducing the number of microsteps from 17 to 13, and they eliminated unnecessary cuts. They speeded up mode selection by incorporating a preselection process that can select the node for execution based on parameter value.

The processor is built around nine 8,000-gate CMOS arrays and fits on three boards. Three internal buses are used: two source buses and one destination bus. The machine's 40-bit word has 32 bits for data and an 8-bit tag, two of which are used for garbage collection and six for identifying the data type.

Major changes in the second PSI are the expansion of the real address space from 24 to 26 bits and enhancement of the tag architecture. Main memory size was quadrupled to 64 megawords, or 320 Mbytes. Furthermore, multiple name space was adopted with logical space allocated to each process generated, increasing the number of processes from 64 in the PSI to no limit. □

For more information, circle 484 on the reader service card.

COMPARING THE TWO ICOT INFERENCE MACHINES

	PSI	PSI II
Maximum performance	about 33,000 logical inferences per second	about 100,000 logical inferences per second
Machine language	KLO (based on DEC 10 Prolog)	KLO (based on Warren instruction set)
Processor technology	high-speed Schottky TTL	CMOS gate array Am29300 series, etc.
Processor board count	12	3
Cache	4-K words x 2	4-K words
Real address space	24 bits	26 bits
Maximum main memory	16 megawords	64 megawords
Number of processes that can be simultaneously generated	64	no limit
Branch dispatch memory	12 patterns	32 patterns
Processor cycle time	200 ns	200 ns
Word configuration	32-bit data 8-bit tag	32-bit data 8-bit tag
Operating system	Simpos	Simpos
Programming language	ESP	ESP

The preceding three Technology to Watch articles were originally published in Nikkei Electronics, which is published by Nikkei-McGraw-Hill Inc., a joint venture of McGraw-Hill Inc., publisher of Electronics, and Nihon Keizai Shimbun. They were translated by Charles L. Cohen.

Industry response to the Sierra Semiconductor Corp.'s single-bit, electrically erasable programmable-read-only memory has been "overwhelming," says Tom Reynolds, vice president of marketing and sales at Sierra Semiconductor. Since the EEPROM cell family's introduction about a year ago [*Electronics*, March 17, 1986, p. 30], the company has begun incorporating varying degrees of cells in the design of systems for about 10 to 15 customers. It has also talked seriously with at least 100 potential clients interested in using the Sierra approach. Moreover, efforts to make the nonvolatile memory-cell family available to users of a range of popular computer-aided-design workstations is approaching the final stages.


In addition, the company is moving beyond its initial family of single-cell EEPROMs and has developed a series of small EEPROM standard-cell arrays up to 200 bits in density, with no penalty in die size or performance. Also being added to the family are a set of high-voltage interface cells, which allow generation of both 5- and 18-v programming voltages on-chip or the use of an

UPDATE: SIERRA'S EEPROM CELL MOVES INTO DESIGNS

external 18-v source. In development is a set of EEPROM standard cells aimed at portable applications, which allow operation down to 3 V, as well as larger EEPROM cell arrays up to 4,000 bits.

The cell family has already been adapted for the work station from Mentor Graphics Corp., of Beaverton, Ore.; beta-site tests are under way. Testing on versions for the workstation from Daisy Systems Corp., Mountain View, Calif., is expected to begin in April. General release is expected in April for the Mentor version and in June for the Daisy version.

—Bernard C. Cole



TECHNOLOGY TO WATCH

A year after Philips announced its PM3050 family of 50-MHz oscilloscopes, it looks as if the \$5.4 million that the Dutch company invested in its development is paying off, says Pieter Fips, product marketing manager for general-purpose oscilloscopes at the Philips Industrial and Electroacoustical Systems Division in Eindhoven, the Netherlands. Philips set out last year to grab the lead in the world market for general-purpose, medium-frequency scopes [*Electronics*, April 7, 1986, p. 39]. That ambitious goal has not yet been reached, Fips says, "but we have come a big step closer. It's turning out to be a big success."

A key to that success has been the fact that the Dutch engineers departed radically from conventional scope construction. They turned to a one-piece plastic chassis for mounting all component parts, betting that they could cut assembly time by up to 30 times for the 3050 family.

The bet has paid off. Fips thinks the single-chassis construction for the 3050 family puts his company years ahead of its competitors. The savings achieved with it are so encouraging that the firm may use the one-chassis concept for future instruments as well.

Building, testing, and calibrating the new models and stuffing the printed-circuit boards needed for them takes a bit more than five days, compared with about eight weeks for a conventional Philips scope. Computer-controlled components-sequencing for the pc boards and automated processes for components placing and solder-

UPDATE: PHILIPS SCORES WITH LOW-COST SCOPES

ing shorten the flowthrough. Automated testing and the use of click-fit mountings, snap-in fixtures, and stops and posts instead of screws, rivets, and metal supports also help. And the one-chassis concept means actual assembly takes only 20 minutes instead of around 10 hours for other scopes.

The savings help keep the scope's price low—\$1,245 for the single-time-base PM3050 and \$1,345 for the dual-time-base PM3055, which Fips says is less than most other general-purpose models. The low price, combined with such user features as a clear display and a microprocessor-controlled autotest key that automatically optimizes various settings, has been a big factor in the success of the 3050 family so far. "We have about doubled the quantity shipped," Fips says.

Actually, the company would have performed better had it not been for the drop in value of the U.S. dollar. "That has given [market leader] Tektronix a big pricing edge on European markets with a low-cost scope it introduced last year," the Philips manager says.



**New cell compilers can
make your ASIC design
really blossom,**



Thanks to Gould.

Introducing the revolutionary application-specific IC (ASIC) cell compiler, SCORE™.

With SCORE™, we create a new cell in one-tenth the time—usually less than a day. And that includes exhaustive design verification and full documentation. In short, you get a custom, proprietary circuit in little more time than a standard cell design—even with analog. Anyone can see the beauty in that.

SCORE™ generates cells a new way.

Typical cell compilers patch together pre-defined function blocks. The only way to customize performance is to stretch or connect gates in parallel. Not very efficient.

SCORE™ configures cells from spatial and performance definitions. You customize by

simply changing cell definitions: propagation delay, load, cell height, function, functional options, feature size and process. SCORE™ “tunes” it to the rest of your circuit.

SCORE™ outputs geometrical mask data, a simulation model, a netlist for reverification, placement and routing frame data, and a data-sheet. The system also performs a design rule check and resimulation.

The bottom line? A true cell-based custom circuit. A layout virtually as tight as hand-drawn. And a lot of never-before-available time on your hands.

Bring your ideas into full flower at Gould.

To find out more about Gould and our cell compilers, call (408) 554-2311 and ask for the brochure, “ASIC Design: A Continuum of Alternatives.” Or write Gould Semiconductors, 3800 Homestead Road, Santa Clara, CA 95051. See if we don't grow on you.

Manufacturer of Gould AMI Semiconductors.



GOULD
Electronics

Circle 77 on reader service card

A MAJOR FACELIFT STARTS FOR STRATEGIC RADAR NETS

Recent advances in solid-state phased arrays and power devices and in pulse compression and signal processing are reshaping U.S. defenses against aircraft and missile attacks

by Marce Eleccion

In a major revamping of its continental defense system, the U.S. Department of Defense has begun a multibillion-dollar program to replace or supplement its aging strategic radar networks with the newest radar technology. What's making this revamping possible is the application of state-of-the-art electronics technology—both to update or replace decades-old radar systems and to provide the circuitry and computing needed to implement highly advanced systems.


Playing major roles in the new radars are fully solid-state phased arrays that include solid-state power generation, pulse-compression techniques, and digital signal processing. Other factors expected to influence future radars are monolithic microwave integrated circuits; adaptive arrays; fiber optics; and new VLSI fabrication methods, some of which are derived from the Pentagon's Very High-Speed Integrated Circuits program. Not only do these technologies greatly enhance radar performance, versatility, and reliability, they also make systems that are smaller, lighter, and less power-hungry. Above all, today's systems can be built at dramatically lower costs.

As a prime thrust of the revamping, the U.S. is installing a new radar system based on over-the-horizon backscatter technology, which can detect objects at far greater distances than conventional radars can. A related radar system, the North Warning System (see fig. 1) is replacing the Distant Early Warning, or DEW, Line that has stretched across northern Canada since the mid-1950s. These radars search for aircraft and cruise missiles that fly in the atmosphere.

The DOD also is about to begin its second upgrade of the Ballistic Missile Early Warning System, or BMEWS, which was built in the 1960s to detect high-flying missiles reentering the atmosphere from the north. And it is modernizing the Perimeter Acquisition Vehicle Entry Phased-Array Warning System (PAVE PAWS), which watches the eastern, western, and southern perimeters of the U.S. PAVE PAWS, which dates only from the early 1980s, is another system that searches above the atmosphere for intercontinental or submarine-launched ballistic missiles.

The most advanced radar of all is still under wraps. It is the Terminal Imaging Radar, which is part of the Reagan Administration's massive Strategic Defense Initiative.

One key existing radar is the Joint Surveillance System, or JSS, which monitors all airspace



1. GUARDIANS. The North Warning System, monitoring the electromagnetically noisy Arctic skies, will supplement four over-the-horizon backscatter radar systems.

within 200 miles of the North American continental borders for low-flying supersonic aircraft and cruise missiles. Developed and built by Hughes Aircraft Co.'s Ground Systems Group, Fullerton, Calif., the JSS integrates existing U. S. Air Force and Canadian surveillance radars with the enormous coverage afforded by the Federal Aviation Administration's civil air-traffic control system. The JSS saves \$100 million a year in operation and maintenance costs over the Semi-Automatic Ground Environment and Back-Up Interceptor Control (SAGE/BUIC) systems it replaced, says a Hughes Aircraft spokesman.

However, despite the extensive coverage provided by JSS, its 200-mile coastal range was not considered adequate for early warning against the new breed of low-flying aircraft and cruise missiles. As a result, two major programs are under way: an over-the-horizon backscatter (OTH-B) radar network designed to detect low-flying missiles and aircraft approaching the continent from the east, west, and south, and the North Warning System, aimed at northern approaches.

UPGRADING ATMOSPHERIC SYSTEMS

Comprising 12 sectors, each radiating 60 degrees outward from the boundaries of the U. S., the OTH-B effort represents the first major attempt to detect targets by reflecting high-power, high-frequency signals off the ionosphere and using the returning backscattered data to determine target range and bearing. In each sector, twelve 100-kW transmitters bounce 5-to-28-MHz signals off ionospheric layers 50 to 250 miles above the earth's surface. OTH-B radars can detect objects at a range of 500 to 1,800 nautical miles.

To avoid signal interference, each OTH-B radar is separated into transmit and receive sites situated some 50 to 100 miles apart in a technique known as bistatic radar. A third site serves as an operations center to process signals, control radar activities, and provide accurate target discrimination.

OTH-B technology has been available for more than a decade, says program director Col. James A. Lee of the Air Force, but "only recently have the signal-processing and computer capabilities been developed to make such a system practical." OTH-B systems use Doppler radar, which discriminates targets by speed. They also must be able to separate the enormous amount of civilian traffic (both planes and ships) and environmental clutter (birds and large waves, for example) from true incoming threats. Such discriminatory capabilities and the complex modes of OTH-B operation require great computational power.

The OTH-B network is grouped into the East Coast Radar System (ECRS), the West Coast Radar Sys-

tem (WCRS), the Central Radar System (CRS), and the Alaskan Radar System (ARS). The ECRS consists of three sectors in Maine: three transmission sites in Moscow, three receiver sites near Columbia Falls, and an operations center at the Air National Guard base in Bangor (see fig. 2). Being built by General Electric Co. under a \$550 million contract issued by the Air Force in June 1982, the ECRS provides 180° coverage and is to be completed by 1988.

The WCRS, which also has three sectors, will provide 180° coverage from three transmitters in Buffalo Flats, Ore.; three receivers in Rimrock Lake, Calif.; and an operations center at Mountain Home Air Force Base, Idaho. Construction on the operations center began in July 1986, and work on the transmit/receive sites begins this spring. A \$315 million contract for hardware, installation, and testing of WCRS was awarded to GE last December.

Although funding for the other two OTH-B systems has yet to be approved by Congress, \$600 million for the CRS and \$450 million for one sector of the ARS have been requested by the Air Force in the fiscal 1989 budget. Four sectors, plus an operations center at Grand Forks Air Force Base, N. D., have been slated for CRS, which will provide 240° southern coverage. Two sectors have been planned for ARS, which will face 120° northwest and will have its operations center at Elmendorf Air Force Base, Alaska.

It has been impossible to design an OTH-B system that can operate effectively to the north, because of electromagnetic disturbances in the Arctic atmosphere, as manifested by the aurora borealis. To span the northern approaches between the eastern and Alaskan OTH-B systems, work has begun on a series of 52 radars across the outer edges of Canada: the North Warning System, or NWS. Designed to replace the aging DEW Line and to supplement the Air Force's 13 SEEK IGLOO solid-state radars built in Alaska in 1979, the NWS will consist of 13 minimally attend-



2. OTH-B OPERATIONS. The first sector of the east coast OTH-B system in Maine should be fully operational late this year. Display and processing are conducted at this operations center in Bangor.

ed long-range 1.2-GHz L-band radars, with a range of up to 280 miles, and 39 unattended short-range radars scanning as far as 90 miles, to fill the gaps in between the L-band installations. When completed in 1992 at an estimated cost of \$1.3 billion, the NWS will be linked to the Canadian and Alaskan control centers. It will save almost \$50 million in annual operating costs

The 52 radars in the North Warning System will monitor the Arctic skies, where electromagnetic disturbances preclude the use of OTH-B radars

over current systems, says U.S. Air Force Lt. Col. William Steele, deputy program manager for the NWS.

A \$59 million contract to build the first 10 long-range L-band radars was awarded to GE in early 1985. Each of the radars uses a planar phased-array antenna that is two-dimensionally phase-scanned in elevation while mechanically rotated within a radome to provide the third dimension. Half of these long-range radars are expected to be deployed by next year, Steele says.

These long-range L-band radars produce raw data that must be processed at sites many miles away, but the 39 short-range radars are sophisticated enough to not only process much of their own data but also to correct any faults that may be detected in the system. "The system can even

make decisions concerning the validity of a target, transmitting only valid threats to the control and command center," claims Charles Zarembo, vice president of advanced systems at Unisys Corp., Great Neck, N.Y. Unisys received \$80 million in September 1985 to build three of the short-range radar prototypes, which will be in production by mid-1988.

"In addition, there is a complete automatic-test-equipment check every 6 or 7 seconds to assess system operation," says Zarembo. Because of built-in redundancy, the system can switch to backup circuits to remain in service.


The two-dimensional phased-array system uses an innovative method to obtain its third dimension, elevation. Instead of rotating a planar antenna, the active dipole elements are configured in a fixed cylindrical phased array. The 72-column array can cover a full 360° by phase-scanning 60 vertical columns at a time to form a 300° beam and then step-shifting around the cylinder by 1-column, or 5°, increments. To cover both short and long distances at the same time, there are two dipoles per column.

Traditionally, the thrust of U.S. defenses has been toward threats that may come from above the atmosphere. Toward this end, BMEWS, one of the oldest U.S. radar systems, is about to be overhauled for the second time in two decades. By June, the Thule, Greenland, radar site (see fig. 3) is expected to be converted from tube-driven power to solid-state phased arrays using not only transmitters with bipolar-silicon uhf transistor power amplifiers, but also active array elements driven by solid-state transceiver modules. As part of the BMEWS modernization program, aging computers for a missile impact predictor are being replaced with off-the-shelf computers, and assembly-language software is being translated into a higher-order language.

The 10-story-high Thule structure has two 84-ft-square faces that look north. Each face covers an angle of 120° and contains 2,560 active and 1,024 dummy elements. The cost of the conversion, to be performed by Raytheon Corp.'s Equipment Division, Wayland, Mass., is estimated at \$95 million.

The upgrading of a second BMEWS site, situated at Fylingdales, UK, is scheduled to begin in June. This three-faced radar has a full 360° coverage, which will place a considerable load on the system's processing power. A decision on a third site, in Clear, Alaska, is expected sometime within the next few years.

The march of technology has already outmoded the first two of the four PAVE PAWS installations. PAVE PAWS, the first large-scale solid-state phased-array radar, is a twin-faced 420-to-450-MHz uhf system with a range of 3,000 nautical miles (see fig. 4). Designed by Raytheon, its four systems are strategically placed in the U.S. to warn against ICBM/SLBM approaches from the east, west, and south—the same directions as the OTH-



3. UPGRADE. The first of the BMEWS radar upgrades, this solid-state installation at Thule, Greenland, will be completed by Raytheon within the next few months.

B radars, which are confined to the atmosphere.

With 1,792 active and 885 dummy antenna elements per face, each PAVE PAWS system has considerable room for upgrading performance, since only 73 by 73 ft of each 103-by-103-ft face are currently covered. Each element is powered by a module containing four 100-W transistors in parallel; 32 modules make up a subarray, with 56 subarrays per face. This enables an extremely long mean time before failure: 100,000 hours, compared with older tube-driven systems, such as Raytheon's COBRA DANE system—currently used to monitor Soviet ballistic-missile tests from across the Bering Sea—which has a 20,000-hour MTBF. The foot-long, 28-v modules are also easier to replace than COBRA DANE's 5-ft, 40,000-v tubes. There are ninety-six 160-kW traveling-wave tubes in all, each driving 160 of the system's 15,360 elements.

One of the advantages of the PAVE PAWS design is relatively low power loss through the system, since signal amplification does not occur until after the signal has been divided among the antenna elements and phase-shifting has already taken place. To offset the lower peak power resulting from solid-state transmission, pulse-coding and pulse-compression techniques are used.

In 1982, the Air Force decided to upgrade the power of the two initial PAVE PAWS sites at Otis Air Force Base, Mass., and Beale Air Force Base, Calif., to 10 dB and to build two additional sites—a \$90 million southeast-looking installation at Robins Air Force Base, Ga., that became operational in October 1986, and a \$70 million southwest-looking unit at El Dorado Air Force Station, Texas, scheduled to be finished in May. Both contracts were awarded to Raytheon.

When completed in 1990 and 1991, respectively, Otis and Beale will have the same computers and displays as Robins and El Dorado: a Control Data Corp. 865 main computer, a Modcom radar controller, a Raytheon signal processor, and Raytheon graphic-display consoles. Expected to be completed by April 1990, the 10-dB Otis and Beale upgrades effectively triple the number of active antenna elements on each face to 5,376.

Although the original upgrade request for Otis and Beale was temporarily halted by DOD budget cuts, a contract will be awarded to Raytheon in June, says an Air Force Electronic Systems Division spokesman. Raytheon will modernize the processing and display capabilities of these sites and will triple the number of active antenna elements at Robins to 5,376 by April 1990.

"The Robins system is particularly important, since it will eventually replace the Eglin Air Force Base AN/FPS-85 space-tracking radar in Florida," says Tom Pucci, PAVE PAWS program director. When finished, the upgrades will give the U.S. greater tactical warning and attack-assessment capability, because the systems will be able to track at greater ranges, detect smaller objects, and discern a greater number of targets.

"Even now, the Otis system can track an object the size of a Volkswagen Bug over London," Pucci adds.

On the defense horizon is the proposed Terminal Imaging Radar, a wide-ranging program to detect and intercept missiles such as ICBMs and SLBMs. Details of the program are closely guarded, because it is part of the Strategic Defense


The first phase of SDI will be to build Terminal Imaging Radar to search for, find, and track approaching missiles; experts say all the technology now exists

Initiative. After two-year contracts with Westinghouse Electric Corp., Baltimore, Md., and Raytheon to submit design proposals, the SDI directorate on March 27 awarded Raytheon a \$174 million, 51-month contract by the Army Strategic Defense Command to build the first Terminal Imaging Radar (TIR) for testing at the Kwajalein Atoll in the mid-Pacific Marshall Islands.

Major subcontractors on the TIR contract are Hughes Aircraft, which will fabricate traveling-wave tubes to drive the radar; Control Data, for computer hardware; TRW, for software development; Wright Schuchart Harbor Co., for turret fabrication; and M/A-COM Microwave Circuits Inc., which will provide a corporate feed system for the transmitter.

TIR, a major factor in determining the success of SDI, will be watched closely—especially by critics who question the program's feasibility. The new radar will be expected to search for, find, and track approaching targets and discriminate those that are potentially dangerous from the wide range of natural and man-made clutter surrounding the planet. TIR will include a direct link to airborne optical sensors as part of its input.

Radar experts say that the resources are available to complete the TIR phase of SDI. Many of these resources are derived from the wide variety of strategic and tactical radar systems built by the military over the past few years. □



4. PAVE PAWS. The first of four solid-state PAVE PAWS sites, this phased-array radar at Otis AFB, Mass., covers 240° and has a range of 3,000 nautical miles.

Quantity

A few today. A few tomorrow
Thousands today. Thousands tomorrow

The choice is yours. Because our new OTP plastic EPLDs give you both the production volumes and production control so crucial to your business.

Look how the whole process works. You design and develop your logic device with our EPLDs. Which means you can do in hours what used to take months.

Then you mass-produce your design with our OTP parts. Saving countless weeks because you don't have to wait for custom parts.

The result is the most cost-effective way to take a project from design through production.

And a fool-proof way to eliminate inventory risk. You get only the quantities you need when you need them. Without having to commit to dedicated inventory. Or an inflexible delivery schedule.

Plus, if you ever have a few of our blank OTP parts left on the shelf, you're not stuck. You can program them to become a new product. Or a successful older one. Or anything you like. Including the brainstorm that emerged after prototyping. It's like having a standard part you can customize at will.


Now before you get the idea we're only selling quantity, let's talk quality. Our plastic logic devices are based on Intel's CHMOS EPROM manufacturing process. And credit where credit's due, it's a process that has paid off with the most reliable OTP plastic parts in the industry.

So be assured. You can get the quantity you want. In gate counts from 300 to 2000. With reliability included. It really is quite a story. Call today for all the details. Because we can produce volumes on the subject.

Call (408) 984-2800

ALTERA

3525 Monroe Street
Santa Clara, CA 95051



CHMOS is a patented process of Intel Corporation.

Distributed in U.S. by Alliance, Pioneer, Quality Components, Schweber and Wyle. In Canada, distributed by Future.

© 1986 Altera Corporation

Assurance.



VHSIC FINALLY BUILDS A HEAD OF STEAM

Phase 1 got off to a slow start, but the controversial Pentagon R&D program is now rapidly moving the advanced chips into military hardware

by Larry Waller

The Pentagon's controversial and expensive Very High Speed Integrated Circuits project has finally gotten its act together. Following some midcourse disappointments with the program, on which government and the industry have spent more than \$1 billion in its first seven years, 1986 saw VHSIC make real progress toward the primary goal: placing advanced chips into new designs or improving existing designs by retrofitting the chips. At the same time, technological fallout is adding to the program's benefits (see report card, below).

There was a great deal of early enthusiasm for VHSIC, but that had worn thin because of delays in delivering samples of the chips developed in Phase 1 for evaluation. One result of these lags was that sockets earmarked for VHSIC devices were filled instead with semicustom gate arrays. The picture changed rapidly in the past year. Managers of 37 electronic weapons system programs for all three branches of the armed services have committed to the chips, under heavy prodding from the Department of Defense. And the best times for VHSIC are ahead. For example, none of the current contracts covers the huge Air Force Advanced Tactical Fighter program, for which VHSIC technology will likely be used in a big way.

The brighter outlook comes none too soon for VHSIC supporters, who have had little to crow about in recent years. "During 1986, a number of significant milestones were passed," reports E. D. (Sonny) Maynard Jr., who has directed the VHSIC Program Office, in the office of the Undersecretary of Defense Acquisition, since 1982. Maynard was recently promoted to director of computer and electronics technology, but he still oversees VHSIC.

The big news is that the 1.25- μ m chips from Phase 1, which started in 1981 and is now winding down, are now in good supply from six contractors. Furthermore, "the performance advantages of the chips have been demonstrated in operational systems," Maynard says. Now, lessons learned from patch-

REPORT CARD: GRADING THE VHSIC PROGRAM

Subject	Grade	Comments
Insertion of high-performance VLSI in military systems	I	(Incomplete) Prototypes are just arriving on the scene. But prospects look good as the military becomes aware of the chips' potential
Actual design-ins	B	There has been a lag of up to two years in chip delivery; doubts about availability remain
Cutting weapons-systems development time	I	(Incomplete) It is too early to judge
Reducing custom-chip cost for military	B+	Even present lofty VHSIC-chip prices—\$3,000 and up—are lower than custom ICs of the past; prices will drop sharply if volumes rise as planned
Pushing the state of the VLSI art	B+	Many advances have been made
Bipolar processes	A	The commercial state of the art has been leapfrogged; VHSIC serves as a process driver
MOS processes	B+	VHSIC has paced commercial development
Architecture	C+	An early compromise on general-purpose structure led to an extensive redesign to meet specific requirements
Feature sizes	A	For now, military devices are equal to production commercial devices
Computer-aided-design tools	A	Users claim efficiencies higher than those gained in the commercial world. The program could help set future CAD standards
Electron-beam lithography	D	The 0.5- μ m line-width goal was probably too ambitious for the program's tight schedule
Manufacturing	B+	Yields are acceptable, after a slow start
Self-testing ICs	A	The program has been so successful in this area that it is being copied by commercial IC houses
Packaging	A	High-pin-count and surface-mount techniques have been developed by most suppliers

ing up Phase 1 have been cycled into the planning and structure of the more ambitious Phase 2 (see p. 91), which specifies 0.5- μ m features.

Of particular interest to users is the fact that Phase 1 ICs from all six contractors are well on their way to being added to the Qualified Parts List for military procurement, says Maynard. The six are Honeywell, Hughes, IBM, TRW, TI, and Westinghouse.

Although the VHSIC insertion program is still in its earliest stages, most participants are confident it will be successful, given the strong backing of the DOD and the military systems manufacturers. But it is becoming clear that the VHSIC effort will have an even broader effect, as a technology and business driver for the U.S. semiconductor industry. Not only are useful technological advances emerging, but formerly uninterested companies are now seeking an eleventh-hour entrée to the VHSIC program. For example, Intel is qualifying its 80286 and 80386 microprocessors to Phase 1 requirements; National Semiconductor is offering a VHSIC foundry service; and systems maker Raytheon has invested \$40 million in a new VHSIC-oriented Microelectronics Center.

The reason for the wave of interest is obvious to Dallas Burns, director of digital technologies at the research and development operation of Honeywell Inc.'s Solid State Electronics Division in Plymouth, Minn. The company is a prime contractor for VHSIC Phase 1 and Phase 2. "Just as important as specific VHSIC chips, the program has raised the technology stakes when it comes to competing in military chip markets," he says.

At Texas Instruments Inc., Dennis Best, manager of IC development for the Defense Systems & Electronics Group in Dallas, notes that VHSIC played a pivotal role in pushing commercial processing to the 1.25- μ m region more rapidly.

VHSIC contractors and program managers offer further examples of the technological fallout:


- **Advances in bipolar processing.** VHSIC became the main bipolar driver during the early 1980s, says Best. Consequently, TI is benefiting in non-VHSIC devices, he says, and he thinks Honeywell is, too. The Honeywell chips "are generally considered to be the most complex bipolar logic chips ever produced," says Burns. To be able to fabricate these chips in integrated Schottky logic and current-mode logic, Honeywell developed its VHSIC 1.25- μ m bipolar process with three layers of metal—a major improvement over the standard two layers.

- **Computer-aided design tools.** Developed by individual contractors, VHSIC CAD has achieved productivity levels beyond those attainable with commercial packages, the contractors say. At Honeywell, for instance, "one-pass success" through the CAD system is now considered the norm. Program managers at both IBM Corp.'s Federal Systems Division in Manassas, Va., and TRW Inc.'s Electronic Systems Group in Redondo Beach, Calif., report similar experiences.

- **The VHSIC Hardware Description Language.**

The cornerstone for the Phase 2 design-automation system, the VHSIC HDL could become a standard for CAD. Not only does it help standardize software development among contractors, it is also precipitating many proprietary products. IBM, for instance, is producing an HDL version of all its VHSIC chips for a cell library. And Honeywell is working on a "behavioral VHDL synthesis system" that will generate a chip architecture from a processor's instruction set.


- **Commercial fallout.** Honeywell is energetically



1. CLASS 10. A worker at Honeywell's facility in Colorado Springs, Colo., prepares to insert a 6-in. wafer in a thin-film analyzer.

transferring its VHSIC experience to commercial developments, and TRW is marketing its line of 13 Phase 1 VHSIC devices. A prime example of commercial fallout is Motorola Inc.'s 32-bit 68020 microprocessor. VHSIC research in Motorola's Semiconductor Products Sector led to significantly increased performance, says a Motorola executive.

All this is a sweet victory for those who have insisted all along that VHSIC was the answer to the lack of interest by semiconductor makers in the advanced digital signal processors needed by military systems. The program was set in motion in 1979, when the Defense Science Board judged that such action, financed and directed by the



2. A BARGAIN. Texas Instruments Inc.'s VHSIC 72-K n-MOS static random-access memory chip now sells for only \$2.25.

DOD, was the only way to get the needed DSPs.

But, as has happened before in military R&D, to justify the program, planners set goals that were too lofty. VHSIC fell into this trap by attempting a task that was difficult to do in the time allotted. The program made its debut in 1980 with great fanfare, promising brassboard prototypes by 1984 and expecting to leapfrog the commercial state of the art in design and production. But, for instance, proven 1.25- μ m bipolar processes did not even exist then.

The ensuing technical shortfall caused scheduling delays that were impossible to make up. Says one VHSIC program director, "it was a bad tactical error, ballyhooing too soon, then not being able to supply devices on schedule." Participants think two things saved the program: the impressive performance of the Phase 1 chips, and deft management by Maynard.

Maynard is credited with an accomplishment more common in the commercial arena than in military contracting. When he took control, Maynard recognized that key parts of VHSIC were in deep trouble.

One obvious gap was that the initial Phase 1 program did not provide for chip "interoperability," or device compatibility—a mix-and-match feature many users needed. "They were literally building a Tower of Babel for themselves," says one executive at a VHSIC contractor. To correct it, Maynard instituted a program to establish a functional standard that would enable VHSIC chips to work together. In Phase 2, IBM, TRW, and Honeywell have a bus interface, known as the Pi-Bus standard, that does this job.

Also, a yield-enhancement effort was started

at about the same time, and is now paying off. IBM, for one, believes that this manufacturing research could lead to the most significant technology fallouts of all. The company points out that for signal-processing elements, VHSIC yields climbed from 1% or 2% all the way to 34%. And Honeywell says its 6-in. wafer front-end is now seeing 40% yields (see fig. 1).

Reacting to the arrival of commercial gate arrays, which had not been foreseen by the original VHSIC planners, VHSIC officials encouraged contractors to add them to their programs. One example is Hughes Aircraft Co., which developed a channelless array with up to 40,000 equivalent two-input gates. With such additions, VHSIC exhibited a flexibility rare to such programs, industry veterans agree.

Still, some problems persist. The prices of certain VHSIC chips are still high. The initial plans contemplated premium prices but figured that increased sales would keep prices within range of commercial levels. However, TI, for instance, has to sell its bipolar version of a processor meeting the 1750A military standard for \$3,200 each. The company hopes that higher volumes by 1990 will bring that price down to \$400 or \$500. Thanks to the economies of scale of n-MOS production, TI has been able to price its VHSIC 72-Kbit n-MOS static random-access memory at \$2.25 (see fig. 2).

DISPELLING RESISTANCE

The limited-payoff scenario is a classic one in military procurement and is used to justify reluctance to take the risks inherent in technology improvements. That resistance is exactly what VHSIC's organizers were aiming to dispel, recalls Richard D. DeLauer, who was one of the program's earliest champions, first at TRW Inc. and later at the Pentagon as assistant secretary for technology. "We wanted to make the services step up to [IC technology] and kept pounding on them to do it," says DeLauer.

Not surprisingly, Maynard believes that the fact that substantial progress has taken place stands out dramatically. "We have succeeded in raising [the military's] level of consciousness. There is a clear recognition that this semiconductor technology is something that they must pay attention to, and not just because [the Office of the Secretary of Defense] will be looking over their shoulders. They're also aware of VHSIC's vast increase in performance in terms of reliability and capability. To that degree, the program has been wildly successful."

VHSIC has indeed pushed military chip technology a big step forward. But it remains to be seen whether military procurement policies can be updated as well, to offer hope that VHSIC chips can be put to use before they become yesterday's technology. □

Additional reporting came from Wesley R. Iversen, J. Robert Lineback, Tobias Naegle, and Ron Schneiderman.

Your very own system specialist **PCA**


The process controller for
interference-free
automatic measurements



Choose your favourite model from this family of process controllers: PCA 2/5 with 80186 CPU or PCA 12/15 with 80286 CPU plus co-processors 80287 and 80186, all rackable 19" units. External interference and RF leakage are extremely low complying with VDE 0871/0875, limit class B. And the storage space? 1-Mbyte RAM, 1.2 Mbyte on 5 1/4" floppy disk drive (two drives, if required) as well as formatted 21.3 Mbyte on Winchester disk drive (option) are there to be used.

Interfaces

IEC/IEEE bus, RS-232-C, Centronics, TTL I/O (56), 14 bit D/A, Multibus I (PCA 12/15 only).



Software

MS-DOS 3.1, extended Basic incl. interfaces, extended Pascal incl. interfaces, UDI, XRUN, Kermit, dBase II, Wordstar, Knowledgeman, Multiplan, Pictures graphics software (PCA 12/15 only).

Test software

RT tests, impedance measurements, useful and interference signal measurements, audio analysis, intermodulation measurements.

And of course: **custom test software developed by our system specialists.**

Ask for details on Process Controllers PCA.

Rohde & Schwarz
Postfach 80 14 69
D-8000 Muenchen 80
Federal Republic of Germany
Telex 523 703 (rus d)
Tel. internat. + (49 89) 41 29-0

There are **R & S agencies** in 80 countries.
We plan and supply stationary and mobile
systems, also on a turn-key basis.
R & S services comprise installation, maintenance,
calibration, training and documentation.



ROHDE & SCHWARZ


Circle 117 on reader service card

The only electronics directory you need. . . 1986--'87 Electronics Buyers' Guide Coming in September

The 1986-'87 Electronics Buyers' Guide. Completely new listings of catalogs, new phone numbers, new addresses, new manufacturers, sales reps, and distributors! The total market in a book—**three** directories in one!

1.

Directory of products.
Over 4,000 products, over
5,000 manufacturers.



2.

Directory of catalogs.
Includes six post-paid
catalog inquiry cards for
10-second ordering.

3.

Directory of
manufacturers. Local
sales offices, reps, and
distributors, with phone
numbers. Number of
employees and engineers,
dollar volume, name of
company contact.

**The only book of its
kind in the field.**

**If you haven't got it,
you're not in the market.**


**To insure prompt delivery
enclose your check now.**

Price: \$50 per copy
(Add \$30 for air mail)

Send order with payment to:
Barbara Copcutt
Electronics Buyers' Guide
McGraw-Hill House
Maidenhead SL6 2QL, England



MIXED SIGNALS.



Teradyne's A500 mixed-signal test system includes a universal 120-pin test bead, two Sun Microsystems work stations, and the Image test-development software.

Teradyne incorporates two testers in the same package.

“A new class of mixed-signal chips is posing a particularly nasty set of problems to the test-systems community. Not only do these chips make greater demands on testers in the analog domain, but many of them carry much more complex digital circuitry than standard mixed-signal test systems are equipped to handle.

Now Teradyne Inc. says that it has developed the first tester specifically designed to handle this difficult mixed-signal test problem, all in one pass. The Boston company claims that by eliminating the need for custom hardware and streamlining the software, it has made a tester that can cut the test-development cycle for complex mixed-signal chips in half...”

Excerpted from an exclusive article in the January 22, 1987 issue.



Electronics

**THE LEADER IN NEW
TECHNOLOGY COVERAGE**

Speed up your data measuring techniques with our instruments for in-service measurements: battery-powered, portable, reliable



With our pocket-sized data comm test sets, you are ready practically anywhere and at any time. Up to five instruments can be packed in the DMS-1 Data Measuring Set carrying case, including cables and a.c. adaptor/charger.

★ **DMT-1 Modem Tester**, for testing V.24/V.28 synchronous and asynchronous modems: bit and block error rates; telegraph distortion measurements.

★ **DLM-20 Data Line Test Set** for impulsive noise and interruptions according to CCITT Recs. O.71 and O.62, particularly for data traffic on voice-grade circuits.

★ **DV-24 and DX-21 Interface Testers** for checking, patching, and simulating at V.24 and X.20/21 interfaces.

★ **SZU-969 Speech Attachment** for the test circuit.

★ **PM-10, PM-20, PMP-20, PM-928 Digital Level Meters** for level, d.c., and noise meas-

urements with 0.1 dB resolution. Types for: 15 Hz to 20 kHz; psophometer, wideband measurement, filter for ED 1000.

PS-10, PS-20 with 10 or 30 fixed frequencies, to 4 or 20 kHz resp. Level steps of 0.1 dB.

A detailed color brochure offers you more than these key words. Ask for one now.

Information Coupon

Please send me:

- ☐ the "DMS" Color Brochure
☐ your Product Line "Data Measurement Technology"

Name

Company

Address

Tel. No.

Wandel & Goltermann

P. O. Box 12 62 · Abt. VMW

D-7412 Eningen u. A.

Fed. Rep. of Germany

Tel. + (49) 71 21-86-0

Telex 7 29 833 wug d



Circle 118 on reader service card

IT'S TIME TO GET OUT OF THE DARK.



Open your eyes and see just how many subjects are covered in the new edition of the Consumer Information Catalog. It's free just for the asking and so are nearly half of the 200 federal publications described inside. Booklets on subjects like financial and career planning; eating right, exercising, and staying healthy; housing and child care; federal benefit programs. Just about everything you would need to know. Write today. We'll send you the latest edition of the Consumer Information Catalog, which is updated and published quarterly. It'll be a great help, you'll see. Just write:



**Consumer Information Center
Department TD
Pueblo, Colorado 81009**

A public service of this publication and the
Consumer Information Center of the
U.S. General Services Administration

VHSIC MOVES HEADLONG INTO THE SUBMICRON STAGE

Building on a slow but very successful Phase 1 effort, the VHSIC program is moving full speed ahead into its second phase. At least 16 companies can now turn out chips to meet the Phase 1 specifications for the Defense Department's Very High Speed Integrated Circuits; already they have produced some 40,000 chips. Phase 2 takes VHSIC from a technology of 1.25- μ m geometries and chips with clock rates of 25 MHz to chips with 0.5- μ m geometries that clock at 100 MHz. In Phase 2, chip density is escalating from 100,000 devices to more than 500,000 per chip, and chip pinouts from 100 to more than 300.

These performance breakthroughs flow from advances in IC processing, lithography, and packaging. Phase 2 has already seen the introduction of extremely large "superchips" with up to 34.7 million devices, including self-contained spares for chip self-repair; complex chips with built-in test; complex multichip packages; extensive use of electron-beam direct writing; and the introduction of three new high-resolution, high-throughput lithography tools based on e-beam, X-ray, and optical lithography.

So far, Phase 2 has avoided the delays that slowed Phase 1. The first phase is now making real progress (see p. 84). And the technology is spreading: the Pentagon's VHSIC Program Office reports that 10 chip makers besides the original six Phase 1 contractors can turn out 1.25- μ m integrated circuits.


THREE PHASE-2 CONTRACTORS

VHSIC's second phase has only half the number of contractors Phase 1 had. The three participants are TRW teamed with Motorola, Honeywell, and IBM. TRW's Phase 2 family of devices is the most advanced of the three competitors, being based on the superchip concept and 0.5- μ m CMOS technology. Honeywell, on the other hand, will make its VHSIC devices with a 0.5- μ m four-layer bipolar process, but it is using the most advanced packaging technology in its multichip, multilayer module. IBM has chosen the most conservative approach by developing its ICs from a 1- μ m CMOS process and then migrating to a final 0.5- μ m version after design verification. IBM uses its established flip-chip and multilayer ceramic technology for its multichip module.

TRW has designed six superchips, of which three—a mass memory, a signal processor, and a convolver correlator—are being funded by the

Building on a successful Phase 1, Phase 2 is aimed at 0.5-micron geometries that clock at 100 MHz, chip densities of more than 500,000 devices, and pinouts over 300

by Jerry Lyman



1. VHSIC PROCESSING. TRW fabricates its VHSIC Phase I and II chips in its Class 10, vibration-isolated processing line in Redondo Beach, Calif.

Pentagon [*Electronics*, July 10, 1986, p. 49]. It's up to the Defense Department to decide whether to fund the remaining three—a Fast Fourier transform chip, a data processor, and an associative processor. Originally, TRW had planned to implement two of the chips with a bipolar process and to use a CMOS process on four of the functions, but the company now has

Phase 2 packaging is 'a very important part of the program in terms of achieving the high speeds needed,' says Honeywell's Anderson

switched to an all-CMOS approach.

The superchips will range from 1.4 by 1.4 in. to 1.2 by 2.4 in. in size and could carry up to 30 million devices per chip. By comparison, TRW's largest Phase 1 chip has 74,000 devices on a chip about a quarter of an inch on a side. A single 30-million-device superchip would be able to do the work of sixty 500,000-device chips typical of the VHSIC Phase 2 chips, or the work of more than 400 Phase 1 chips.

The superchips incorporate three key concepts that improve reliability and manufacturing yields: self-contained spare components, built-in testing, and software reconfiguration. This new approach to on-chip redundancy enables a superchip to identify its faults, bypass failed devices, and form new interconnections using spare devices, all without user intervention. With this method, TRW believes it can obtain chip yields of 20% to 50%—comparable with the best commercial results for LSI chips.

Another source of superchip reliability is the

reduction in the number of interconnections. One superchip does the work of many Phase 1 chips, so interconnections between chips, the weakest point in any electronic system, are greatly reduced, as fewer chips are necessary.

All of TRW's Phase 1 and 2 chips are being fabricated in its D1 facility in Redondo Beach, Calif. (see fig. 1), which is a vibration-isolated Class 10 IC processing line. Direct-writing e-beam lithography based on a Cambridge Instruments system is used to expose 0.5- μ m details. TRW and Perkin-Elmer Corp. of Norwalk, Conn., are in the process of an acceptance phase for Perkin-Elmer's Aeble 150 direct-writing e-beam system. This unit is slated for pilot-line production of superchips.

The superchips will be housed in large single-layer four-sided flatpacks with up to 320 leads on 25-mil centers. This package is simply an extension of the same technology used on TRW's 132-lead Phase 1 chip (see fig. 2). Because of the efficiency of the superchips' interconnection, the Phase 2 package will probably not have to use its full input-output capability, which is well above 320 leads.

TRW has produced a proof-of-concept 1- μ m superchip, a 700-Kbit dynamic random-access memory with 9.8 million devices. This unit demonstrated redundancy and built-in test features. Prototype superchips are expected in late 1988, a brassboard in 1989, and sample availability for other contractors in 1989.

HONEYWELL'S EFFORT


Honeywell, unlike TRW and IBM, is taking a bipolar approach with its Phase 2 devices. Honeywell's current-mode logic is a 0.5- μ m process with four-layer planar metal and grooved isolation. However, Honeywell is working, on its own, on a 0.5- μ m CMOS VHSIC-like technology.

The company is fabricating three basic chip types that will be used to make a Phase 2 electro-optical signal-processor brassboard: a bus-interface unit of about 45,000-gate complexity that is a custom design, a 50,000-gate configurable array, and a 70,000-gate configurable array. The two large configurable gate arrays will be used to make four circuit designs for the brassboard.

Packaging is "a very important part of the program in terms of achieving the high speeds needed," says George Anderson, VHSIC submicron program manager at Honeywell's Solid State Electronics Division in Plymouth, Minn. "As we get to faster circuits, the interconnect becomes more and more of a factor."

This is why Honeywell has developed for its Phase 2 effort a multichip package (see fig. 3) based on an alumina substrate with alternating layers of copper conductors and polyimide dielectric. These layers are used to fabricate a multilayer structure with signal interconnections and power and ground planes.

This package delivers better electrical charac-



2. FLATPACK. For Phase II, TRW will use a larger version of this four-sided ceramic flatpack with leads on 25-mil centers that was used in Phase I.

teristics than the conventional co-fired multilayer ceramic types that IBM uses. For example, by using polyimide rather than alumina as the insulator, signal propagation in the Honeywell package is about 60 ps/cm, compared with about 100 ps/cm in a conventional co-fired ceramic package. In addition, since the Honeywell copper/polyimide substrate uses IC-type processing, it is relatively easy to put down 1-mil-wide copper conductors, as compared with 5 mils or wider with co-fired ceramic. For its brassboard demonstration in October 1988, Honeywell plans to use a 3.25-by-3.25-in. package carrying seven tape-bonded Phase 2 chips.

Honeywell has set up a pilot production line in Plymouth with three JEOL Ltd. e-beam systems. The plan is to start with e-beam direct write for all layers and then mix optical lithography steps on the less critically aligned portions of the large configurable arrays.

The company is working on the bus-interface unit, the first deliverable chip in the submicron program. "We will be delivering that chip to the government during the third quarter," Anderson notes, adding that the Plymouth pilot line is running at full speed. He plans to transfer this technology to Honeywell's 6-in.-wafer facility in Colorado Springs perhaps next year.


THE IBM TWO-STEP

IBM, which does all its VHSIC work at its facility in Manassas, Va., is first developing a 1- μ m version of its 0.5- μ m CMOS chip set. These interim chips will be available as samples from a pilot line in May and June. After IBM completes this interim phase, a design effort to shrink the 1- μ m chips to their final submicron dimensions will begin. Pilot-line samples of the final chips are scheduled for mid-1988.

IBM has already fabricated four Phase 2 chip types in the intermediate 1- μ m stage: a systolic processor, an address generator, a static 18-Kbit configurable RAM, and a bus-interface unit. These chips, all 5.5 mm², can have up to 220 I/Os. The lithography for these chips was done on IBM's internally developed EL-3 e-beam direct-write systems.

Like Honeywell, IBM's multichip package will accommodate up to 16 chips on a multilayer ceramic substrate in a pin-grid array. However, the IBM chips use the company's C-4 flip-chip process for face-up reflow attachment to the multichip substrate rather than Honeywell's TAB-type attachment. The multilayer ceramic substrate is based on proven IBM technology.

The work of all three contractors will benefit from extensive preparation and support by the Defense Department. Pentagon planners of



3. COPPER POLYIMIDE. To overcome the speed limitations of an all-ceramic package, Honeywell developed a multilayer copper on polyimide structure.

VHSIC Phase 2 realized that high-speed, high-resolution lithography systems would have to be available for pilot-line production of the Phase 2 devices. To provide them, the DOD awarded contracts to Perkin-Elmer for the Aeble 150 and an X-ray stepper and to GCA Corp. of Andover, Mass., for an advanced optical stepper.

Perkin-Elmer's Aeble 150 has design goals of 0.5- μ m resolution, 0.15- μ m alignment accuracy, and a throughput as high as 20 wafer exposures per hour (VHSIC's original goal was four wafers per hour). It is now being qualified for two VHSIC participants, TRW and Motorola.

Perkin-Elmer's X-ray stepper is now about to go into acceptance testing. This unit, with 0.5- μ m resolution, will have a throughput of about 20 wafer exposures per hour and an alignment accuracy of 0.15 μ m.

The most intriguing new lithography tool is GCA's Advanced Wafer Imaging System, or AWIS, a 10:1 optical stepper capable of 0.5- μ m resolution, a throughput of twenty-five 4-in. wafers per hour, and an alignment accuracy of 0.25 μ m with a global-type alignment. With a 0.1- μ m die-by-die alignment accuracy, this system could be the submicron aligner everyone's looking for. It also could cost substantially less than its competitors' machines.

To meet tight price and delivery specs, GCA replaced the light source of one of its DSW 8000 aligners with an excimer laser and the optics with newly designed Tropel lenses. These two features have pushed the optical aligner into the submicron region. The AWIS is being assembled and tested at GCA's Fairport, N. Y., facility for shipment to IBM in May.

In an AWIS-related development, the Army's Harry Diamond Laboratories in Adelphi, Md., recently purchased a KLA/Micron 808 focused ion-beam mask-repair system for repairing defects on reticles for the VHSIC program, such as those the AWIS stepper uses. This Army facility will support any VHSIC Phase 2 reticle activity. □

Additional reporting by Wesley R. Iversen and J. Robert Lineback

SEEKING THE ULTIMATE MICROCODE DEVELOPMENT SYSTEM?



Bit Slice

ASIC

VHSIC

Bipolar
Processors

DSP

CPU
Design

YOUR SEARCH IS OVER!

Speed, support and satisfaction. That's the HILEVEL approach to meeting *your* microcode development systems needs, *without compromise*.

Microprogram development and debug is fast and easy, thanks to highly-productive software development tools combined with the most powerful hardware available. We back each system with unmatched service and support, and *the longest warranty in the industry*.

- **Guaranteed Access Time at Target Side of Pod.**
- **Most Powerful Logic Analyzer, with Exclusive Trace Waveform Display.**
- **Most Advanced Macro-Meta Assembler in the Industry.**
- **Toll-Free Applications Assistance.**
- **Memory Board Exchange Credit.**

And, we'll demonstrate an ease-of-use that invites comparison with any other system on the market.

Avoid compromises. Demand the finest. Call today.

DIAL TOLL FREE:
1-800-HILEVEL
In California, call
1-800-752-5215

HILEVEL
TECHNOLOGY, INC.

18902 Bardeen, Irvine, CA 92715 • Phone: (714) 752-5215 • TELEX 655316 • TELEFAX (714) 752-0724

Circle 127 for "LITERATURE ONLY"

Circle 94 for "TOPAZ DEMO"

MILITARY/AEROSPACE NEWSLETTER

SEMATECH PLANNING IS RUNNING AHEAD OF SCHEDULE AT SIA

The Semiconductor Industry Association's Sematech task force will beat its own June 1 deadline to produce a formal operating and funding plan for the proposed semiconductor manufacturing technology consortium. In fact, the SIA expects to hold a special board of directors meeting no later than mid-May to act on the task force's plans. Funding, establishing operational priorities, government oversight, and creating a tax-exempt status for Sematech have taken up most of the SIA task force's time. One of the group's major concerns when it met in early March to formulate plans for Sematech—how to persuade Congress to grant Sematech an antitrust waiver—apparently is no longer considered a problem. "If Congress decides that it [Sematech] is in the national interest, they'll make it happen," says an industry source close to the task force. Congressional action will have to be taken by July 4 for the consortium to get started this year. □

DOD PICKS CANDIDATE PROJECTS FOR CONVENTIONAL DEFENSE INITIATIVE

The Department of Defense has singled out five major categories of projects it wants to work on for its Conventional Defense Initiative: smart weapons, battle management, high-power microwaves, armor and anti-armor technology, and special technology opportunities—among them "high-temperature" superconductivity. Some 250 candidate projects have been identified among the major categories, say Pentagon officials, who add that a significant portion of CDI's proposed \$5.4 billion 1988 budget will go for target recognition and surveillance, information management, and optical signal processing. CDI program managers will shortly announce an "informational" meeting to discuss the program in detail with potential contractors. □

NAVY SETS ITS PRIORITIES FOR NEAR-TERM R&D

Low-frequency radar and fiber optics, along with antisubmarine warfare, have been given top priority among the Navy's near-term research programs. Richard Rumpf, principal deputy assistant secretary of the Navy for research, engineering, and systems, says the Navy considers the radar work as crucial to an arsenal of techniques it must develop to counter the threat of stealth aircraft and missiles. As for fiber optics, the key concentration will be in missile guidance systems. Rumpf revealed the Navy's R&D thrust at an early-April meeting in Alexandria, Va., cosponsored by the Defense Advanced Research Projects Agency and the Electronic Industries Association. □

SIA NOW ACKNOWLEDGES MIL-SPEC CHIP STANDARDS NEED REVISING

The Semiconductor Industry Association has revised its position on a proposal by a Defense Science Board study group to eliminate most mil-spec components. The SIA last September opposed the recommendation of the DSB, which claimed that state-of-the-art commercial devices have outpaced military-qualified production lines. At the time, the SIA warned that commercial devices wouldn't offer the same reliability as mil-spec semiconductors. However, in a letter mailed in early April to Assistant Secretary of Defense for Acquisition and Logistics Robert Costello, SIA president Andrew A. Procassini called for the modernization of the Pentagon's semiconductor procurement regulations. Among the suggestions from the SIA's Government Procurement Committee: the Pentagon should adopt commercial process-control-qualification techniques and reduce the number of test steps currently used on mil-spec devices. "The mil-spec system is 25 years old and needs to be revamped," says Jon E. Cornell, senior vice president of Harris Corp.'s Semiconductor Sector and chairman of the committee. □

MILITARY/AEROSPACE NEWSLETTER

INTEL, ARTHUR ANDERSEN, AND WIZDOM JOIN TO IMPLEMENT ICAM

Intel Corp., Arthur Andersen & Co., and Wizdom Systems Corp. have joined forces to develop for builders of advanced tactical weapons systems a version of the Air Force's Integrated Computer Aided Manufacturing model. For this first implementation of ICAM, Arthur Andersen's Defense Computer Integrated Manufacturing Group in Dallas will serve as project manager; in that capacity, it will provide planning assistance, software development, and productivity tools. Wizdom Systems, Chicago, the principal architect of ICAM, will provide technical assistance in the design of subsystems and integration. The system will be based on Intel's Series 300 Microcomputer, with real-time control and monitoring for assembly and manufacturing operations. Intel also is providing Ethernet-based network services. □

CONCURRENT'S ADA LETS USERS WORK WITH FORTRAN SUBROUTINES

System developers can use their Fortran programs and subroutines and still meet the Defense Department's requirement that they use Ada, the DOD's programming language. Concurrent Computer Corp.'s version of Ada, C³Ada, features an interface that lets users work with the company's Fortran VII Run Time Library and their own Fortran VII subroutines as if they had been written in Ada, says the Tinton Falls, N. J., company. C³Ada's interface also contributes to impressive processing speeds. Running on the company's 3280MPS computer, C³Ada executes 5,000 Dhrystone instructions/s—at the top of the mips range for comparable systems—using a single processor. As many as six processors can run simultaneously in large systems, boosting the performance to more than 25,000 Dhrystones. □

DARPA EYES A BROADER ROLE IN SEMICONDUCTOR R&D

Watch for the Defense Advanced Research Projects Agency to expand its efforts in semiconductor research and development. Darpa already has a \$19.8 million gallium arsenide pilot line under way (see "Bell Labs Setting Up GaAs MOD FET Pilot Line," p. 36), and the director of the agency, Robert C. Duncan, told a Darpa-Electronic Industries Association meeting held in early April in Alexandria, Va., that Darpa had started investigating several potential new semiconductor R&D programs. The agency's emphasis in semiconductors, he explained, is shifting from basic research to prototype programs. One obvious indication of the shift: Darpa has decided to open its own contracting office and has started looking for someone to head it, Duncan says. He expects the agency will eventually manage up to one third of the R&D contracts that are now being handled for it by the U. S. Army, Navy, and Air Force. □

HARRIS AND SILICON COMPILER ADAPTING GENESIL TO RAD-HARD CMOS

Aiming at what it sees as a growing market for customer-designed integrated circuits for the military, Harris Semiconductor's Custom Integrated Circuits Division, Melbourne, Fla., has agreed to help Silicon Compiler Systems Corp., San Jose, Calif., adapt its Genesil design system for Harris' radiation-hardened CMOS design techniques. Harris will fabricate rad-hard chips designed using the new system in a 2- μ m double-level-metal process. Meanwhile, an agreement between the companies will allow designs completed on the existing Genesil systems to conform to Harris process-design rules. IC designers will use the Genesil system to define circuit functions and translate these definitions into a custom silicon layout. The finished layout will then be transferred to Harris, along with a formatted test program, for fabrication. □

The Microminiature NO-TWIST™ Pin

One-piece, die-formed construction, with four equally-spaced compliant tines — eliminates the most common problems and failure modes associated with twisted-wire type pins.

No crushed pins — uniform, integral nose design assures smooth entry and alignment.

No excessive gold plating — smooth surface area allows economical, uniform application of gold only where it's needed.

No significant process variations — each pin is die-formed for optimum process control and repeatability.

No excessive mating forces — four tines flex (comply) with mating half, resulting in less than 3 oz. insertion force per pin.

The NO-TWIST pin. That's why Elco's microminiature connectors, the first to be qualified to MIL-C-83513, are clearly superior to connectors that use twisted-wire type pins. It's easy to see why. Elco's NO-TWIST pin has a simpler construction than twist-pin contacts made with two crimps, bulged and heat-treated wire bundles and welded tips. Elco's NO-TWIST pin is easier to mate, costs less to produce, less to plate and less to use. It even eliminates the need for coupling screws in many applications. The NO-TWIST pin is used in a wide range of Elco MICROCON 50 mil connectors for wire-to-wire and board-mounted applications, both thru-hole and surface mount (integral tail). And, all are intermateable with existing twist-pin sockets. For our free NO-TWIST Pin Technical Report and MICROCON catalog, call or write

MICROCON Product Manager,
Elco Corporation, Huntingdon, PA 16652.
(814) 643-0700.

 **Elco Corporation**
A Subsidiary of Wickes Manufacturing Company

Circle 97 on reader service card

NEW PRODUCTS

LOGIC-ARRAY SERIES RUNS 25% FASTER, USES LESS POWER


APPLIED MICRO CIRCUITS DOES IT BY SCALING DOWN BIPOLAR PROCESS

By scaling down its 3- μ m oxide-isolated bipolar process to 2 μ m, Applied Micro Circuits Corp. has boosted the performance of the new Q5000T logic-array series by as much as 25% over its predecessor, the Q3500 series.

Reduced feature sizes in the internal core of the 2- μ m arrays yield die sizes that are 30% smaller than the Q3500 family of arrays, says Bernie Rosenthal, product marketing manager.

DENSE. "This allows the Q5000 arrays to have higher densities and speed/power savings over anything Applied Micro Circuits offered previously," says Rosenthal. Internal equivalent gate delays of 210 to 545 ps are 10% to 25% faster than the company's comparable earlier macros, for example, and overall power savings of about 10% can be expected. "The reduced power also helps achieve the better reliability of the new family," he adds. Average utilization of total cell count is 95%. Input/output cells on the arrays provide both emitter-coupled logic and TTL compatibility.

The arrays have been designed to permit direct access to core logic. In the ECL mode, signals can bypass the input buffers and interface directly to the high-speed clock inputs of selected macros. With this technique, differential



EASY I/O. Input/output cells on the arrays provide compatibility for both ECL and TTL external circuitry.

ECL input and output frequencies of up to 600 MHz can be attained. In TTL circuits, maximum input and output frequencies of 160 MHz and 90 MHz, respectively, can be supported.

In the logic core of the new family, as with the existing product series, densities are achieved with triple-level series-gated structures, Rosenthal notes. In his opinion, these triple-level structures have the advantage of providing higher

functional density than cascaded, two-level structures used for equivalent gate densities by competing array manufacturers.

To provide compatibility for the off-chip drive features, the I/O cells have characteristics and feature sizes that closely resemble those of the current Q3500 series. All I/O cells are universal—capable of input, output, or bidirectional operation.

TWO LAYERS. The new array family uses the two-layer-metal interconnect scheme employed by the Q3500 series, except for the top-of-the-line Q5000T (AMCC uses a T to differentiate the new series), which has three-layer metal throughout.

The first array, the Q3500T, is now available, and four other devices are slated to debut through the third quarter of this year. The Q3500T has 3,500 equivalent gates, 120 usable I/O channels, and typical power dissipation of 2.5 to 6.0 W. The dissipation specification is at 95% utilization and is based on complex macros and the availability of speed/power options, the company notes. Prices are identical to the Q3500's 3¢ to 4¢ per gate for an order of 10,000 units.

—Larry Waller

Applied Micro Circuits Corp., 5502 Oberlin Dr., San Diego, Calif. 92121.

Phone (619) 450-9333 [Circle 360]

DIODE STACKS HANDLE HIGH VOLTAGES

A new range of extra-high-voltage diode stacks from Philips can be customized for current ratings from 0.1 A to 1.5 A and voltage ratings from 2 kV to 20 kV. According to the Dutch company, they offer better reliability and performance than competitive products provide.

The devices, which amount to as many as 30 diode crystals stacked on top of each other to provide the specified voltage rating, boast reverse-recovery times as fast as 30 ns, says Graham Hine, international marketing manager for diodes at Philips's Electronic

Components and Materials (Elcoma) Division in Eindhoven, the Netherlands.

Philips's glass-bead encapsulation technology accounts for performance improvements over conventional plastic-bodied diode stacks. The moisture-tight hermetic glass seal ensures high reliability and also provides better junction passivation, which leads to better stability. These features are combined in devices that Hine says are the only medium-power ultrafast diode stacks available in glass encapsulation.

Tests with the new stacks have shown the failure rate to be just 1 per 1 billion

device hours at maximum ratings. This failure rate is one to three orders of magnitude lower than that achieved with ordinary plastic-encapsulated stacks, says Hine.

Reverse-recovery times of as fast as 30 ns are achieved by diffusing platinum into the silicon at high temperature. By shortening charge-carrier lifetime, this platinum-killing process improves switching speed.

The fast switching speed is well suited to the latest generation of 128-kHz switched-mode and series-resonant power supplies. Control of the platinum-kill-

ing process enables Philips Elcoma to offer a choice of speeds other than 30 ns. Customers can specify 75-, 150-, 350-, and 5,000-ns devices—a wider choice than that offered by plastic-bodied diode stacks.

Typical applications for the diode stacks are microwave ovens, X-ray equipment, and automobile ignition and distributor circuits. Their hermetic glass seal makes the stacks suitable for high-reliability medical, industrial, military, and aerospace applications. Because of its high current ratings, a single stack can replace two or more paralleled low-current devices, saving in cost and in space.

Depending on the current rating, the devices come in SOD-61, SOD-88, or SOD-89 packages. The length of the

glass body depends on the number of crystals in it.

The devices are designed for each user's applications, so prices depend on customer specifications of current, voltage, and reverse-recovery time. Minimum order, including engineering and fabrication, is about \$20,000.

Samples of custom diode stacks are available three months from receipt of customer specifications, Hine says. Production can start two to three months after a customer accepts the samples.

—John Gosch

Amperex Sales Corp., George Washington Hwy., Smithfield, R. I. 02917.

Phone (401) 762-3800 [Circle 361]

Philips, Elcoma Division, 5600 MD Eindhoven, the Netherlands.

Phone 31-40-723623 [Circle 362]

WAFERSCALE MULTIPLIERS BOAST 30-ns CYCLE TIME

Looking to jump out in front of the competition in the market for the multiplier-accumulators widely used in digital-signal-processing applications, Waferscale Integration Inc. has introduced a parallel 16-by-16-bit device that it claims is 25% faster than competitive designs.

The 1.2- μ m CMOS WS59510-30J boasts a total throughput clock cycle of only 30 ns—10 ns faster than its nearest competitor, says Dale Prull, director of marketing.

NOT PIPELINED. The WS59510 has a 16-bit-by-16-bit parallel multiplier and a 35-bit accumulator. It owes its speed to its nonpipelined architecture. Whereas pipelined approaches require two clock cycles to process new data, the WS59510 requires just one. The architecture provides for two's-complement or unsigned-magnitude 16-bit operations. Multiplications are based on a modified Booth's multiplication algorithm.


Also contributing to performance are a parallel addition array in the multiplier—structured as a Wallace tree—and the use of carry-select logic in the final add stage.

The major advantage of the WS59510 over competitive devices is that it requires the least delay to calculate X , Y , and P parameters, says development engineer Yoram Ceder.

"The device enables data to be evaluated one step closer to real time, which is essential in such high-performance applications as 3-d color graphics, military real-time control and guidance systems, array processing, telecommunications, and other DSP applications," Ceder says.

All inputs—both data and instruction—and all the bidirectional outputs

are registered. Independently clocked, these registers are positive edge-triggered D-type flip-flops. Designed to be preloaded through the bidirectional output ports, the 35-bit accumulator/output register is divided into a 3-bit extended product (XTP), a 16-bit most-significant product (MSP), and a 16-bit least-significant product (LSP). The XTP and MSP have dedicated ports for three-state output, and the LSP is multiplexed through the Y input.




The WS59510-30J is pin-compatible with such devices as Advanced Micro Devices Inc.'s AM29510 and Texas Instruments Inc.'s TDC1010. It is now available in 68-pin plastic leaded-chip-carrier packages, starting at \$34 each in quantities of 1,000 or more. The circuit is also available in ceramic dual in-line packages and ceramic leadless-chip-carrier packages, as well as in macro cell form as part of the company's semicustom cell library.

—Bernard C. Cole

Waferscale Integration Inc., 47280 Kato Rd., Fremont, Calif. 94528.

Phone (415) 656-5400 [Circle 363]

Contactless de-soldering and soldering with the Leister-Labor "S" Hot Air Tool



Electronic Temperature Adjustment from 20 to 600 °C. Electronical Air Volume Adjustment from 1 to 150 litres per minute.

For contactless de-soldering and soldering of SMD- and DIP-components in 2-4 seconds.

Ask for free brochure UW 70

Brian R. White Co. Inc., 313 Henry Station Road
Ukiah, CA 95482 Tel. (707) 462 9795
Eatontown, NJ 07724 Tel. (201) 544 1212
Akron, OH 44307 Tel. (216) 253 4044

Circle 99 on reader service card

We've got a job so important, it takes a retired person to do it.

We want you to help give new lives to the 27 million Americans who are functionally illiterate.

Today, illiteracy has become an epidemic that has reached one out of five adults. But you can help stop it by joining the fight against illiteracy.

Call the Coalition for Literacy at toll-free 1-800-228-8813 and volunteer.

Volunteer Against Illiteracy.
The only degree you need
is a degree of caring.



Coalition for Literacy

EDGE'S DUAL-PROCESSOR 1200 RUNS AT 11 MIPS

**32-KBYTE INSTRUCTION CACHE, EQUAL BUS LOADING
DELIVER SUPERMINI PERFORMANCE FOR \$128,000**

Edge Computer Corp.'s newest superminicomputer achieves a sustained performance of 11 million instructions/s—and a 16-mips peak—by harnessing a pair of proprietary 10-chip, 2- μ m CMOS processors to a pipelined, dual-bus architecture and then maximizing bus utilization with a two-pronged design strategy: equalizing bus loading and using a 32-Kbyte instruction cache.

Although the Edge 1200's blazing speed matches high-end superminicomputer performance, its \$128,000 price tag is about one-sixth that of a high-end supermini, says a spokesman for the Scottsdale, Ariz., company. The 1200 offers original-equipment manufacturers the opportunity to configure a system compatible with Motorola Corp.'s 680X0 instruction set but with performance that is superior to the 5-mips 68020 microprocessor.


BUS LOADING. Maximizing throughput on the two 30-Mbyte/s buses became a key element in the design strategy, because simply adding another processor to the company's existing 32-bit, 6-mips Edge 1 would have resulted in bottlenecks, says Robert W. Crawford, vice president of development.

Edge designers began by equalizing bus loading. In the company's dual-bus, single-processor Edge 1, the A bus handles instruction/fetch functions and the B bus does operand/execute functions. This architecture allows both an instruction and data to be accessed in a single clock cycle, says Crawford, but it also loads the buses unequally.

Typically, the instruction bus runs at 45% capacity and the operand bus at 60%. But by reversing bus assignments for the second processor—the A bus for operands and the B bus for instructions—designers reduced the likelihood of bottlenecks. Edge further unburdened the buses by implementing a two-way set, 32-Kbyte instruction cache for each processor. By fetching instructions from the cache, the system cuts loading from 45% to 5% of each instruction bus, says Crawford.

I/O CAPABILITY. The two-pronged strategy results in 65% loading on each bus, leaving 35% for the input/output operations critical in departmental computing.

For customers who now need single-processor performance but expect their computing needs to grow, Edge offers a new, single-processor Edge 1100 that



CUTTING EDGE. The 10-chip central processors are implemented in 2- μ m gate arrays.

can be upgraded by adding another processor board.

Edge's dual-processor system retains the same proprietary 10-chip central processor design, 7-chip floating-point coprocessor, and 3-chip memory-management and control units used in the Edge 1. All 20 chips are implemented in a 2- μ m CMOS channelless gate array having 8,500 gates.

While almost doubling performance over its previous offering, Edge maintains its commitment to a small, open-architecture 32-bit computer with advanced networking capabilities. Edge's GSX Unix operating system is an enhanced version of AT&T Co.'s Unix System V. The 1200 has eight I/O channels, each with a 6-Mbyte/s transfer rate, and can handle up to 512 terminals. It operates on 110 V and fits in a 17 in.-by-29 in.-by-32 in. cabinet.

Edge sees a growing market in applications such as calculation-intensive scientific computing and departmental networks that are saturating the 68020's performance capabilities. President Alex Cimochoowski says that by offering "continuity of compatible computing" for the 680X0 instruction set, Edge provides the same performance-upgrading opportunities now offered only by Digital Equipment Corp. and IBM Corp.

In addition, he says, although reduced-instruction-set computers offer price/performance ratios comparable to Edge's, users of 680X0-based products must change operating systems, compilers, and data formats to switch to RISC systems.

Available in June, a 1200 system with 8 Mbytes of system memory, 337 Mbytes of hard-disk storage, and the GSX Unix operating system will cost \$128,000. The single-processor 1100, similarly configured, will cost \$104,000.

Edge Computer Corp., 7273 E. Butherus Dr., Scottsdale, Ariz. 85260.

Phone (602) 951-2020

[Circle 340]

NEW SOFTWARE SIMPLIFIES DOCUMENTATION CHANGES

A major enhancement to Context Corp.'s document-management software makes it possible to incorporate alterations and additions into a report, manual, or other engineering document by electronically tagging each amendment and automatically tracing its implications through the entire document.

The new package—called Change Control—becomes part of Context's series of Documentation Workstations, a hierarchical engineering documentation system in which a large document can be broken up into a smaller pieces, or modules, that can be worked on individually. Typically, Context software is used for in-plant publishing of product proposals, engineering specifications, and manuals. Its output is sent to a laser printer.

The Beaverton, Ore., software developer is a spinoff of Mentor Graphics Corp. Like Mentor's computer-aided-design software, Context's documentation

software runs on an Apollo Domain work station.

The new Change Control software package eliminates the time-consuming task of searching out and manually changing each reference to a change in design, text, or graphic in the documentation of a new product, making it much simpler to update manuals, reports, or any other printed document derived from the electronic original.

WHODUNIT. Alterations—including overlapping and conflicting changes—are identified according to who made a change, and when and why it was made.

Individuals are tagged according to a specific color or overlay pattern—a process Context refers to informally as a "computer-aided magic marker." System administrators can accept or reject changes, or even tailor the changes to particular versions of a document. Some manuals, for instance, need different versions for the different countries in

which a product is sold. With the Change Control software, all versions can be maintained as a single electronic document that is automatically and selectively edited when the time comes to produce a manual, report, or other end product.

Pictures, tables, and other documents are included by reference, so that changes made to any given module will be reflected in all documents containing that module.

Control software can be added to Context's documentation packages at no cost. Prices for the basic software range from \$4,900 for a text editor to more than \$30,000 for a full package.



The Change Control packages will be available on a limited basis in the second quarter of this year, with regular shipments due to commence in the third quarter.

Context Corp., 8285 S.W. Nimbus Ave., Beaverton, Ore. 97005.

Phone (503) 646-2600 [Circle 341]

CONTROLLER CUTS I/O INTERRUPTIONS

A multiport VMEbus peripheral controller card from Interphase Corp. shares direct-memory-access management duties with the host system's processor to achieve as much as a tenfold reduction in the number of times the host is interrupted while transferring data files to printers, plotters, or small-computer-system interface (SCSI) ports.

Once the host initiates DMA sequences, the V/MIX 3210's state machine finishes the task, issuing a single interrupt when the transfer is complete. The performance advantage is considerable, because plotter data files, for example, can be as large as 100 Kbytes.

The controller has three ports for SCSI interfaces, printers, and plotters. Available now, it costs \$995 each in volume purchases.

Interphase Corp., 2925 Merrell Rd., Dallas, Texas 75229.

Phone (214) 350-9000 [Circle 345]



Plug-in pins, pigtail leads or taped for auto-insertion - TR 5 fuses are internationally acceptable.

This new generation of sub-miniature fuses to IEC 127/part 3 and UL 198 G, satisfies various requirements. Established technology, recognised high quality, universally acceptable; VDE, SEMKO, UL and CSA approved. 250 V and 125 V, quick-acting, medium time-lag, and time-lag characteristics. Please contact us for further details.




A mark of safety

Wickmann-Werke GmbH

Annenstr. 113 · Postbox 2520 · D-5810 Witten 6
Tel. 02302/6620 · Telex 8229145wwg d · Fax 02302/662111

Circle 101 on reader service card



"We're looking for retired managers who want to get back into action."

Harold W. McGraw, Jr.,
Chairman,
McGraw-Hill, Inc.

I'm a volunteer supporter of the International Executive Service Corps, a not-for-profit organization with a vital mission:

We send retired U.S. managers overseas to help businesses in developing countries, which often respond by increasing their imports of U.S. goods. In fact, developing countries consume about 40 percent of U.S. exports.

As an IESC volunteer, you would not get a salary. But you would get expenses for you and your spouse, plus a world of personal satisfaction.

IESC leads the field in this kind of work. We've done over 9,000 projects in 81 countries. We could have a project that's just right for you.

For more information, send this coupon to: Harold W. McGraw, Jr., Chairman, McGraw-Hill, Inc., P.O. Box 10005, Stamford, CT 06904-2005.

Dear Mr. McGraw: Tell me more about becoming an IESC volunteer. I am a recently retired manager or technician—or am about to retire—from a U.S. company. I'm free to accept an overseas assignment. I understand that volunteers receive expenses for themselves and their spouses, but no salary.

Name _____
Address _____
City _____ State _____ Zip _____



International Executive Service Corps

It's not just doing good. It's doing good business.

FLEXIBLE NETWORK MIXES COAX AND FIBER OPTICS

SYSTECH NET SUPPORTS A WIDE RANGE OF CONFIGURATIONS: OPTICAL TRANSMISSION CABLES EXTEND IT UP TO 4,000 FT

A distributed communications subsystem from Systech Corp., San Diego, does away with modems, dedicated plug-in connection boards, and signal repeaters in connecting a host computer to as many as 128 terminals.

The system offers original equipment manufacturers two advantages: configuration flexibility and fiber-optic transmission compatibility. Using a token-passing bit-serial bus system, it offers 2.5-Mbit/s data transmission rates with either the coaxial or fiber-optic transport interfaces.


Systech Pluriaxial Unplug Repeaters, or SPURs, consist of a line driver and receiver compatible with Systech's existing host adapters and cluster controllers that handle up to 16 terminals each. Every SPUR has six coaxial ports.

Flexibility is the system's main advantage, says Robert A. Hahn, vice president of marketing. A simple serial bus can be modified to a star topology, for example. "Permutations and combinations of configurations using SPURs are almost limitless," he says.

With SPURs and coaxial cabling, a fan-out of up to five

separate segments of 1,000 feet each can be installed. Converting from coaxial to fiber-optic cables means each segment can extend up to 4,000 ft.

With fiber-optic cabling, a chained series of SPURs can stretch as far as three miles from the host computer to the most distant cluster controller, says Hahn. Fiber-optic cable can also be used in segments where electrical isolation is important.



EXTENDED. Fiber-optic cables (in color) can be combined with coaxial links to form extended networks.

Both types of transmission media can be mixed in the same installation, and maximum distances are achieved by chaining together a number of SPURs. "Without SPUR, distances of this magnitude [up to three miles] would require a much more costly approach, using modems and telephone lines or similar approaches," Hahn says.

For a 16-terminal configuration of 1,000-ft. lines, the modem/phone line approach would cost about \$20,000, compared with about \$6,500 using SPURs, and that includes about \$5,000 for cable, says Hahn.

Each SPUR measures 2 7/8 in. in height, 1 3/8 in. in width, and 10 in. in depth. It weighs 3.9 lb and operates from 115- or 220-V sources. Indicators are tricolor light-emitting diodes.

The company says that the subsystem must do more than just pass along a signal, because of the long distances of the data transmission. Built-in circuitry to reduce any inherent data-transmission "jitter" continually cleans and regenerates the signal.

Founded in 1981, Systech specializes in communications subsystems that increase performance of large computer systems by offloading communications functions. SPURs are available in three formats: HPS-5580, with six coaxial ports, at \$610; HPS-5581, with an added fiber-optic port, \$1,505; and HPS-5582, with two fiber-optic ports, \$2,205. —Larry Waller

Systech Corp., 6465 Nancy Ridge Dr., San Diego, Calif. 92121.

Phone (619) 453-8970 [Circle 440]

UNIT GIVES PCs FAX CAPABILITY

Brooktrout Technology's Fax-Mail products eliminate the personnel costs associated with facsimile-machine transmissions of data and graphics by providing hardware and software that let IBM Corp. Personal Computers or compatibles double as facsimile machines.

Using board-level digital-signal-processing technology, bit-mapped pages of text and high-resolution graphics can be transmitted between fax machines and PCs at up to 9,600 baud without the blurring caused by light-scanning techniques. As many as 10 letter-size pages can be stored on a single floppy disk. Fax-Mail is CCITT Group II and III compatible.

The great bulk of business information exists on paper, says the company, and Fax-Mail provides a low-cost means of transmitting it throughout an installed base of millions of personal computers.

Available now, the 9,600-baud Fax-Mail 96 costs \$995; the 4,800-baud Fax-

Mail 48 is \$795; and the Fax-Mail 24 is \$595. Prices include software. By contrast, facsimile machines cost around \$3,000.

Brooktrout Technology Inc., 110 Cedar St., Wellesley Hills, Mass. 02181.

Phone (617) 235-3026 [Circle 445]



FASTNET CONNECTS MACINTOSH TO LANs

Dove Computer Corp.'s FastNet system provides Apple Computer Corp.'s Macintosh family access to mainframe computers over Ethernet local-area networks.

FastNet's Communication Control Unit is built around a Motorola Corp. 68000 microprocessor and comes equipped with 512 Kbytes of random-access memory. It is available for small computer-system interface connections with the Macintosh 512E, Macintosh Plus, Macintosh SE, and Macintosh II.

Network file transfers, file access, and mail transactions are controlled using familiar Macintosh icons. Transmission rates up to 19.2 Kbaud are supported. Available now, the control unit costs \$1,099. Modules for connecting it to Ethernet LANs cost \$399 each.

Dove Computer Corp., 1200 N. 23rd St., Wilmington, N.C. 28405.

Phone (800) 622-7627 [Circle 446]

Electronics CAREER OPPORTUNITIES

Electronics reaches over 130,000 engineers

Upcoming 1987 Editorial Features:

Issue		Closing	Issue		Closing
May 14	Software Special Issue Power Supplies Semicon/West Preview Custom IC Conference Preview	April 27	June 11	NCC Preview Bonus Distribution Computer-Aided Design Ultrascale Integration	May 25
May 28	Linear VLSI	May 11	June 25	Industrial Electronics Design Automation Conference	June 8

For more information, contact Susan Barnes-Ronga, National Recruitment Sales Representative, at (212) 512-2787



**WE GIVE A
HOOT, SO
WE WON'T
POLLUTE!**

You can do something about pollution: Join the Woodsy Team and pledge to help keep your environment clean.



Forest Service-USDA

Portrait of the Great American Investor



You can tell by looking at him that he believes in working hard. And he expects his investments to do the same. Which is why he has his money in

U.S. Savings Bonds. Bonds have changed. They now pay competitive rates, like money market accounts. Find out more, call anytime 1-800-US-BONDS.

U.S. SAVINGS BONDS
THE GREAT AMERICAN INVESTMENT

Bonds held less than five years earn a lower rate.

A public service of this publication.

Engineers

The Boeing Electronics Company, and the Electronics High Technology Center, have immediate requirements for engineers experienced in bringing new products on line.

Since Boeing Electronics Company is a fast-growing technologically-advanced company, you will have an opportunity to

work with the most renowned people in their field. And you will be able to do things that have never been done before.

The salaries are right. The benefits package is comprehensive. And the positions are located in the Pacific Northwest, near Seattle, the Number One-ranked recreation city in America.

These Positions Are Available Right Now

Microelectronic Engineers/Manufacturing: Experience is required in the theory of operation of hybrid devices and materials; physics aspects of devices, materials, structures and operations; MIL-STD-1772 thick/thin film.

EE Packaging Engineers: Perform packaging research and design of RF or high-speed circuits; have knowledge of military design techniques, microwave and millimeter wave. Design electronic circuits for operating environments using physical, mechanical, electrical and thermal design techniques.

Integrated Circuit Computer Aided Design (I/C-CAD) Engineers: Design develop code and maintain ECAD software programs. You must be familiar with VAX, VMS, and UNIX. PASCAL is required.

Software Engineers: Perform validation and verification of avionics realtime software. You must be familiar with microprocessors; design realtime avionics software.

A BS degree in EE, Computer Sciences, ME or Manufacturing Engineering with 3 years experience and U.S. citizenship are required.

Power Supply Design Engineers: Design and development analog and digital power processing equipment.

PhD EEs

The Electronics High Technology Center has requirements for PhD's EEs — or in closely related fields — for applied research and development in microelectronics and RF.

Microelectronics: Digital gallium arsenide, device modelling, advanced CAD tools, high speed interconnect technology.


RF: Microwave/Millimeter Wave Hybrid Circuit and/or Monolithic Integrated Circuit (MMIC) Design.

RF positions require U.S. citizenship.

We'd Like To Hear From You.

If you qualify, please send your résumé with present and expected salary, to The Boeing Company, P.O. Box 3707-DHC, Seattle, WA 98124. An equal opportunity employer.

BOEING



With your help, we'll mastermind still more of tomorrow's space and defense systems technologies.

Mastermind a Dream.

If an idea is good, it shouldn't stay an idea for long. At Martin Marietta Denver Aerospace, dreams—even the "impossible" ones, the long shots—can come true.

Working with highly advanced equipment in state-of-the-art facilities, our engineers tackle a broad variety of interesting and challenging assignments each day—an unmatched repertoire of advanced launch and space propulsion systems, spacecraft, instruments and strategic defense systems.

We're looking for top engineers with a B.S. degree or equivalent (advanced degree desirable) in electronic engineering or physics and 5 to 15 years of experience to take several leading-edge programs from the conceptual stage forward.

Antenna System Engineers Antenna Design Engineers

Several opportunities exist in conceptual design, analyses and laboratory development of advanced microwave antennas or similar work in electromagnetics.

Communication Systems Engineers

Explore exceptional opportunities in spacecraft and missile communication systems design and analysis.

Microwave and Millimeter Wave Systems Engineers

We have multiple opportunities in the conceptual design and analysis of advanced microwave and millimeter wave systems.

Sr. Spacecraft Controls System Analysts

Here are several opportunities for specialists with 5 to 10 years of

experience which includes digital computer modeling and flexible/rigid bodies.


Sr. Guidance and Control Hardware Engineers (PIE)

You'll need 5 to 10 years of experience in systems integration and knowledge of subcontract work involving gyros, accelerometers, momentum wheels, star trackers, star scanners, sun sensors and related areas.

AN FBI/SBI BACKGROUND INVESTIGATION MAY BE REQUIRED.

Please send your resume to Martin Marietta Denver Aerospace, Personnel Department, P.O. Box 179, G1311, P70036, Denver, Colorado 80201. No agencies, please. We're an Affirmative Action Employer actively seeking veterans and the handicapped. U.S. Citizenship is required.

MARTIN MARIETTA



Software Paradise

Come to Lockheed Missiles & Space and you'll find yourself surrounded by a fascinating variety of opportunities.

We offer you a software paradise, full of exotic projects and rare challenges. As well as access to advanced computer systems, such as APOLLO, SYMBOLICS, VAX and CDC CYBERS.

Qualified software engineers are invited to explore the following career paths:

Software Requirements Analysis, Design and ADA Code Development

- Five or more years' software engineering experience
- ADA design and code development experience is preferred.

Simulation and Real-Time Code Design

- Experience with VAX/VMS, FORTRAN and PDP 11/70 Assembly Language is required.

Real-Time and Operating Systems Development

- Eight or more years' software engineering experience
- Knowledge of FORTRAN and VAX/VMS is required.

FORTRAN Software Development

- Four or more years' experience in a VAX/VMS environment
- Experience in real-time modeling, VMS Systems Management, FMS/Datatrieve, Database Management or graphics software is preferred.

Experience with high-priority defense programs is strongly desired.

Take a walk on the wild side. Send your resume to Professional Staffing, Dept. 524GOLB, Lockheed Missiles & Space Company, P.O. Box 3504, Sunnyvale, CA 94088-3504. We are an equal opportunity, affirmative action employer. U.S. citizenship is required.

 **Lockheed Missiles & Space Company**
Innovation
driving shape to imagination

MOS/VLSI ENGINEERS

Long Island, NY based semiconductor manufacturer seeks product, design, systems, CAE and test engineers with strong academic background and 3+ years MOS/VLSI exp., analog CMOS preferred. Intermediate thru managerial positions available. Send resume including salary history in confidence to : ROL Associates, P.O. Box 293, Great Neck, N.Y. 11022 (516) 486-8667.

**Find the
Personnel
you need!**

**Place
your
recruitment
advertisement
in**

**Electronics
Career Opportunities
Section**

Call

Susan Barnes Ronga

at

(212) 512-2787

NA PUBLIC AUCTION

**TUESDAY, APRIL 28th
AT 10 AM (Local Time)**

Machinery & Equipment no longer required
in the continuing operations of

A T & T TECHNOLOGIES, INC. 3300 Old Lexington Road Winston-Salem, NC CAPACITOR MANUFACTURING EQUIP.

RADIAL CAPACITOR EQUIP.: Systemation
Epoxy Coater (1976); Systemation
Fluidized Bed Coater; (3) Die-Craft
Lead Formers; Lead Welders; etc.

BALANCES: Mettler, Torsion, Sartorius-
Werke Analytical

AXIAL CAPACITOR EQUIPMENT: Well-
power Auto. Lead Welders; Lead
Shears; Universal Lead Taping Ma-
chines; Capping Stations; Markem
Marking Machines

ANODIZING EQUIPMENT: (8) OMI, Meaker
Anodizers (To 1982)

PLATING & ETCHING EQUIP.: Sel-Rex
Type X-7T-LP Plater; Millipower Etch
Module; Sel-Rex Rectifiers

ELECTRONIC COMPONENT INSERTERS:
(9) Univ. Models 6288, 1636, 1638,
6383, 6797; Univ. Prepping Mach.

VACUUM FURNACES: (4) Abar Models
B8X12T16A130 & BR-12X28 (All '79)

SINTERING FURNACES: (6) NRC Model
2945 High Temp.; (5) NRC Vacuum
Retorts; (5) Roots 10 HP Blowers; (6)
Kinney 5 HP Vacuum Pumps

STRESS OVENS: (10) Grieve Electric Walk
Through Axial Lead (1966 - 1980); (2)
Everett/Charles Model 12 Lead & 25
Lead (To 1976); (4) Thermacraft
Model S.O.1E0019

PYROLIZER OVENS: (6) Grieve Electric
Conveyorized (10 1976)

OVENS: (16) Blue M, Grieve, Tenny Life
Test, Drying, Industrial, Curing, Batch
Ovens (To 1985)

PRESSES: (10) Mull, MTI Molding & En-
capsulating, Dies for Presses, Pre-
heaters; (14) Dorst, Hubert Compact-
ing Presses

MISC.: Test Equipment Including Leak-
age Fixture & Test Sets (To 1986),
Volt Meters; Tantalum Powder Equip-
ment; Welding & Soldering Equip-
ment; (4) Screw Insertion Machines
(1972 - 76); Lab Equipment; Power
Supplies; Hoffman Eng. Oiltight Wire-
way Parts, Shop & Factory, etc.


Inspection: Mon., April 27th, 9 am to 4:30 pm
Terms of Sale: 25% (Cash or Certified Check)
at time of sale

Call for Free Illustrated Circular

NORMAN LEVY ASSOCIATES, INC.
21415 Civic Center Drive
Southfield, Michigan 48076
Phone 313-353-8640 Telex 23-0701
London, England Office: Phone 01-611-0701, Telex 887291
Auctioneers/Liquidators/Appraisers

COMPUTER MARKETPLACE

SCHEMA II Schematic Capture



FREE Demo Disk: 1-800-553-9119

SCHEMA's success is the talk of the CAE industry and *thousands* of satisfied SCHEMA owners know why. Incredible speed, ease of use, and power have made SCHEMA a best-selling schematic capture program for engineering professionals the world over.



Now, SCHEMA II is available.
SCHEMA II sells for \$495 and sup-
ports most common IBM PC/XT/
AT configurations. Please call today
for a free SCHEMA II demo disk.

OMATION

In Texas Call (214) 231-5167

SPICE Circuit Simulation
8/16/32 bit PC's
PC too slow? Need > Maxmem?
Northern Valley Software
28327 Rothrock Dr. R.P.V., CA.
(213) 541-3677 90274



100Mhz Logic Analyzer Card

For PC/XT, PC/AT Monochrome &
Color Card Systems

\$1199

- 24 Channels at 25KHz - 25 Mhz
- 6 Channels at 100 Mhz
- Internal Clock up to 100Mhz
- External Clock up to 25Mhz
- Threshold Voltage TTL, ECL,
or variable from -10 to +10v
- Totally Software Controlled
- All Software Included



PAL/EPROM Programmer Card For PC/XT/AT Systems



\$399

- Programs All 20 and 24 Pin
MMI, NS, TI PALs
- Programs Eproms from 2716
to 27512 and 27512A
- Software Functions Include:
Read, Write, Verify, Protect,
Edit, Print, and File Save
and Load of Program.
- All Software Included

CALL NOW FOR ORDERS
AND TECHNICAL INFORMATION (201) 994-6669
Link Computer Graphics, Inc. 4 Sparrow Dr.,
Livingston, NJ 07039

SPICE up your PC

Z/SPICE professional circuit simulation
Full version \$300 Student version \$79
ZTEC box 737, college place, wa 99324
(509)-529-7025

Special Software Section

Coming
May 14

"SOFTWARE
SPECIAL ISSUE"
Closing April 20

**To place your
Computer Software Ad**

**Call Ilene Fader
212-512-2984**


**To place
your ad call
Ilene Fader**

212/512-2984

Electronics



HOW GENERAL MOTORS IMPROVES ITS TOP END PERFORMANCE.



Elliott M. Estes
Former
President General Motors

Edward N. Cole
Former
President General Motors

F. James McDonald
Current
President General Motors

One of General Motors' most important suppliers doesn't make parts. It makes leaders. Over the past 19 years all three General Motors Presidents have come from the ranks of a college program called Co-operative Education.

It's a nationwide program that allows students to alternate studies at the college of their choice with paid, practical work experience in the field of their choice.

For students, Co-op Education is a chance to pick up the most valuable kind of knowledge. For employers, it's a chance to pick up the most valuable kind of student. If you'd like some information on how your company can participate in Co-op Education, write to us at the address below. Who knows, you may end up hiring a future company president. It wouldn't be the first time.

Co-op Education

You earn a future when you earn a degree.



For a free booklet write: Co-op Education • P.O. Box 999 • Boston, MA 02115
A Public Service of This Publication © 1985 National Commission for Cooperative Education

POSITIONS VACANT

Manager — Quality Control & Liaison —

Person sought to plan and direct activities concerned with development, application, and maintenance of quality standards for smoke detectors and electronic lighting products. Devise testing, inspection, evaluation and sampling procedures for above products manufactured in Far East. Design forms for recording data. Work closely with Underwriters Laboratories (UL) to ensure that all new designs for sale in U.S. and modifications meet UL 217 standards. Advise design engineers in Far East manufacturing plants modification needed to meet UL standards. This requires telephone calls to engineers in charge of production and quality control in Far East plants. Travel to Far East 5-10% of the time. Forty hours per week, 8:00 a.m. to 4:30 p.m. \$38,855 a year. Minimum requirements: three years college majoring in electronic engineering or three years training in electronic engineering and three years experience, or three years experience in the related occupation of Production Engineer (smoke detectors). Must speak Mandarin and Cantonese. Applicants should send resumes to: Illinois Department of Employment Security, 401 S. State Street, Third-floor South, Chicago, Illinois, 60605 Attn: Joan Haight. Reference #5626-4. An Employer Paid Ad.

POSITIONS WANTED

Electronic Engr, for hire. Microprocessor based designs, controls, telecom. Contract or per diem. Mr. Barry Masel. 718-476-1516.

SPECIAL SERVICES

286/386 Software Development Integration RMX/UNIX/DOS. Dafco Computer Services, Inc., P.O. Box 6599, 340 Iradell Road, Ithaca, NY 14851-6599. (607) 387-5517.

Overseas — 75 Countries — Interviewing now. All Fields — for Conn. interview. Send resume: Global Services, (O) Clinton, CT 06413. Transportation not paid to Connecticut.

Electronic Designer that can convert your design problems into working solutions. Flexible fees. 916-721-3020.

TO ANSWER BOX NUMBER ADS: Address separate envelopes (smaller than 11" x 5") for each reply to:

Box Number (As indicated)
Classified Advertising Department
Electronics
Post Office Box 900, NY 10108

Advertisers Index

* AB Electronic Products Group	31	* Murata Mfg. Co. Ltd.	44
Advanced Micro Devices	6, 7	National Semiconductor	2nd C, 1
Altera	82, 83	Nicolet Test Instrument Division	32
AMP Inc.	66, 67	* Norma Masstechnik	30
Anritsu Corporation	50, 51	Orbit Semiconductor	21
Calmos Systems Inc.	8	* Phillips T&M	25, 29
Catalyst-Semiconductor	16	† Rhodnius Inc.	68
Cherry Electrical Products	13	* Rohde & Schwarz	45, 87
Cypress Semiconductor	14, 15	† Seiko Instruments	44, 45
Data Translation	26	SGS Semiconductor	40, 41, 43
† Digital Equipment Corporation	14, 15	† Shin-Etsu Chemical Co. Ltd.	25
† DuPont/Corlam	87	* Siemens	63
Elco Co. Ltd.	97	Silicon Systems	22
Fairchild Advanced Signal Processing Division	3rd C	† SMOS Systems	64, 65
† Fujitsu Microelectronics	30, 31	* Sonnenschein	68
† Fulton Metalurgical Products	101	† Texas Instruments	17-20, 29
† GenRad	49	† Thomson Components Mostek	88, 89
Gould AMI	76, 77	UMC	52
Hi-Level Technology	94	† United Technology	63, 90
Hybricon Corporation	56	* Wandel & Goltermann	90
Inmos Corporation	10, 11	Wickmann Werke GmbH	101
International Robomation Intelligence	55	Zoran	9
Karl Leister	99		
Matrox Electronic Systems Ltd.	4th C		
MicroSim Corporation	12		
Mitel Corporation	2		

Classified and employment advertising

Link Computer Graphic, Inc.	107
Norman Levy Associates, Inc.	107
Northern Valley Software	107
Omaton	107
ZTEC	107
Career Opportunities	
Boing Company	104
Lockheed Missiles & Space	106
Martin Marietta	105
ROL Associates	106

- For more information of complete product line see advertisement in the latest Electronics Buyers Guide
- * Advertisers in Electronics International
- Advertisers in Electronics domestic edition

Advertising Sales Staff

Atlanta, Ga. 30319: Joseph Milroy
4170 Ashford-Dunwoody Road N.E.
[404] 252-0626

Boston, Mass. 02116:
M. E. "Casey" McKibben, Jr.
575 Boylston St.
[617] 262-1160

Chicago, Ill. 60611: William J. Walker
633-0155 Mobil Phone

Cleveland, Ohio 44113:
[216] 496-3800

Costa Mesa, Calif. 92626: Fran Cowen
3001 Red Hill Ave. Bldg. #1 Suite 222
[714] 557-6292

Dallas, Texas 75240: Harry B. Doyle, Jr.
5151 Belt Line Road, Suite 907
[214] 458-2400

Englewood, Co. 80112: Harry B. Doyle, Jr.
7400 South Alton Court Suite 111
[303] 740-4633

Houston, Texas 77040: Harry B. Doyle, Jr.
7600 West Tidwell, Suite 500
[713] 462-0757

Los Angeles, Calif. 90010: Chuck Crowe
3333 Wilshire Blvd.
[213] 480-5210

New York, N.Y. 10020:
Matthew T. Reseska [212] 512-3617
John Gallie [212] 512-4420
1221 Avenue of the Americas

Stamford, Ct. 06902:
Albert J. Liedel
777 Long Ridge Road. Bldg. A
[203] 968-7115

San Mateo, Ca 94404:
Rich Bastas, Jeffrey C. Hoopes, Paul Mazzacano
3rd Floor
951 Mariner's Island Blvd.
[415] 349-4100

Philadelphia, Pa. 19102: Joseph Milroy
Three Parkway, [215] 496-3800

Pittsburgh, Pa. 15222: Joseph Milroy
Suite 215, 6 Gateway Center, [215] 496-3800

Southfield, Michigan 48075:
4000 Town Center, Suite 770, Tower 2
[313] 352-9760

San Francisco, Calif. 94111:
Rich Bastas, Jeffrey C. Hoopes, Paul Mazzacano
425 Battery Street
[415] 362-4600

Frankfurt/Main: Fritz Krusebecker, Dieter Rothenbach
19 Liebigstrasse, Germany
Tel: 72-01-81

Milan: Manuela Capuano
1 via Baracchini, Italy
Tel: 86-90-656

Paris: Jean - Christian Acis, Alain Faure
128 Faubourg Saint Honore, 75008 Paris, France
Tel: [1] 42-89-0381

Scandinavia: Andrew Karnig
Finnbodavagen
S-131 31 Nacka
Sweden
Tel. 46-8-440005
Telex: 17951 AKA S

Tokyo: Hirokazu Morita
McGraw-Hill Publications Overseas Corporation,
Kasumigaseki Building 3-2-5, chome,
Kasumigaseki, Chiyoda-Ku, Tokyo, 100 Japan
[581] 9811

United Kingdom: Art Scheffer
34 Dover Street, London W1
Tel: 01-493-1451

Business Department

Thomas E. Vachon
Director of Operations
[212] 512-2627

Daniel McLaughlin
Director of Circulation
[212] 512-6598

Roseann Lehmann
Office Administrator
[212] 512-3469

Frances M. Vallone
Manager, Reader/Sales Services
[212] 512-6058

Ann Strignano
Billing Specialist
[212] 512-2589

Thomas M. Egan
Production Director
[212] 512-3140

Carol Gallagher
Production Manager
[212] 512-2045

Evelyn Dillon
Production Manager Related Products
[212] 512-2044

Classified Advertising

[212] 512-2556

Recruitment Advertising

Susan Barnes-Ronga
[212] 512-2787
[212] 512-2788

Subscription Sales
[201] 988-3258

ELECTRONICS WEEK

CHINA MARKET GETS GOOD REVIEWS

It appears the time is ripe for foreign companies to make strategic commitments in China. In a recent study, half of the foreign investors responding said their joint ventures there had exceeded performance targets; 28% reported that they had greatly exceeded their goals; 44% said they had met targets; and only 6% said they fell below targets. In 1985, U.S.-based investors contributed \$357 million—more than 37% of all foreign investment in China. The study was conducted by A. T. Kearney Inc., New York, and the International Trade Research Institute of Beijing, China.

GE EXPECTS VHSIC FAB CERTIFICATION

General Electric Co. is awaiting certification of one of its fabrication lines to make chips for the Pentagon's Very High-Speed Integrated Circuits program (see p. 84). The U.S. Defense Electronics Supply Center has just completed an audit of GE Semiconductor's fabrication line in Research Triangle Park, N.C., for VHSIC-compatible 1.25- μ m circuit production. The company is in the process of qualifying a 1.25- μ m butterfly chip for radar applications, and it says it will pursue generic qualification of the 1.25- μ m line later this year.

MMI, ALTERA SETTLE PATENT SUIT

Monolithic Memories Inc., of Santa Clara, Calif., has reached a settlement of its programmable-logic patent case against Altera Corp., also of Santa Clara. MMI claimed basic rights to programmable array logic in suits against both Altera and Lattice Semiconductor Corp., Beaverton, Ore., last September. This month Altera and MMI settled their dispute and licensed each other's technol-

ogies, with Altera agreeing to provide an unspecified financial consideration for the benefit of MMI. No money or royalties were involved. Lattice, which had countersued, says it has been unable to come to terms with MMI.

NOW SHOWING: THE THREE AMIGAS

Moving to broaden the appeal of its Amiga, a home-oriented microcomputer based on the Motorola 68000 microprocessor, Commodore Business Machines Inc., West Chester, Pa., is expanding the line to include low- and high-end versions. Commodore will offer a stripped-down machine for the home, the \$649 model 500, and a more powerful machine for business, the \$1,500 model 2000. In addition, the Amiga operating system software now resides in read-only memory rather than on floppy disk.

DG OFFERS TO BUY AI FIRM IN CHAPTER 11

Just days after Lisp Machines Inc., a maker of artificial intelligence hardware and software, filed for Chapter 11 protection, Data General Corp. of Westboro, Mass., offered to buy all of its technology and assets and hire its remaining 50 employees. Lisp has appointed as interim president Patrick Kareiva, a merger and acquisitions specialist, to review Data General's offer and solicit other offers. The \$10 million Lowell, Mass., company struggled for months to gain market share in such AI areas as factory automation and process control against stiff competition, including Symbolics Inc. and Texas Instruments.

AMPEX IS SOLD TO LANESBOROUGH

Ampex Corp., a pioneer in video recording technology, will retain its present management after being sold by technology conglomerate Allied-Signal Inc. of Morris

Township, N. J., to Lanesborough Corp. for \$479 million. Rolm Corp. founder M. Kenneth Oshman headed a venture group that tried to buy Ampex, but the group lost out to Lanesborough, a privately held New York chemical firm. Ampex president Charles A. Steinberg says the Redwood City, Calif., company will function as a stand-alone corporation.

HONEYWELL BULL UNVEILS PRODUCTS

A week after Honeywell Inc. sold 57.5% of its computer business, Honeywell Information Systems, to Compagnie des Machines Bull of France and NEC Corp. of Japan, the new company—Honeywell Bull, of Minneapolis—announced its first new products. A new line of high-end mainframes, the DPS 7000 Series, replaces the current DPS7 line. The five new models, designed and built by Bull, use Honeywell 22,000-gate CMOS chips. The sale of Honeywell Information Systems represents what Edson Spencer, Honeywell's chief executive officer, says is his company's "last major step in restructuring." Honeywell, Bull, and NEC jointly manage Honeywell Bull.

ROBOT ASSISTS BRAIN SURGEON

Being demonstrated at this month's Robots 11 show in Chicago is a Westinghouse Unimate Puma 200 robot that assists a neurosurgeon performing simulated brain surgery. In the operation, the robot replaces part of the stereotactic head frame used in conventional neurosurgery to position surgical probes for insertion into the brain. The robot can position a probe to within 0.1 mm accuracy at the desired trajectory to hit an intracranial target, based on computerized tomographic scanning data. The probe is then inserted manually by the surgeon. The technique, de-

veloped at Long Beach Memorial Hospital in California, has been used on 24 patients during the past year.

VLSI TECHNOLOGY SIGNS SCHWEBER

VLSI Technology Inc. has signed Schweber Electronics, the third largest U.S. electronics distributor, to handle its memory and ASIC-derived standard products in Minneapolis, Baltimore, and San Jose and Irvine in California. Schweber distributes rival LSI Logic Inc. parts in Boston, New York, and Atlanta. VLSI Technology retains Aero Electronics, the second largest distributor, in San Jose and in Fairfield, N. J.

SEMICONDUCTOR RESEARCH IN SPACE

Rockwell International has signed an agreement to perform experiments with semiconductor materials in space aboard one of the National Aeronautics and Space Administration's space shuttles. The experiments are planned to begin in February 1988. Rockwell researchers will use the floating-zone crystal-growth process on indium and selenium, and NASA scientists will investigate polymer materials. Both experiments aim at developing structural integrities that can't be achieved on earth because of gravity.

GaAs MARKET TO BE \$4.4 BILLION IN 1991

The worldwide market for gallium arsenide semiconductors will be \$4.4 billion in 1991, says San Jose, Calif., market researcher Dataquest Inc. That's nearly triple the \$1.8 billion recorded in 1984. Dataquest pins the growth on the fact that GaAs devices are moving out of the lab and into commercial applications, notably fiber-optic and satellite communications, supercomputing, and electronic test and measurement.

It's hard to compete when you have no competition.

When we looked for a single-chip modem system to compare to our Surelink™ family, we couldn't find one. Simply because nothing else comes close.

We realize this may sound a bit boastful. But we have every reason to be.

According to TeleQuality Associates' Modem Performance Analysis, the Fairchild μ A212AT has the best performance of any single-chip modem IC in existence, and better performance than the leading 2-chip sets.

When they tested us against Gould/AMI, SSI, Sierra, Rockwell, and a handful of others, only our modem performed completely without fault. And scored the

group's lowest BER (Bit Error Rate). Maybe that's why we're the largest supplier of single-chip modems. With over 80 design wins and parts available right now. In quantity.

The Surelink family includes the Bell 212A-compatible μ A212AT, and the CCITT V.22-compliant μ AV22. Both offering 1200 bps, on-chip tone-dialers, and the lowest power consumption of any modem chip or chip set – just 35 mW. And since Surelink is a constantly growing family, we offer an evolutionary migration path for the future. Along with comprehensive design aids and support.

For a copy of the Surelink Informa-

tion Package, call The Fairchild Customer Information Center at 1-800-554-4443.

We'd also like to suggest comparing us to the competition. But there doesn't seem to be any.


©1987 Fairchild Semiconductor Corporation. Surelink is a trademark of Fairchild Semiconductor Corporation. *Reprinted with the permission of TeleQuality Associates.

We're taking the high ground.

FAIRCHILD

A Schlumberger Company

SURELINK
SINGLE-CHIP MODEMS



Circle 901 on reader service card

STERRA
GOULD/AMI



DISCRETE SOLUTIONS
SSI

ROCKWELL

PLEASE FILE

I-800-361-4903

**MATROX IS ABOUT TO
DRAMATICALLY CHANGE YOUR VIEW OF
IMAGING AND MACHINE VISION ON THE IBM AT.**



If you think that serious imaging and PCs are light years apart – but wish they weren't – we present the following facts:

MVP-AT

- Real-Time Processing – Convolutions, Histograms, Profiles, Feature Extraction, Area of Interest, Much, Much More
- True Color ▪ Graphics Overlay
- EGA Video Switch ▪ Non-Interlaced Display
- Complete Software Library
- Image Pro Driver

MVP-AT

- Powerful Processing
- Unlimited Applications
- \$4995

CALL US.



matrox

IBM and IBM AT are trademarks of International Business Machines Corporation. ELEC-MVP
In Canada, call (514) 685-2630.

Circle 902 on reader service card

See us at Booth 315 **ELECTRONIC IMAGING 87**